

LIBERIA
CIVIL AVIATION REGULATIONS





PART 13.1

AERODROMES
(AIRPORT DESIGN AND OPERATION STANDARDS)

EDITION 1.0

July 2021





PUBLISHED BY AUTHORITY

VOL. XXI WEDNESDAY, AUGUST 11, 2021 NO. 46

EXTRAORDINARY

The Government of the Republic of Liberia announces that the Liberia Civil Aviation Authority, pursuant to its mandate under the Liberia Civil Aviation Act of 2019, and specifically consistent with Subchapter XII, Section 1218 (1), has issued on August 11, 2021 its Regulation N0. LCAA/LCAR/001/2021, herein under:

CONCERNING LIBERIA CIVIL AVIATION REGULATIONS

BY ORDER OF THE PRESIDENT

**AMB. DEE-MAXWELL SAAH KEMAYAH, SR.
MINISTER OF FOREIGN AFFAIRS**

**MINISTRY OF FOREIGN AFFAIRS
MONROVIA, LIBERIA**



AUTHORITY TO PROMULGATE CIVIL AVIATION REGULATIONS

**IN EXERCISE OF THE POWERS CONFERRED ON THE DIRECTOR GENERAL OF
LIBERIA CIVIL AVIATION AUTHORITY UNDER THE LIBERIA CIVIL AVIATION
ACT OF 2019 THESE REGULATIONS ARE MADE.**

DATE: 13th July 2021



**SIGNATURE: _____
Hon. Moses Y. Kollie
DIRECTOR GENERAL**

THIS PAGE INTENTIONALLY LEFT BLANK

Introduction

This regulation contains provisions that prescribe the physical characteristics and obstacle limitation surfaces to be provided for at aerodromes, and certain facilities and technical services normally provided at an aerodrome. It also contains specifications dealing with obstacles outside those limitation surfaces. It is not intended that these specifications limit or regulate the operation of an aircraft.

To a great extent, the specifications for individual facilities detailed in this regulation, have been interrelated by a reference code system, described in this chapter, and by the designation of the type of runway for which they are to be provided, as specified in the definitions. This not only simplifies the reading of this regulation, but in most cases, provides for efficiently proportioned aerodromes when the specifications are followed.

This regulation sets forth the minimum aerodrome specifications for aircraft which have the characteristics of those which are currently operating or for similar aircraft that are planned for introduction. Accordingly, any additional safeguards that might be considered appropriate to provide for more demanding aircraft are not taken into account. Such matters are left to appropriate authorities to evaluate and take into account as necessary for each particular aerodrome. Provisions for the accommodation of more demanding aircraft at existing aerodromes can be found in the PANS-Aerodromes (Doc 9981). Guidance on some possible effects of future aircraft on these specifications is given in the Aerodrome Design Manual (Doc 9157), Part 2.

It is to be noted that the specifications for precision approach runway categories II and III are only applicable to runways intended to be used by aeroplanes in code numbers 3 and 4.

this regulation does not include specifications relating to the overall planning of aerodromes (such as separation between adjacent aerodromes or capacity of individual aerodromes), impact on the environment, or to economic and other non-technical factors that need to be considered in the development of an aerodrome.

Aviation security is an integral part of aerodrome planning and operations. This regulation contains several specifications aimed at enhancing the level of security at aerodromes. Specifications on other facilities related to security are given in Annex 17 — Security and detailed guidance on the subject is contained in the ICAO's Aviation Security Manual.

Table of Contents

AMENDMENTS	4
Introduction	5
13.1 DESIGN AND OPERATION OF AERODROMES	10
13.1.1 GENERAL	10
13.1.1.1 Applicability.....	10
13.1.1.2 Definitions.....	10
13.1.1.3 Abbreviations and Symbols.....	21
13.1.1.4 Common reference system.....	24
13.1.1.5 Certification of aerodromes.....	24
13.1.1.6 Airport Design. (<i>Applicable until 2 November 2022</i>).....	25
(13.1.1.6) Airport Design and Master Plan (<i>Applicable as of 3 november 2022</i>).....	25
13.1.1.7 Aerodrome Reference Code.....	26
13.1.1.8 Specific Procedures for Aerodrome Operations.....	27
13.1.2 AERODROME DATA	29
13.1.2.1 Aeronautical data.....	29
13.1.2.2 Aerodrome Reference Point.....	29
13.1.2.3 Aerodrome and Runway Elevations.....	29
13.1.2.4 Aerodrome Reference Temperature.....	30
13.1.2.5 Aerodrome Dimensions and Related Information.....	30
13.1.2.6 Strength of pavements. (<i>Applicable until 27 November 2024</i>).....	31
13.1.2.6.1 Strength of pavements. (<i>Applicable as of November 2024</i>).....	33
13.1.2.7 Pre-Flight Altimeter Check Location.....	36
13.1.2.8 Declared Distances.....	36
13.1.2.9 Condition of the Movement Area and Related Facilities.....	37
13.1.2.10 Water on a Runway (<i>Applicable until 4 November 2020</i>).....	38
13.1.2.11 Disabled Aircraft Removal.....	40
13.1.2.12 Rescue and Firefighting.....	40
13.1.2.13 Visual Approach Slope Indicator Systems.....	40
13.1.2.14 Coordination between Aeronautical Information Services and Aerodrome Operator.....	41
13.1.3 PHYSICAL CHARACTERISTICS	43
13.1.3.1 Runways.....	43
13.1.3.2 Runway Shoulders.....	49
13.1.3.3 Runway Turn Pads.....	50
13.1.3.4 Runway Strips.....	52
13.1.3.5 Runway End Safety Areas.....	56
13.1.3.6 Clearways.....	58
13.1.3.7 Stopways.....	59
13.1.3.8 Radio Altimeter Operating Area.....	59
13.1.3.9 Taxiways.....	60
13.1.3.10 Taxiway Shoulders.....	65
13.1.3.11 Taxiway Strips.....	66
13.1.3.12 Holding Bays, Runway-Holding Positions, Intermediate Holding Positions And Road-Holding Positions.....	67
13.1.3.13 Aprons.....	69
13.1.3.14 Isolated Aircraft Parking Position.....	70
13.1.4 OBSTACLE RESTRICTION AND REMOVAL	71
13.1.4.1 Obstacle Limitation Surfaces.....	71
13.1.4.2 Obstacle Limitation Requirements.....	76
13.1.4.3 Objects Outside The Obstacle Limitation Surfaces.....	83
13.1.4.4 Other Objects.....	83
13.1.4.5 Shielding Principles.....	84
13.1.5 VISUAL AIDS FOR NAVIGATION	86
13.1.5.1 Indicators and Signaling Devices.....	86
13.1.5.2 Markings.....	88
13.1.5.3 Lights.....	109
13.1.5.4 Signs.....	169
13.1.5.5 Markers.....	181
13.1.6 VISUAL AIDS FOR DENOTING OBSTACLES	185

13.1.6.1	Objects To Be Marked and/or Lighted.....	185
13.1.6.2	Marking And Lighting Of Objects.....	187
13.1.7	VISUAL AIDS FOR DENOTING RESTRICTED USE AREAS	201
13.1.7.1	Closed Runways And Taxiways, or Parts Thereof.....	201
13.1.7.2	Non-Load-Bearing Surfaces.....	202
13.1.7.3	Pre-Threshold Area.....	203
13.1.7.4	Unserviceable Areas.....	203
13.1.8	ELECTRICAL SYSTEMS	205
13.1.8.1	Electrical Power Supply Systems For Air Navigation Facilities.....	205
13.1.8.2	System Design.....	208
13.1.8.3	Monitoring.....	208
13.1.9	AERODROME OPERATIONAL SERVICES, EQUIPMENT AND INSTALLATIONS	210
13.1.9.1	Aerodrome Emergency Planning.....	210
13.1.9.2	Rescue and Firefighting.....	212
13.1.9.3	Disabled Aircraft Removal.....	219
13.1.9.4	Wildlife Strike Hazard Reduction.....	219
13.1.9.5	Apron Management Service.....	220
13.1.9.6	Ground Servicing Of Aircraft.....	221
13.1.9.7	Aerodrome Vehicle Operations.....	221
13.1.9.8	Surface Movement Guidance and Control Systems.....	222
13.1.9.9	Siting Of Equipment and Installations On Operational Areas.....	223
13.1.9.10	Fencing.....	225
13.1.9.11	Security Lighting.....	225
13.1.9.12	Autonomous Runway Incursion Warning System.....	225
13.1.10	AERODROME MAINTENANCE	227
13.1.10.1	General.....	227
13.1.10.2	Pavements.....	227
13.1.10.3	Removal of Contaminants.....	228
13.1.10.4	Runway Pavement Overlays.....	229
13.1.10.5	Visual Aids.....	229
APPENDIX 1: COLORS FOR AERONAUTICAL GROUND LIGHTS, MARKINGS, SIGNS AND PANELS		232
APPENDIX 2: AERONAUTICAL GROUND LIGHT CHARACTERISTICS.....		244
APPENDIX 3: MANDATORY INSTRUCTION MARKINGS AND INFORMATION MARKINGS		271
APPENDIX 5: LOCATION OF LIGHTS ON OBSTACLES.....		288

THIS PAGE INTENTIONALLY LEFT BLANK

13.1: AERODROMES (AIRPORT DESIGN AND OPERATION STANDARDS)

13.1 DESIGN AND OPERATION OF AERODROMES

13.1.1 GENERAL

13.1.1.1 Applicability

- (a) These Regulations shall apply to all aerodromes open to public use as well as to airports subjected to changes approved by LCAA.
- (b) The specifications contained in this Regulation, shall apply to all aerodromes open to public use in accordance with the requirements of Article 15 of the Chicago Convention.
- (c) The specifications of section 13.1.3, shall apply only to land aerodromes.
- (d) The specifications in this regulation shall apply, where appropriate, to heliports but shall not apply to stolports.

13.1.1.2 Definitions

- (a) When the following terms are used in these Regulations they have the following meanings:
 - (1) **Aerodrome.** A defined area on land or water (including any buildings, installations and equipment) intended to be used either wholly or in part for the arrival, departure and surface movement of aircraft
 - (2) **Aerodrome beacon.** Aeronautical beacon used to indicate the location of an aerodrome from the air.
 - (3) **Aerodrome certificate.** A certificate issued by the authority under applicable regulations for the operation of an aerodrome.
 - (4) **Aerodrome elevation.** The elevation of the highest point of the landing area.
 - (5) **Aerodrome identification sign.** A sign placed on an aerodrome to aid in identifying the aerodrome from the air.
 - (6) **Aerodrome mapping data (AMD).** Data collected for the purpose of compiling aerodrome mapping information for aeronautical uses.

Note. — Aerodrome mapping data are collected for purposes that include the improvement of the user's situational awareness, surface navigation operations, training, charting and planning.
 - (7) **Aerodrome mapping database (AMDB).** A collection of aerodrome mapping data organized and arranged as a structured data set.
 - (8) **Aerodrome reference point.** The designated geographical location of an aerodrome.
 - (9) **Aerodrome traffic density:**
 - (i) *Light.* Where the number of movements in the mean busy hour is not greater than 15 per runway typically, less than 20 total aerodrome movements.

- (ii) *Medium*. Where the number of movements in the mean busy hour is of the order of 16 to 25 per runway or typically between 20 to 35 total aerodrome movements.
- (iii) *Heavy*. Where the number of movements in the mean busy hour is of the order of 26 or more per runway or typically more than 35 total aerodrome movements.

Note 1. — The number of movements in the mean busy hour is the arithmetic mean over the year of the number of movements in the daily busiest hour.

Note 2. — Either a take-off or a landing constitutes a movement.

- (10) **Aeronautical beacon**. An aeronautical ground light visible at all azimuths, either continuously or intermittently, to designate a particular point on the surface of the earth.
- (11) **Aeronautical ground light**. Any light specially provided as an aid to air navigation, other than a light displayed on an aircraft.
- (12) **Aeroplane reference field length**. The minimum field length required for take-off at maximum certificated take-off mass, sea level, standard atmospheric conditions, still air and zero runway slope, as shown in the appropriate aeroplane flight manual prescribed by the certifying authority or equivalent data from the aeroplane manufacturer. Field length means balanced field length for aeroplanes, if applicable, or take-off distance in other cases.
Note. — Attachment A, Section 2, provides information on the concept of balanced field length and the Airworthiness Manual (Doc 9760) contains detailed guidance on matters related to take-off distance.
- (13) **Aircraft classification number (ACN*)**. A number expressing the relative effect of an aircraft on a pavement for a specified standard subgrade category. (* Applicable until 27 November 2024)
- (14) **Aircraft classification rating (ACR**)**. A number expressing the relative effect of an aircraft on a pavement for a specified standard subgrade category. (** Applicable as of 28 November 2024)

Note. — The aircraft classification number is calculated with respect to the center of gravity (CG) position which yields the critical loading on the critical gear. Normally the aftmost CG position appropriate to the maximum gross apron (ramp) mass is used to calculate the ACN. In exceptional cases the forward most CG position may result in the nose gear loading being more critical.

- (15) **Aircraft stand**. A designated area on an apron intended to be used for parking an aircraft.
- (16) **Apron**. A defined area, on a land aerodrome, intended to accommodate aircraft for purposes of loading or unloading passengers, mail or cargo, fuelling, parking or maintenance.
- (17) **Apron management service**. A service provided to regulate the activities and the movement of aircraft and vehicles on an apron.

- (18) **Arresting system.** A system designed to decelerate an aeroplane overrunning the runway.
- (19) **Autonomous runway incursion warning system (ARIWS).** A system which provides autonomous detection of a potential incursion or of the occupancy of an active runway and a direct warning to a flight crew or a vehicle operator.
- (20) **Authority** The civil aviation authority responsible for the oversight of civil aviation in Liberia (Liberia Civil Aviation Authority)
- (21) **Balked landing.** A landing maneuver that is unexpectedly discontinued at any point below the obstacle clearance altitude or height (OCA/H).
- (22) **Barrette.** Three or more aeronautical ground lights closely spaced in a transverse line so that from a distance they appear as a short bar of light.
- (23) **Calendar.** Discrete temporal reference system that provides the basis for defining temporal position to a resolution of one day (ISO 19108*).
- (24) **Certified aerodrome.** An aerodrome whose operator has been granted an aerodrome certificate.
- (25) **Clearway.** A defined rectangular area on the ground or water under the control of the appropriate authority, selected or prepared as a suitable area over which an aeroplane may make a portion of its initial climb to a specified height.
- (26) **Cyclic redundancy check (CRC).** A mathematical algorithm applied to the digital expression of data that provides a level of assurance against loss or alteration of data.
- (27) **Data accuracy.** A degree of conformance between the estimated or measured value and the true value.
- (28) **Data Integrity (assurance level).** A degree of assurance that an aeronautical data and its value has not been lost nor altered since the origination or authorized amendment.
- (29) **Data quality.** A degree or level of confidence that the data provided meet the requirements of the data user in terms of accuracy, resolution and integrity (or equivalent assurance level) traceability, timeliness, completeness and format.
* ISO Standard 19108, Geographic information — Temporal schema
- (30) **Datum.** Any quantity or set of quantities that may serve as a reference or basis for the calculation of other quantities (ISO 19104**).
- (31) **De-icing/anti-icing pad.** An area comprising an inner area for the parking of an aeroplane to receive de-icing/anti-icing treatment and an outer area for the maneuvering of two or more mobile de-icing/anti-icing equipment.
- (32) **Declared distances.**
- (i) **Take-off run available (TORA).** The length of runway declared available and suitable for the ground run of an aeroplane taking off.
 - (ii) **Take-off distance available (TODA).** The length of the take-off run available plus the length of the clearway, if provided.

- (iii) **Accelerate-stop distance available (ASDA).** The length of the take-off run available plus the length of the stopway, if provided.
- (iv) **Landing distance available (LDA).** The length of runway which is declared available and suitable for the ground run of an aeroplane landing.
- (33) **Dependent parallel approaches.** Simultaneous approaches to parallel or near-parallel instrument runways where radar separation minima between aircraft on adjacent extended runway center lines are prescribed.
- (34) **Displaced threshold.** A threshold not located at the extremity of a runway
- (35) **Effective intensity.** The effective intensity of a flashing light is equal to the intensity of a fixed light of the same color which will produce the same visual range under identical conditions of observation.
- (36) **Ellipsoid height (Geodetic height).** The height related to the reference ellipsoid, measured along the ellipsoidal outer normal through the point in question.
- (37) **Fixed light.** A light having constant luminous intensity when observed from a fixed point.
- (38) **Foreign object debris (FOD).** An inanimate object within the movement area which has no operational or aeronautical function and which has the potential to be a hazard to aircraft operations.
- (39) **Frangible object.** An object of low mass designed to break, distort or yield on impact so as to present the minimum hazard to aircraft.

Note. — Guidance on design for frangibility is contained in the *Aerodrome Design Manual (Doc 9157)*, Part 6.

- (40) **Geodetic datum.** A minimum set of parameters required to define location and orientation of the local reference system with respect to the global reference system/frame.

** ISO Standard 19104, Geographic information — Terminology

- (41) **Geoid.** The equipotential surface in the gravity field of the Earth which coincides with the undisturbed mean sea level (MSL) extended continuously through the continents.

Note. — The geoid is irregular in shape because of local gravitational disturbances (wind tides, salinity, current, etc.) and the direction of gravity is perpendicular to the geoid at every point.

- (42) **Geoid undulation.** The distance of the geoid above (positive) or below (negative) the mathematical reference ellipsoid.

Note. — The World Geodetic System — 1984 (WGS-84) defined ellipsoid, the difference between the WGS-84 ellipsoidal height and orthometric height represents WGS-84 geoid undulation.

- (43) **Gregorian calendar.** Calendar in general use; first introduced in 1582 to define a year that more closely approximates the tropical year than the Julian calendar (ISO 19108***).

Note. — In the Gregorian calendar, common years have 365 days and leap years 366 days divided into twelve sequential months.

- (44) **Hazard beacon.** An aeronautical beacon used to designate a danger to air navigation.
- (45) **Heliport.** An aerodrome or a defined area on a structure intended to be used wholly or in part for the arrival, departure and surface movement of helicopters.
- (46) **Holding bay.** A defined area where aircraft can be held, or bypassed, to facilitate efficient surface movement of aircraft
- (47) **Holdover time.** The estimated time the anti-icing fluid (treatment) will prevent the formation of ice and frost and the accumulation of snow on the protected (treated) surfaces of an aeroplane.
- (48) **Hot spot.** A location on an aerodrome movement area with a history or potential risk of collision or runway incursion, and where heightened attention by pilots or drivers is necessary.
- (49) **Human Factors principles.** Principles which apply to aeronautical design, certification, training, operations and maintenance and which seek safe interface between the human and other system components by proper consideration to human performance.
- (50) **Human performance.** Human capabilities and limitations which have an impact on the safety and efficiency of aeronautical operations.
- (51) **Identification beacon.** An aeronautical beacon emitting a coded signal by means of which a particular point of reference can be identified.
- (52) **Independent parallel approaches.** Simultaneous approaches to parallel or near-parallel instrument runways where radar separation minima between aircraft on adjacent extended runway center lines are not prescribed.
- (53) **Independent parallel departures.** Simultaneous departures from parallel or near-parallel instrument runways.
- (54) **Instrument runway.** One of the following types of runways intended for the operation of aircraft using instrument approach procedures:
 - (i) *Non-precision approach runway.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type A and a visibility not less than 1 000 m.*** ISO Standard 19108, Geographic information — Temporal schema
 - (ii) *Precision approach runway, category I.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type B with a decision height (DH) not lower than 60 m (200 ft) and either a visibility not less than 800 m or a runway visual range not less than 550 m.
 - (iii) *Precision approach runway, category II.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type B with a decision height (DH) lower than 60 m (200 ft) but not lower than 30 m (100 ft) and a runway visual range not less than 300 m.

- (iv) *Precision approach runway, category III.* A runway served by visual aids and non-visual aid(s) intended for landing operations following an instrument approach operation type B :
- with a decision height (DH) lower than 30 m (100ft), or no decision height and a runway visual range less than 300m.
 - no runway visual range limitations

Note 1. — Visual aids need not necessarily be matched to the scale of non-visual aids provided. The criterion for the selection of visual aids is the conditions in which operations are intended to be conducted.

Note 2. — Refer to Annex 6 — Operation of Aircraft for instrument approach operation types.

- (55) **Integrity classification (aeronautical data).** Classification based upon the potential risk resulting from the use of corrupted data. Aeronautical data is classified as:
- (i) *routine data:* there is a very low probability when using corrupted routine data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe;
 - (ii) *essential data:* there is a low probability when using corrupted essential data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe; and
 - (iii) *critical data:* there is a high probability when using corrupted critical data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe.
- (56) **Intermediate holding position.** A designated position intended for traffic control at which taxiing aircraft and vehicles shall stop and hold until further cleared to proceed, when so instructed by the aerodrome control tower.
- (57) **Landing area.** That part of a movement area intended for the landing or take-off of aircraft.
- (58) **Landing direction indicator.** A device to indicate visually the direction currently designated for landing and for take-off.
- (59) **Laser-beam critical flight zone (LCFZ).** Airspace in the proximity of an aerodrome but beyond the LFFZ where the irradiance is restricted to a level unlikely to cause glare effects.
- (60) **Laser-beam free flight zone (LFFZ).** Airspace in the immediate proximity of the aerodrome where the irradiance is restricted to a level unlikely to cause any visual disruption.
- (61) **Laser-beam sensitive flight zone (LSFZ).** Airspace outside, and not necessarily contiguous with, the LFFZ and LCFZ where the irradiance is restricted to a level unlikely to cause flash-blindness or after-image effects.
- (62) **Lighting system reliability.** The probability that the complete installation operates within the specified tolerances and that the system is operationally usable.

- (63) **Manoeuvring area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.
- (64) **Marker.** An object displayed above ground level in order to indicate an obstacle or delineate a boundary.
- (65) **Marking.** A symbol or group of symbols displayed on the surface of the movement area in order to convey aeronautical information.
- (66) **Movement area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the maneuvering area and the apron(s).
- (67) **Near-parallel runways.** Non-intersecting runways whose extended center lines have an angle of convergence or divergence of 15 degrees or less.
- (68) **Non-instrument runway.** A runway intended for the operation of aircraft using visual approach procedures or an instrument approach procedure to a point beyond which the approach may continue in visual meteorological conditions.
- Note. — Visual meteorological conditions (VMC) are described in Chapter 3 of Annex 2 — Rules of the Air.*
- (69) **Normal flight zone (NFZ).** Airspace not defined as LFFZ, LCFZ or LSFZ but which must be protected from laser radiation capable of causing biological damage to the eye.
- (70) **Obstacle.** All fixed (whether temporary or permanent) and mobile objects, or parts thereof, that:
- (i) are located on an area intended for the surface movement of aircraft; or
 - (ii) extend above a defined surface intended to protect aircraft in flight; or
 - (iii) stand outside those defined surfaces and that have been assessed as being a hazard to air navigation.
- (71) **Obstacle free zone (OFZ).** The airspace above the inner approach surface, inner transitional surfaces, and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than a low-mass and frangibly mounted one required for air navigation purposes.
- (72) **Outer Main Gear Wheel Span (OMGWS)** The distance between the outside edges of the main gear wheels.
- (73) **Orthometric height.** Height of a point related to the geoid, generally presented as an MSL elevation.
- (74) **Pavement classification number (PCN*).** A number expressing the bearing strength of a pavement for unrestricted operations. (* Applicable until 27 November 2024)
- (75) **Pavement classification number (PCN**).** A number expressing the bearing strength of a pavement for unrestricted operations. (** Applicable until 28 November 2024)

- (76) **Precision approach runway**, see **Instrument runway**.
- (77) **Primary runway(s)**. Runway(s) used in preference to others whenever conditions permit.
- (78) **Protected flight zones**. Airspace specifically designated to mitigate the hazardous effects of laser radiation.
- (79) **Road**. An established surface route on the movement area meant for the exclusive use of vehicles.
- (80) **Road-holding position**. A designated position at which vehicles may be required to hold.
- (81) **Runway**. A defined rectangular area on a land aerodrome prepared for the landing and take-off of aircraft.
- (82) **Runway condition assessment matrix (RCAM)**. A matrix allowing the assessment of the runway condition code, using associated procedures, from a set of observed runway surface condition(s) and pilot report of braking action
- (83) **Runway condition code (RWYCC)**. A number describing the runway surface condition to be used in the runway condition report.

Note.— The purpose of the runway condition code is to permit an operational aeroplane performance calculation by the flight crew. Procedures for the determination of the runway condition code are described in the PANS-Aerodromes (Doc 9981).

- (84) **Runway condition report (RCR)**. A comprehensive standardized report relating to runway surface condition(s) and its effect on the aeroplane landing and take-off performance.
- (85) **Runway end safety area (RESA)**. An area symmetrical about the extended runway center line and adjacent to the end of the strip primarily intended to reduce the risk of damage to an aeroplane undershooting or overrunning the runway.
- (86) **Runway guard lights**. A light system intended to caution pilots or vehicle drivers that they are about to enter an active runway.
- (87) **Runway-holding position**. A designated position intended to protect a runway, an obstacle limitation surface, or an ILS/MLS critical/sensitive area at which taxiing aircraft and vehicles shall stop and hold, unless otherwise authorized by the aerodrome control tower.

Note. — In radiotelephony phraseologies, the expression “holding point” is used to designate the runway-holding position.

- (88) **Runway strip**. A defined area including the runway and stopway, if provided, intended:
- (i) to reduce the risk of damage to aircraft running off a runway; and
 - (ii) to protect aircraft flying over it during take-off or landing operations.

- (89) **Runway surface condition(s)** A description of the condition(s) of the runway surface used in the runway condition report which establishes the basis for the determination of the runway condition code for aeroplane performance purposes.

Note 1.— The runway surface conditions used in the runway condition report establish the performance requirements between the aerodrome operator, aeroplane manufacturer and aeroplane operator.

Note 2.— Aircraft de-icing chemicals and other contaminants are also reported but are not included in the list of runway surface condition descriptors because their effect on runway surface friction characteristics and the runway condition code cannot be evaluated in a standardized manner.

Note 3.— Procedures on determining runway surface conditions are available in the PANS-Aerodromes (Doc 9981).

- (iii) *Dry runway.* A runway is considered dry if its surface is free of visible moisture and not contaminated within the area intended to be used.
- (iv) *Wet runway.* The runway surface is covered by any visible dampness or water up to and including 3 mm deep within the intended area of use.
- (v) *Slippery wet runway.* A wet runway where the surface friction characteristics of a significant portion of the runway have been determined to be degraded.
- (vi) *Contaminated runway.* A runway is contaminated when a significant portion of the runway surface area (whether in isolated areas or not) within the length and width being used is covered by one or more of the substances listed in the runway surface condition descriptors.

Note.— Procedures on determination of contaminant coverage on runway are available in the PANS-Aerodromes (Doc 9981).

- (vii) *Standing water.* Water of depth greater than 3 mm.

Note.— The descriptions for (vii) (a) to (h) are used solely in the context of the runway condition report and are not intended to supersede or replace any existing WMO definitions.

Note.— Running water of depth greater than 3 mm is reported as standing water by convention.

- (90) **Runway turn pad.** A defined area on a land aerodrome adjacent to a runway for the purpose of completing a 180-degree turn on runway.
- (91) **Runway visual range (RVR).** The range over which the pilot of an aircraft on the center line of a runway can see the runway surface markings or the lights delineating the runway or identifying its centerline.
- (92) **Safety management system (SMS).** A systematic approach to managing safety including the necessary organizational structure, accountabilities, policies and procedures.
- (93) **Segregated parallel operations.** Simultaneous operations on parallel or near-parallel instrument runways in which one runway is used exclusively for approaches and the other runway is used exclusively for departures.

- (94) **Shoulder.** An area adjacent to the edge of a pavement so prepared as to provide a transition between the pavement and the adjacent surface.
- (95) **Sign.**
- (i) *Fixed message sign.* A sign presenting only one message.
 - (ii) *Variable message sign.* A sign capable of presenting several predetermined messages or no message, as applicable.
- (96) **Signal area.** An area on an aerodrome used for the display of ground signals.
- (97) **Station declination.** An alignment variation between the zero-degree radial of a VOR and true north, determined at the time the VOR station is calibrated.
- (98) **Stopway.** A defined rectangular area on the ground at the end of take-off run available prepared as a suitable area in which an aircraft can be stopped in the case of an abandoned take-off.
- (99) **Switch-over time (light).** The time required for the actual intensity of a light measured in a given direction to fall from 50 per cent and recover to 50 per cent during a power supply changeover, when the light is being operated at intensities of 25 per cent or above.
- (100) **Take-off runway.** A runway intended for take-off only.
- (101) **Taxiway.** A defined path on a land aerodrome established for the taxiing of aircraft and intended to provide a link between one part of the aerodrome and another, including:
- (i) **Aircraft stand taxilane.** A portion of an apron designated as a taxiway and intended to provide access to aircraft stands only.
 - (ii) **Apron taxiway.** A portion of a taxiway system located on an apron and intended to provide a through taxi-route across the apron.
 - (iii) **Rapid exit taxiway.** A taxiway connected to a runway at an acute angle and designed to allow landing aeroplanes to turn off at higher speeds than are achieved on other exit taxiways thereby minimizing runway occupancy times.
- (102) **Taxiway intersection.** A junction of two or more taxiways.
- (103) **Taxiway strip.** An area including a taxiway intended to protect an aircraft operating on the taxiway and to reduce the risk of damage to an aircraft accidentally running off the taxiway.
- (104) **Threshold.** The beginning of that portion of the runway usable for landing.
- (105) **Touchdown zone.** The portion of a runway, beyond the threshold, where it is intended landing aeroplanes first contact the runway.
- (106) **Usability factor.** The percentage of time during which the use of a runway or system of runways is not restricted because of the crosswind component.

Note — Wherever a color is referred to in this regulation, the specifications for that color given in Appendix 1 shall apply

Note. — Crosswind component means the surface wind component at right angles to the runway center line.

13.1.1.3 Abbreviations and Symbols

Abbreviations

ACN	Aircraft classification number
ACN*	Aircraft classification number.* (Applicable until 27 November 2024)
ACR**	Aircraft classification rating (**Applicable as of 28 November 2024)
ADP	Airside drivers permit
AIP	Aeronautical information publication
APAPI	Abbreviated precision approach path indicator
aprx	Approximately
ARIWS	Autonomous runway incursion warning system
ASDA	Accelerate-stop distance available
ATS	Air traffic services
AT-VASIS	Abbreviated T visual approach slope indicator system
C	Degree Celsius
CBR	California bearing ratio
cd	Candela
CIE	Commission Internationale de l'Éclairage
CRC	Cyclic redundancy check
DME	Distance measuring equipment
E	Modulus of elasticity
FOD	Foreign object debris
ft	Foot
ILS	Instrument landing system
IMC	Instrument meteorological conditions
K	Degree Kelvin
kg	Kilogram
km	Kilometer
km/h	Kilometer per hour
kt	Knot
L	Liter
LCAA	Liberia Civil Aviation Authority
LCAR	Liberia Civil Aviation Regulations

LCFZ	Laser-beam critical flight zone
LDA	Landing distance available
LFFZ	Laser-beam free flight zone
LSFZ	Laser-beam sensitive flight zone
m	Meter
max	Maximum
MLS	Microwave landing system
mm	Millimeter
mnm	Minimum
MN	Mega newton
MPa	Mega pascal
MSL	Mean sea level
NFZ	Normal flight zone
NM	Nautical mile
NU	Not usable
OCA/H	Obstacle clearance altitude/height
OFZ	Obstacle free zone
OLS	Obstacle limitation surface
OMGWS	Outer main gear wheel span
PAPI	Precision approach path indicator
PCN*	Pavement classification number (* Applicable until 27 November 2024)
PCR**	Pavement classification rating (**Applicable as of 28 November 2024)
PLR	Pavement load rating
RCR	Runway condition report
RESA	Runway end safety area
RILS	Runway identification lights
RSC	Runway surface condition
RFFS	Rescue and firefighting service
RVR	Runway visual range
S	South
secs	Seconds
SIRO	Simultaneous intersecting runway operations

SMS	Safety management system
T	True
TDZ	Touchdown zone
TDZE	Touchdown zone elevation
TDZL	Touchdown zone lighting
TODA	Take-off distance available
TORA	Take-off run available
T-VASIS	visual approach slope indicator system
VFR	Visual flight rules
VMC	Visual meteorological conditions
VOR	Very high frequency omnidirectional radio range
WHMP	Wildlife hazard management program
WIP	Work in progress
W	West

Symbols

°	Degree
=	Equals
'	Minute of arc
μ	Friction coefficient
>	Greater than
<	Less than
%	Percentage
±	Plus or minus

13.1.1.4 Common reference system

- (a) **Horizontal reference system:** World Geodetic System — 1984 (WGS-84) shall be used as the horizontal (geodetic) reference system. Reported aeronautical geographical coordinates (indicating latitude and longitude) shall be expressed in terms of the WGS-84 geodetic reference datum.

Note.— Comprehensive guidance material concerning WGS-84 is contained in the World Geodetic System — 1984 (WGS-84) Manual (Doc 9674).

- (b) **Vertical reference system:** Mean sea level (MSL) datum, which gives the relationship of gravity-related height (elevation) to a surface known as the geoid, shall be used as the vertical reference system.

Note 1.— The geoid globally most closely approximates MSL. It is defined as the equipotential surface in the gravity field of the Earth which coincides with the undisturbed MSL extended continuously through the continents.

Note 2.— Gravity-related heights (elevations) are also referred to as orthometric heights while distances of points above the ellipsoid are referred to as ellipsoidal heights.

- (c) **Temporal reference system**

- (1) The Gregorian calendar and Coordinated Universal Time (UTC) shall be used as the temporal reference system.
- (2) When a different temporal reference system is used, this shall be indicated in GEN 2.1.2 of the Robert Flight Information Region (RFIR) Aeronautical Information Publication (AIP).

Note.— See PANS-AIM (Doc 10066), Appendix 2.

13.1.1.5 Certification of aerodromes

- (a) No person shall operate an aerodrome for international operations without having been certified in accordance with the specifications contained in this Part, Annex 14, Volume I as well as other relevant ICAO specifications as may be specified through an appropriate regulatory framework.

Note.— Specific procedures on the stages of certifying an aerodrome are given in the PANS-Aerodromes (Doc 9981). Further guidance on aerodrome certification can be found in the Manual on Certification of Aerodromes (Doc 9774).

- (b) The regulatory framework for certification of aerodromes is given in Part 13.23.
- (c) As part of the certification process, Liberia shall ensure that an aerodrome manual which will include all pertinent information on the aerodrome site, facilities, services, equipment, operating procedures, organization and management including a safety management system, is submitted by the applicant for approval/acceptance prior to granting the aerodrome certificate.

Note 1.— Contents of an aerodrome manual, including procedures for its submission and approval/acceptance, verification of compliance and granting of an aerodrome certificate, are available in the LCAR Part 13.2.

Note 2.— The intent of a safety management system is to have in place an organized and orderly approach in the management of aerodrome safety by the aerodrome operator. Annex 19 — Safety

Management contains the safety management provisions applicable to certified aerodromes. Guidance on a harmonized safety management system is given in the Safety Management Manual (SMM) (Doc 9859) and in the Manual on Certification of Aerodromes (Doc 9774). Procedures on the management of change, conduct of safety assessment, reporting and analyses of safety occurrences at aerodromes and continuous monitoring to enforce compliance with applicable specifications so that identified risks are mitigated can be found in the PANS-Aerodromes (Doc 9981).

13.1.1.6 **Airport Design.** (APPLICABLE UNTIL 2 NOVEMBER 2022)

- (a) Architectural and infrastructure-related requirements for the optimum implementation of international civil aviation security measures shall be integrated into the design and construction of new facilities and alterations to existing facilities at an aerodrome.

Note. — Guidance on all aspects of the planning of aerodromes including security considerations is contained in AC 14-019. Further guidance can be found in Airport Planning Manual (Doc 9184), Part 1.

- (b) Any aerodromes design, construction of new airport facilities and changes to existing airport facilities shall take into account, where appropriate, land-use and environmental control measures.

Note. — Guidance on land-use planning and environmental control measures is contained in the AC 14-018 and Airport Planning Manual (Doc 9184), Part 2.

(13.1.1.6) Airport Design and Master Plan (APPLICABLE AS OF 3 NOVEMBER 2022)

Introductory Note.— A master plan for the long-term development of an aerodrome displays the ultimate development in a phased manner and reports the data and logic upon which the plan is based. Master plans are prepared to support modernization of existing aerodromes and creation of new aerodromes, regardless of size, complexity, and role. It is important to note that a master plan does not constitute a confirmed implementation programme. It provides information on the types of improvements to be undertaken in a phased manner. Guidance on all aspects of the planning of aerodromes is contained in the Airport Planning Manual (Doc 9184), Part 1.

- (a) A master plan containing detailed plans for the development of aerodrome infrastructure shall be established for aerodromes deemed relevant by States.

Note 1. - A master plan represents the development plan of a specific aerodrome. It is developed by the aerodrome operator based on economic feasibility, traffic forecasts, current and future requirements provided by, among others, aircraft operators (see 13.1.1.6.(c)).

Note 2. - A master plan may be required when the lack of capacity at an airport, due to conditions such as, but not limited to expected traffic growth, changing weather and climatic conditions or major works to address safety or environmental concerns, would put the connectivity of a geographical area at risk or cause severe disruption to the air transport network

- (b) The master plan shall:

- 1) contain a schedule of priorities including a phased implementation plan; and
- 2) be reviewed periodically to take into account current and future aerodrome traffic

© Aerodrome stakeholders, particularly aircraft operators, shall be consulted in order to facilitate the master planning process using a consultative and collaborative approach.

Note 1. — Provision of advanced planning data to facilitate the planning process include future aircraft types, characteristics and numbers of aircraft expected to be used, the anticipated growth of aircraft movements, number of passengers and amount of cargo projected to be handled.

Note 2. — See Annex 9, Chapter 6 on the need for aircraft operators to inform aerodrome operators concerning the former's service, schedule and fleet plans to enable rational planning of facilities and services in relation to the traffic anticipated.

Note 3. — See ICAO's Policies on Charges for Airports and Air Navigation Services Doc 9082), Section 1, regarding consultation with users concerning provision of advance planning data and protection of commercially sensitive data

(d) Architectural and infrastructure-related requirements for the optimum implementation of international civil aviation security measures shall be integrated into the design and construction of new facilities and alterations to existing facilities at an aerodrome.

€ The design of aerodromes shall take into account, land-use and environmental control measures.

Note.— Guidance on land-use planning and environmental control measures is contained in the Airport Planning Manual, (Doc 9184) Part 2.

13.1.1.7 **Aerodrome Reference Code**

Introductory Note.— The intent of the reference code is to provide a simple method for interrelating the numerous specifications concerning the characteristics of aerodromes so as to provide a series of aerodrome facilities that are suitable for the aeroplanes that are intended to operate at the aerodrome. The code is not intended to be used for determining runway length or pavement strength requirements. The code is composed of two elements which are related to the aeroplane performance characteristics and dimensions. Element 1 is a number based on the aeroplane reference field length and element 2 is a letter based on the aeroplane wingspan. The code letter or number within an element selected for design purposes is related to the critical aeroplane characteristics for which the facility is provided. When applying Annex 14, Volume I, first identify the aeroplanes which the aerodrome is intended to serve and then determine the two elements of the code.

- (a) An aerodrome reference code — code number and letter — which is selected for aerodrome planning purposes shall be determined in accordance with the characteristics of the aeroplane for which an aerodrome facility is intended.
- (b) The aerodrome reference code numbers and letters shall have the meanings assigned to them in Table 13.1-1.
- (c) The code number for element 1 shall be determined from Table 13.1.1-1 selecting the code number corresponding to the highest value of the aeroplane reference field lengths of the aeroplanes for which the runway is intended.

Note 1.— The determination of the aeroplane reference field length is solely for the selection of a code number and is not intended to influence the actual runway length provided.

Note 2.— Guidance on determining the runway length is given in the Aerodrome Design Manual, (Doc 9157), Part 1 — Runways.

- (d) The code letter for element 2 shall be determined from Table 13.1.1 -1 by selecting the code letter which corresponds to the greatest wingspan of the aeroplanes for which the facility is intended.

Note.— Guidance on determining the aerodrome reference code is given in the Aerodrome Design Manual (Doc 9157), Parts 1 and 2.

TABLE 13.1.1-1: AERODROME REFERENCE CODE

Code element 1	
Code number	Aeroplane reference field length
1	Less than 800 m
2	800 m up to but not including 1 200 m
3	1 200 m up to but not including 1 800 m
4	1 800 m and over
Code element 2	
Code letter	Wingspan
A	Up to but not including 15 m
B	15 m up to but not including 24 m
C	24 m up to but not including 36 m
D	36 m up to but not including 52 m
E	52 m up to but not including 65 m
F	65 m up to but not including 80 m

Note. — Guidance on planning for aeroplanes with wingspans greater than 80 m is given in the Aerodrome Design Manual (Doc 9157), Parts 1 and 2.

Note 2.— Procedures on conducting aerodrome compatibility study to accommodate aeroplanes with folding wing tips spanning two code letters are given in the Procedures for Air Navigation Services Aerodromes (PANS-Aerodromes, Doc9981). Further guidance can be found in the manufacturer’s aircraft characteristics for airport planning manual

13.1.1.8 **Specific Procedures for Aerodrome Operations**

Introductory Note.— This section introduces PANS-Aerodromes (Doc 9981) for use by an aerodrome undertaking an assessment of its compatibility with the type of traffic or operation it is intending to accommodate. The material in the PANS-Aerodromes addresses operational issues faced by existing aerodromes and provides the necessary procedures to ensure the continued safety of operations. Where alternative measures, operational procedures and operating restrictions have been developed, these are detailed in the aerodrome manual and reviewed periodically to assess their continued validity. The PANS-Aerodromes does not substitute nor circumvent the provisions contained in this Annex. It is expected that infrastructure on an existing aerodrome or a new aerodrome will fully comply with the

requirements in this Annex. See Annex 15, 5.2.2 c) on a State's responsibilities for the listing of its differences to the related ICAO Procedures in its Aeronautical Information Publication.

- (a)** When the aerodrome accommodates an aeroplane that exceeds the certificated characteristics of the aerodrome, the compatibility between the operation of the aeroplane and aerodrome infrastructure and operations shall be assessed and appropriate measures developed and implemented in order to maintain an acceptable level of safety during operations.

Note.— Procedures to assess the compatibility of the operation of a new aeroplane with an existing aerodrome can be found in the PANS-Aerodromes (Doc 9981).

- (b)** Information concerning alternative measures, operational procedures and operating restrictions implemented at an aerodrome arising from 1.7.1 shall be promulgated.

Note 1.— See Part 26 of LCAR on the provision of a detailed description of local traffic regulations.

Note 2.— See PANS-Aerodromes (Doc 9981), Chapter 3, section 3.6, on promulgation of safety information.

13.1.2 AERODROME DATA

13.1.2.1 Aeronautical data

- (a) Determination and reporting of aerodrome-related aeronautical data shall be in accordance with the accuracy and integrity classification required to meet the needs of the end-users of aeronautical data.

Note.— Specifications concerning the accuracy and integrity classification related to aerodrome-related aeronautical data are contained in PANS-AIM (Doc 10066), Appendix 1.

Note – Additional Standards and specifications concerning aerodrome data quality are contained in Liberia Aerodrome Data Quality System Manual (DSQM-AGA010)

- (b) Aerodrome mapping data shall be made available to the aeronautical information services for aerodromes deemed relevant by States where safety and/or performance-based operations suggest possible benefits.

Note 1.— Aerodrome mapping databases related provisions are contained in Annex 15, Chapter 5 and PANS-AIM (Doc 10066), Chapter 5.

- (c) Where made available in accordance with (b) above, the selection of the aerodrome mapping data features to be collected shall be made with consideration of the intended applications.

Note 1.— It is intended that the selection of the features to be collected match a defined operational need.

Note 2.— Aerodrome mapping databases can be provided at one of two levels of quality — fine or medium. These levels and the corresponding numerical requirements are defined in RTCA Document DO-272B and European Organization for Civil Aviation Equipment (EUROCAE) Document ED-99C — User Requirements for Aerodrome Mapping Information.

- (d) Digital data error detection techniques shall be used during the transmission and/or storage of aeronautical data and digital data sets.

Note.— Detailed specifications concerning digital data error detection techniques are contained in LCAA ANS Regulations.

13.1.2.2 Aerodrome Reference Point

- (a) The Aerodrome Operator shall ensure that an aerodrome reference point shall be established for each aerodrome.
- (b) The aerodrome reference point shall be located near the initial or planned geometric center of the aerodrome and shall normally remain where first established.
- (c) The position of the aerodrome reference point shall be measured by the Aerodrome Operator and reported to the Authority in degrees, minutes and seconds.

13.1.2.3 Aerodrome and Runway Elevations

- (a) The Aerodrome Operator shall ensure that the aerodrome elevation and geoid undulation at the aerodrome elevation position shall be measured to the accuracy of one-half meter or foot and reported to the aeronautical information services Authority.
- (b) For an aerodrome used by international civil aviation for non-precision approaches, the elevation and geoid undulation of each threshold, the elevation of the runway end and any significant high and low intermediate points along the runway shall be measured to the accuracy of one-half meter or foot and reported to the aeronautical information services Authority.
- (c) For precision approach runway, the elevation and geoid undulation of the threshold, the elevation of the runway end and the highest elevation of the touchdown zone shall be measured to the accuracy of one-quarter meter or foot and reported to the Authority.

Note.— Geoid undulation must be measured in accordance with the appropriate system of coordinates.

13.1.2.4 Aerodrome Reference Temperature

- (a) The Aerodrome Operator shall ensure that an aerodrome reference temperature shall be determined for an aerodrome in degrees Celsius.
- (b) The aerodrome reference temperature shall be the monthly mean of the daily maximum temperatures for the hottest month of the year (the hottest month being that which has the highest monthly mean temperature). This temperature shall be averaged over a period of years.

13.1.2.5 Aerodrome Dimensions and Related Information

- (a) The following data shall be measured or described, as appropriate, for each facility provided on an aerodrome:
 - (1) runway — true bearing to one-hundredth of a degree, designation number, length, width, displaced threshold location to the nearest meter or foot, slope, surface type, type of runway and, for a precision approach runway category I, the existence of an obstacle free zone when provided;
 - (2)

strip runway end safety area stopway	}	length, width to the nearest metre or foot, surface type; and
--	---	--

 arresting system — location (which runway end) and description;
 - (3) taxiway — designation, width, surface type;
 - (4) apron — surface type, aircraft stands;
 - (5) the boundaries of the air traffic control service;
 - (6) clearway — length to the nearest meter or foot, ground profile;
 - (7) visual aids for approach procedures, marking and lighting of runways, taxiways and aprons, other visual guidance and control aids on taxiways and aprons, including taxi-holding positions and stopbars, and location and type of visual docking guidance systems;
 - (8) location and radio frequency of any VOR aerodrome checkpoint;

- (9) location and designation of standard taxi-routes; and
 - (10) distances to the nearest meter or foot of localizer and glide path elements comprising an instrument landing system (ILS) or azimuth and elevation antenna of a microwave landing system (MLS) in relation to the associated runway extremities.
- (b) The geographical coordinates of each threshold shall be measured and reported to the aeronautical information services provider in degrees, minutes, seconds and hundredths of seconds.
 - (c) The geographical coordinates of appropriate taxiway center line points shall be measured and reported to the aeronautical information services provider in degrees, minutes, seconds and hundredths of seconds.
 - (d) The geographical coordinates of each aircraft stand shall be measured and reported to the aeronautical information services provider in degrees, minutes, seconds and hundredths of seconds.
 - (e) The geographical coordinates of obstacles in Area 2 (the part within the aerodrome boundary) and in Area 3 shall be measured and reported to the aeronautical information services authority in degrees, minutes, seconds and tenths of seconds. In addition, the top elevation, type, marking and lighting (if any) of obstacles shall be reported to the aeronautical information services authority.

Note 1.— PANS-AIM (Doc 10066) and Appendix 8 provide requirements for obstacle data determination in Areas 2 and 3.

13.1.2.6 **Strength of pavements. (APPLICABLE UNTIL 27 NOVEMBER 2024)**

- (a) The bearing strength of a pavement shall be determined.
- (b) The bearing strength of a pavement intended for aircraft of apron (ramp) mass greater than 5 700 kg shall be made available using the aircraft classification number — pavement classification number (ACN-PCN) method by reporting all of the following information:
 - (1) the pavement classification number (PCN);
 - (2) pavement type for ACN-PCN determination;
 - (3) subgrade strength category;
 - (4) maximum allowable tire pressure category or maximum allowable tire pressure value; and
 - (5) evaluation method.

Note.— If necessary, PCNs may be published to an accuracy of one-tenth of a whole number.

- (c) The pavement classification number (PCN) reported shall indicate that an aircraft with an aircraft classification number (ACN) equal to or less than the reported PCN can operate on the pavement subject to any limitation on the tire pressure, or aircraft all-up mass for specified aircraft type(s).

Note.— Different PCNs may be reported if the strength of the pavement is subject to significant seasonal variation.

- (d) The ACN of an aircraft shall be determined in accordance with the standard procedures associated with the ACN-PCN method.

Note.— The standard procedures for determining the ACN of an aircraft are given in the Aerodrome Design Manual (Doc 9157), Part 3. For convenience several aircraft types currently in use have been evaluated on rigid and flexible pavements founded on the four subgrade categories in 2.6.6 b) below and the results tabulated in that manual.

- (e) For the purposes of determining the ACN, the behavior of a pavement shall be classified as equivalent to a rigid or flexible construction.
- (f) Information on pavement type for ACN-PCN determination, subgrade strength category, maximum allowable tire pressure category and evaluation method shall be reported using the following codes:

(a)	<i>Pavement type for ACN-PCN determination:</i>	
	Rigid pavement	Code R
	Flexible pavement	F
	<i>Note.— If the actual construction is composite or non-standard, include a note to that effect (see example 2 below).</i>	
(b)	<i>Subgrade strength category:</i>	
	<i>High strength:</i> characterized by $K = 150 \text{ MN/m}^3$ and representing all K values above 120 MN/m^3 for rigid pavements, and by CBR = 15 and representing all CBR values above 13 for flexible pavements.	Code A
	<i>Medium strength:</i> characterized by $K = 80 \text{ MN/m}^3$ and representing a range in K of 60 to 120 MN/m^3 for rigid pavements, and by CBR = 10 and representing a range in CBR of 8 to 13 for flexible pavements.	B
	<i>Low strength:</i> characterized by $K = 40 \text{ MN/m}^3$ and representing a range in K of 25 to 60 MN/m^3 for rigid pavements, and by CBR = 6 and representing a range in CBR of 4 to 8 for flexible pavements.	C
	<i>Ultra low strength:</i> characterized by $K = 20 \text{ MN/m}^3$ and representing all K values below 25 MN/m^3 for rigid pavements, and by CBR = 3 and representing all CBR values below 4 for flexible pavements.	D
(c)	<i>Maximum allowable tire pressure category:</i>	
	<i>Unlimited:</i> no pressure limit	Code W
	<i>High:</i> pressure limited to 1.75 MPa	X
	<i>Medium:</i> pressure limited to 1.25 MPa	Y
	<i>Low:</i> pressure limited to 0.50 MPa	Z
	<i>Note.— See Note 5 to 10.2.1 where the pavement is used by aircraft with tire pressures in the upper categories.</i>	
(d)	<i>Evaluation method:</i>	
	<i>Technical evaluation:</i> representing a specific study of the pavement characteristics and application of pavement behavior technology.	Code T
	<i>Using aircraft experience:</i> representing a knowledge of the specific type and mass of aircraft satisfactorily being supported under regular use.	U

Note.— The following examples illustrate how pavement strength data are reported under the ACN-PCN method.

Example 1.— If the bearing strength of a rigid pavement, resting on a medium strength subgrade, has been assessed by technical evaluation to be PCN 80 and there is no tire pressure limitation, then the reported information would be:

PCN80/R/B/W/T

Example 2.— If the bearing strength of a composite pavement, behaving like a flexible pavement and resting on a high strength subgrade, has been assessed by using aircraft experience to be PCN 50 and the maximum tire pressure allowable is 1.25 MPa, then the reported information would be:

PCN50/F/A/Y/U

Note.— Composite construction.

Example 3.— If the bearing strength of a flexible pavement, resting on a medium strength subgrade, has been assessed by technical evaluation to be PCN 40 and the maximum allowable tire pressure is 0.80 MPa, then the reported information would be:

PCN 40 / F / B / 0.80 MPa /T

Example 4.— If a pavement is subject to a B747-400 all-up mass limitation of 390 000 kg, then the reported information would include the following note.

Note.— The reported PCN is subject to a B747-400 all-up mass limitation of 390 000 kg.

- (g) Aircraft whose ACN is higher than the PCN shall be accepted if $PCN < ACN < 1.1$ for PCN (Code F) or 1.05 for PCN (Code R) and the number of Movements is less than 5% of the total annual number of aircraft movements. These overload movements shall not, however, be permitted on pavements which show signs of weakness or breakage or where the resistance of the pavement and its foundation may be impaired by water. In the case of overloading, the aerodrome operator shall check at least once a year the condition of the pavements and the operating criteria in overload, since excessive repetition of overloads may severely shorten the duration Road service or require extensive repairs. In other cases, acceptance shall be subjected to the authorization of the aerodrome operator after an aeronautical study.

Note.— the Aerodrome Design Manual (Doc 9157), Part 3, includes the descriptions of more detailed procedures for evaluation of pavements and their suitability for restricted overload operations.

- (h) The bearing strength of a pavement intended for aircraft of apron (ramp) mass equal to or less than 5 700 kg shall be made available by reporting the following information:
- (1) maximum allowable aircraft mass; and
 - (2) maximum allowable tire pressure.

Example: 4 000 kg/0.50 MPa.

13.1.2.6.1 **Strength of pavements. (APPLICABLE AS OF NOVEMBER 2024)**

- (a) The bearing strength of a pavement shall be determined.
- (b) The bearing strength of a pavement intended for aircraft of apron (ramp) mass greater than 5700 kg shall be made available using the aircraft classification rating – pavement classification rating (ACR-PCR) method by reporting all of the following information:
 - (1) the pavement classification rating (PCR) and numerical value;
 - (2) pavement type for ACR-PCR determination;

- (3) sub-grade strength category;
- (4) maximum allowable tyre pressure category or maximum allowable tyre pressure value; and
- (5) evaluation method.

Note – Guidance on reporting and publishing of PCRs is contained in Aerodrome Design Manual (Doc 9157, Part 3).

© The pavement classification rating (PCR) reported shall indicate that an aircraft with an aircraft classification rating (ACR) equal to or less than the reported PCR can operate on the pavement subject to any limitation on the tyre pressure, or aircraft all-up mass for specified aircraft type(s).

Note – Different PCRs may be reported if the strength of the pavement is subject to significant seasonal variation.

(d) The ACR of an aircraft shall be determined in accordance with the standard procedures associated with the ACR-PCR method.

Note – The standard procedures for determining the ACR of an aircraft are given in the ICAO Aerodrome Design Manual(DOC 9157), Part 3. Dedicated software is available on the ICAO website, for computing any aircraft ACRs at any mass on rigid and flexible pavements for the four standard subgrade strength categories detailed in 13.1.2.6.6 (b)

(f) For the purposes of determining the ACR, the behaviour of a pavement shall be classified as equivalent to a rigid or flexible construction.

(g) Information on pavement type for ACR-PCR determination, sub grade strength category, maximum allowable tyre pressure category and evaluation method shall be reported using the following codes:

(a) Pavement type for ACR-PCR determination:	Code
Rigid pavement	R
Flexible pavement	F

Note – If the actual construction is composite or non-standard, include a note to that effect (See example 2 below).

(b) Sub grade strength category:	Code
High strength: characterized by E=200 MPa and representing all E values equal to or above 150 MPa for rigid and flexible pavements	A
Medium strength: characterized by E=120 MPa and representing a range of E values equal to or above 100 MPa and strictly less than 150 MPa for rigid and flexible pavements	B
Low strength: characterized by E=80 MPa and representing a range of E values equal to or above 60 MPa	C

and strictly less than 100 MPa for rigid and flexible pavements

Ultra low strength: characterized by $E=50$ MPa and representing all E values strictly less than 60 MPa for rigid and flexible pavements D

(c)	Maximum allowable tyre pressure category	Code
	Unlimited : no pressure limit	W
	High: pressure limited to 1.50 MPa	X
	Medium: pressure limited to 1.00 MPa	Y
	low: pressure limited to 0.50 MPa	Z

Note.— See Note 5 to 10.2.1 where the pavement is used by aircraft with tyre pressures in the upper categories.

(d)	Evaluation method:	Code
	Technical evaluation: representing a specific study of the pavement characteristics and the types of aircraft which the pavement is intended to serve .	T
	Using aircraft experience: representing a knowledge of the specific type and mass of aircraft satisfactorily being supported under regular use.	U

Note – The following examples illustrate how pavement strength data are reported under the ACR-PCR method. Further guidance on this topic is contained in the Aerodrome Design Manual (Doc 9157), Part 3 - Pavements

Example 1 – If the bearing strength of a rigid pavement, resting on a medium strength sub grade, has been assessed by technical evaluation to be PCR 760 and there is no tyre pressure limitation, then the reported information would be:

PCR 760/ R / B / W / T

Example 2 – If the bearing strength of a composite pavement, behaving like a flexible pavement and resting on a high strength sub grade, has been assessed using aircraft experience to be PCR 550 and the maximum tyre pressure allowable is 1.25 MPa, then the reported information would be:

PCR 550/ F / A / Y / U

Note.— Composite construction.

(h) Criteria shall be established to regulate the use of a pavement by an aircraft with an ACR higher than the PCR reported for that pavement in accordance with sections 13.1.2.6.(b) and 13.1.2.6(c).

Note – Guidance Material“Supplementary Guidance Material to Aerodrome Regulation (GM-AGA005), Section 19 details a simple method for regulating overload operations while the ICAO Aerodrome Design Manual(Doc 9157), Part 3 includes the descriptions of more detailed procedures for evaluation of pavements and their suitability for restricted overload operations.

(i) The bearing strength of a pavement intended for aircraft of apron (ramp) mass equal to or less than 5700 kg shall be made available by reporting the following information:

(a) maximum allowable aircraft mass; and

(b) maximum allowable tyre pressure.

Example: 4 800 kg/0.60 MPa.

13.1.2.7 Pre-Flight Altimeter Check Location

(a) One or more pre-flight altimeter check locations shall be established by the Aerodrome Operator for each aerodrome subject to approval by the Authority.

(b) A pre-flight check location shall be located on an apron.

Note 1. — Locating a pre-flight altimeter check location on an apron enables an altimeter check to be made prior to obtaining taxi clearance and eliminates the need for stopping for that purpose after leaving the apron.

Note 2. — Normally an entire apron can serve as a satisfactory altimeter check location.

(c) The elevation of a pre-flight altimeter check location shall be given as the average elevation, rounded to the nearest meter or foot, of the area on which it is located. The elevation of any portion of a pre-flight altimeter check location shall be within 3 m (10 ft) of the average elevation for that location.

13.1.2.8 Declared Distances

(a) The following distances shall be calculated to the nearest meter or foot for a runway intended for use by international commercial air transport:

- (1) take-off run available;
- (2) take-off distance available;
- (3) accelerate-stop distance available; and
- (4) landing distance available.

13.1.2.9 Condition of the Movement Area and Related Facilities

- (a) The Aerodrome Operator shall ensure that information on the condition of the movement area and the operational status of related facilities shall be provided to the aeronautical information services Section, and similar information of operational significance to the air traffic services units, to enable those units to provide the necessary information to arriving and departing aircraft. The information shall be kept up to date and changes in conditions reported without delay.

Note. — *The nature, format and conditions of the information to be provided are specified in the PANS-AIM (Doc 10066) and the PANS-ATM (Doc 4444). Specific procedures pertaining to work in progress of such works are specified in the PANS-Aerodromes (Doc 9981)*

- (b) The condition of the movement area and the operational status of related facilities shall be monitored by the Aerodrome Operator, and reports on matters of operational significance affecting aircraft and aerodrome operations shall be provided in order to take appropriate action, particularly in respect of the following:

- (1) construction or maintenance work;
- (2) rough or broken surfaces on a runway, a taxiway or an apron;
- (3) anti-icing or de-icing liquid chemicals or other contaminants on a runway, taxiway or apron;
- (4) other temporary hazards, including parked aircraft;
- (5) failure or irregular operation of part or all of the aerodrome visual aids; and
- (6) failure of the normal or secondary power supply.

Note 1.— *As of 5 November 2020, other contaminants may include mud, dust, sand, volcanic ash, oil and rubber. Procedures for monitoring and reporting the conditions of the movement area are included in the PANS-Aerodromes (Doc 9981).*

Note 2.— *As of 5 November 2020, the Aeroplane Performance Manual (Doc 10064) provides guidance on aircraft performance calculation requirements regarding the description of runway surface conditions in 2.9.2 c), e) and f).*

Note 3.— *As of 5 November 2020, origin and evolution of data, assessment process and the procedures are prescribed in the PANS-Aerodromes (Doc 9981). These procedures are intended to fulfil the requirements to achieve the desired level of safety for aeroplane operations prescribed by Annex 6 and Annex 8 and to provide the information fulfilling the syntax requirements for dissemination specified in Annex 15 and the PANS-ATM (Doc 4444).*

- (c) Until 4 November 2020, to facilitate compliance with (a) and (b), the Aerodrome Operator shall ensure that the following inspections of the movement area shall be carried out each day:

- (1) for the movement area, at least once where the aerodrome reference code number is 1 or 2 and at least twice where the aerodrome reference code number is 3 or 4; and
- (2) for the runway(s), inspections in addition to a) whenever the runway surface conditions may have changed significantly due to meteorological conditions.

- (d) As of 5 November 2020, to facilitate compliance with (a) and (b), the Aerodrome Operator shall ensure that the following inspections of the movement area shall be carried out each day:
- (1) for the movement area, at least once where the aerodrome reference code number is 1 or 2 and at least twice where the aerodrome reference code number is 3 or 4; and
 - (2) for the runway(s), inspections in addition to (1) whenever the runway surface conditions may have changed significantly due to meteorological conditions.

Note 1.— Procedures on carrying out daily inspections of the movement area are given in the PANS-Aerodromes (Doc 9981). Further guidance is available in the Airport Services Manual (Doc 9137), Part 8, in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476) and in the Advanced Surface Movement Guidance and Control Systems (A-SMGCS) Manual (Doc 9830).

Note 2.— The PANS-Aerodromes (Doc 9981) contains clarifications on the scope of a significant change in the runway surface conditions.

- (e) As of 5 November 2020, Personnel assessing and reporting runway surface conditions required in 13.1.2.9(b) and 13.1.2.10 shall be trained and have competence that meets criteria set by Authority.

Note 1.— Guidance on training of personnel is given in Attachment A, Section 6 [applicable 5 November 2020].

Note 2.— Information on training for personnel assessing and reporting runway surface conditions is available in the PANS-Aerodromes (Doc 9981).

13.1.2.10 **Water on a Runway (Applicable until 4 November 2020)**

- (a) The Aerodrome Operator shall ensure that whenever water is present on a runway, a description of the runway surface conditions shall be made available using the following terms:
- (1) DAMP — the surface shows a change of color due to moisture.
 - (2) WET — the surface is soaked but there is no standing water.
 - (3) STANDING WATER — for aeroplane performance purposes, a runway where more than 25 per cent of the runway surface area (whether in isolated areas or not) within the required length and width being used is covered by water more than 3 mm deep.
- (b) The Aerodrome Operator shall ensure that information that a runway or portion thereof may be slippery when wet shall be made available.

Note.— The determination that a runway or portion thereof may be slippery when wet is not based solely on the friction measurement obtained using a continuous friction measuring device. Supplementary tools to undertake this assessment are described in the Airport Services Manual (Doc 9137), Part 2.

- (c) Notification shall be given to aerodrome users when the friction level of a paved runway or portion thereof is less than that specified by the Authority in accordance with 13.1.10.2 (c).

Runway surface condition(s) for use in the runway condition report [applicable 5 November 2021]

Introductory Note.— The philosophy of the runway condition report is that the aerodrome operator assesses the runway surface conditions whenever water, snow, slush, ice or frost are present on an operational runway. From this assessment, a runway condition code (RWYCC) and a description of the runway surface are reported which can be used by the flight crew for aeroplane performance calculations. This report, based on the type, depth and coverage of contaminants, is the best assessment of the runway surface condition by the aerodrome operator; however, all other pertinent information may be taken into consideration. See Attachment A, Section 6, for further details. The PANS-Aerodromes (Doc 9981) contains procedures on the use of the runway condition report and assignment of the RWYCC in accordance with the runway condition assessment matrix (RCAM).

- (a) The runway surface condition shall be assessed and reported through a runway condition code (RWYCC) and a description using the following terms:

SLUSH
STANDING WATER
CHEMICALLY TREATED
LOOSE SAND

Note 1.— The runway surface conditions are those conditions for which, by means of the methods described in the PANS-Aerodromes (Doc 9981), the flight crew can derive appropriate aeroplane performance.

Note 2.— The conditions, either singly or in combination with other observations, are criteria for which the effect on aeroplane performance is sufficiently deterministic to allow assignment of a specific runway condition code.

Note 3.— The terms CHEMICALLY TREATED and LOOSE SAND do not appear in the aeroplane performance section but are used in the situational awareness section of the runway condition report.

- (b) Whenever an operational runway is contaminated, an assessment of the contaminant depth and coverage over each third of the runway shall be made and reported.

Note.— Procedures on depth and coverage reporting are found in the PANS-Aerodromes (Doc 9981).

- (c) When friction measurements are used as part of the overall runway surface assessment, the friction measuring device shall meet the standard set or agreed by the Authority.

- (d) Friction measurements made on runway surface conditions with contaminants other than compacted snow and ice should not be reported.

Note.— Friction measurements on loose contaminants such as snow and slush, in particular, are unreliable due to drag effects on the measurement wheel.

- (e) Information that a runway or portion thereof is slippery wet shall be made available.

Note 1.— The surface friction characteristics of a runway or a portion thereof can be degraded due to rubber deposits, surface polishing, poor drainage or other factors. The determination that a runway or portion thereof is slippery wet stems from various methods used solely or in combination. These methods may be functional friction measurements, using a continuous friction measuring device, that fall below a minimum standard as defined by the Authority, observations by aerodrome maintenance personnel, repeated reports by pilots and aircraft operators based on flight crew experience, or through analysis of aeroplane stopping performance that indicates a substandard surface. Supplementary tools to undertake this assessment are described in the PANS-Aerodromes (Doc 9981).

Note 2.— See 13.1.2.9 and 13.1.2.14 concerning the provision of information to, and coordination between, appropriate authorities.

- (f) Notification shall be given to relevant aerodrome users when the friction level of a paved runway or portion thereof is less than the minimum friction level specified by the State in accordance with 13.1.10.2©.

Note 1.— Guidance on determining and expressing the minimum friction level is provided in Assessment, Measurement and Reporting of Runway Surface Conditions (Cir 329

Note 2.— Procedures on conducting a runway surface friction characteristics evaluation program are provided in the PANS-Aerodromes (Doc 9981)) and Guidance Material on Assessment of Runway Friction (GM-AGA011)

Note 3.— Information to be promulgated in a NOTAM includes specifying which portion of the runway is below the minimum friction level and its location on the runway.

13.1.2.11 **Disabled Aircraft Removal**

- (a) Each Aerodrome operator shall, upon request, provide aircraft operators with the telephone or telex number(s) of the office of the aerodrome coordinator of operations for the removal of an aircraft disabled on or adjacent to the movement area.
- (b) Every aerodrome operator shall publish information concerning its capability to remove an aircraft disabled on or adjacent to the movement area.

Note. — The capability to remove a disabled aircraft may be expressed in terms of the largest type of aircraft which the aerodrome is equipped to remove.

13.1.2.12 **Rescue and Firefighting**

- (a) The Aerodrome Operator shall ensure that information concerning the level of protection provided at an aerodrome for aircraft rescue and firefighting purposes is published.

Note. — See 13.1.9.2 for information on rescue and firefighting services.

- (b) The level of protection normally available at an aerodrome shall be expressed in terms of the category of the rescue and firefighting services as described in 13.1.9.2 and in accordance with the types and amounts of extinguishing agents normally available at the aerodrome.
- (c) Changes in the level of protection normally available at an aerodrome for rescue and firefighting shall be notified to the air traffic services Section and aeronautical information services Section to enable those Sections to provide the necessary information to arriving and departing aircraft. When such a change has been corrected, the above units shall be advised accordingly.

Note.— Changes in the level of protection from that normally available at the aerodrome could result from a change in the availability of extinguishing agents, equipment to deliver the agents or personnel to operate the equipment, etc.

- (d) A change shall be expressed in terms of the new category of the rescue and firefighting service available at the aerodrome.

13.1.2.13 **Visual Approach Slope Indicator Systems**

The Operator shall ensure that the following information concerning a visual approach slope indicator system installation shall be made available:

- (1) associated runway designation number;
- (2) type of system according to 13.1.5.3 (e) (1)(ii). For an AT-VASIS, PAPI or APAPI installation, the side of the runway on which the lights are installed, i.e. left or right, shall be given;
- (3) where the axis of the system is not parallel to the runway center line, the angle of displacement and the direction of displacement, i.e. left or right, shall be indicated;
- (4) nominal approach slope angle(s). For a T-VASIS or an AT-VASIS this shall be angle θ according to the formula in Figure 13.1.5-18 and for a PAPI and an APAPI this shall be angle $(B + C) \div 2$ and $(A + B) \div 2$, respectively as in Figure 13.1.5-20; and
- (5) minimum eye height(s) over the threshold of the on-slope signal(s). For a T-VASIS or an AT-VASIS this shall be the lowest height at which only the wing bar(s) are visible; however, the additional heights at which the wing bar(s) plus one, two or three fly- down light units come into view may also be reported if
- (6) such information would be of benefit to aircraft using the approach. For a PAPI this shall be the setting angle of the third unit from the runway minus $2'$, i.e. angle B minus $2'$, and for an APAPI this shall be the setting angle of the unit farther from the runway minus $2'$, i.e. angle A minus $2'$.

13.1.2.14 **Coordination between Aeronautical Information Services and Aerodrome Operator**

- (a) To ensure that aeronautical information services Section obtains information to enable them to provide up-to-date pre-flight information and to meet the need for in-flight information, arrangements shall be made between aeronautical information services Section and aerodrome Operator responsible for aerodrome services to report to the responsible aeronautical information services unit, with a minimum of delay:
 - (1) information on the status of certification of aerodromes and aerodrome conditions (*ref. 13.1.1.5, 13.1.2.9, 13.1.2.10, 13.1.2.11 and 13.1.2.12*);
 - (2) the operational status of associated facilities, services and navigation aids within their area of responsibility;
 - (3) any other information considered to be of operational significance.
- (b) Due account of the time needed by the AIS Section for the preparation, production and issue of relevant material for publication, shall be taken into consideration before introducing changes to the air navigation system. To ensure timely provision of the information to AIS, close coordination between those services concerned shall be required.
- (c) Predetermined, internationally agreed AIRAC effective dates in addition to 14 days' postage time shall be observed by the Aerodrome Operator when submitting the raw information or data to aeronautical information services Section in respect of Changes to aeronautical information that affect charts and or computer-based navigation systems which qualify to be notified by the Aeronautical Information Regulation and Control (AIRAC) system, as specified in Part 15 of the Liberia Civil Aviation (ANS) Directives. The by the responsible aerodrome services.

Note – Detailed specifications concerning the AIRAC system are contained in PANS-AIM (Doc 10066), Chapter 6.

- (d) The aerodrome services responsible for the provision of raw aeronautical information and aeronautical data to the aeronautical information services Section shall do that while taking into account accuracy and integrity requirements required to meet the needs of the end-user of aeronautical data.

Note 1. - Specifications concerning the accuracy and integrity classification of aerodrome-related aeronautical data are contained in PANS-AIM (Doc 10066), Appendix 1.

Note 2. - Specifications for the issue of NOTAM is contained in Liberia Civil Aviation (ANS) Regulations.

Note 3. - AIRAC information is distributed by the AIS at least 42 days in advance of the AIRAC effective dates with the objective of reaching recipients at least 28 days in advance of the effective date.

Note 4. - The schedule of the predetermined internationally agreed AIRAC common effective dates at intervals of 28 days and guidance for the AIRAC use are contained in the Aeronautical Information Services Manual (Doc 8126, Chapter 2).

13.1.3 PHYSICAL CHARACTERISTICS

13.1.3.1 Runways

(a) **Number and orientation of runways**

Introductory Note.— *Many factors affect the determination of the orientation, siting and number of runways.*

One important factor is the usability factor, as determined by the wind distribution, which is specified hereunder.

Another important factor is the alignment of the runway to facilitate the provision of approaches conforming to the approach surface specifications.

When a new instrument runway is being located, particular attention needs to be given to areas over which aeroplanes will be required to fly when following instrument approach and missed approach procedures, so as to ensure that obstacles in these areas or other factors will not restrict the operation of the aeroplanes for which the runway is intended.

- (1) The Aerodrome Operator shall ensure that the number and orientation of runways at an aerodrome shall be such that the usability factor of the aerodrome is not less than 95 per cent for the aeroplanes that the aerodrome is intended to serve.
- (2) The siting and orientation of runways at an aerodrome shall, where possible, be such that the arrival and departure tracks minimize interference with areas approved for residential use and other noise-sensitive areas close to the aerodrome in order to avoid future noise problems.

Note. — Guidance on how to address noise problems is provided in LCAR Part 16 and further guidance can be found in the Airport Planning Manual (Doc 9184), Part 2, and in Guidance on the Balanced Approach to Aircraft Noise Management (Doc9829).

(b) **Choice of maximum permissible crosswind components.** Pursuant to the provisions of (a), under normal circumstances there shall be no landing or take-off of aeroplanes if the value of the crosswind component exceeds:

- (1) 37 km/h (20 kt) in the case of aeroplanes whose reference field length is 1 500 m or over, except that when poor runway braking action owing to an insufficient longitudinal coefficient of friction is experienced with some frequency, a crosswind component not exceeding 24 km/h (13 kt) should be assumed;
- (2) 24 km/h (13 kt) in the case of aeroplanes whose reference field length is 1 200 m or up to but not including 1 500 m; and
- (3) 19 km/h (10 kt) in the case of aeroplanes whose reference field length is less than 1 200m.

(c) **Data to be used.** The selection of data to be used for the calculation of the usability factor shall be based on reliable wind distribution statistics that extend over as long a period as possible, preferably of not less than five years. The observations used shall be made at least eight times daily and spaced at equal intervals of time.

Note — These winds are mean winds. Reference to the need for some allowance for gusty conditions is made in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 1.

(d) Location of Threshold.

- (1) The Aerodrome Operator shall ensure that the runway threshold shall be located at the extremity of a runway unless operational considerations justify the choice of another location which justification shall be subject to the approval of the Authority

Note — Guidance on the siting of the threshold is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 12.

- (2) When it is necessary to displace a threshold, either permanently or temporarily, from its normal location, account shall be taken of the various factors which may have a bearing on the location of the threshold. Where this displacement is due to an unserviceable runway condition, a cleared and graded area of at least 60 m in length shall be available between the unserviceable area and the displaced threshold. Additional distance shall also be provided to meet the requirements of the runway end safety area as appropriate.

Note — Guidance on factors which may be considered in the determination of the location of a displaced threshold is given in, Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 12.

(e) Actual Length of Runways

- (1) **Primary runway.** Except as provided in (3) below, the Aerodrome Operator shall ensure that the actual runway length to be provided for a primary runway shall be adequate to meet the operational requirements of the aeroplanes for which the runway is intended and shall be not less than the longest length determined by applying the corrections for local conditions to the operations and performance characteristics of the relevant aeroplanes.

Note 1. — This specification does not necessarily mean providing for operations by the critical aeroplane at its maximum mass.

Note 2. — Both take-off and landing requirements need to be considered when determining the length of runway to be provided and the need for operations to be conducted in both directions of the runway.

Note 3. — Local conditions that may need to be considered include elevation, temperature, runway slope, humidity and the runway surface characteristics.

Note 4. — When performance data on aeroplanes for which the runway is intended are not known, guidance on the determination of the actual length of a primary runway by application of general correction factors is given in the Aerodrome Design Manual (Doc 9157), Part 1.

- (2) **Secondary runway.** The length of a secondary runway shall be determined similarly to primary runways except that it need only to be adequate for those aeroplanes which require to use that secondary runway in addition to the other runway or runways in order to obtain a usability factor of at least 95 percent.
- (3) **Runways with stopways or clearways.** Where a runway is associated with a stopway or clearway, an actual runway length less than that resulting from application of (a) or (b) above, as appropriate, shall be considered satisfactory, but in such a case any combination of runway, stopway and clearway provided shall permit compliance with the operational requirements for take-off and landing of the aeroplanes the runway is intended to serve.

Note — Guidance on use of stop ways and clearways is given in, Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 2.

(f) Width of runways

- (1) The Aerodrome Operator shall ensure that the width of a runway shall be not less than the appropriate dimension specified in the following tabulation:

Code number	Outer Main Gear Wheel Span (OMGWS)			
	Up to but not including 4.5 m	4.5 m up to but not including 6 m	6 m up to but not including 9 m	9 m up to but not including 15 m
1 ^a	18 m	18 m	23 m	–
2 ^a	23 m	23 m	30 m	–
3	30 m	30 m	30 m	45 m
4	–	–	45 m	45 m

a. The width of a precision approach runway should be not less than 30 m where the code number is 1 or 2.

Note 1. — The combinations of code numbers and OMGWS for which widths are specified have been developed for typical aeroplane characteristics.

Note 2. — Factors affecting runway width are given in the Aerodrome Design Manual (Doc 9157), Part 1.

Note 3. — See 13.1.3.2 concerning the provision of runway shoulders, in particular for Code F aeroplanes with four (or more) engines

(g) Minimum distance between parallel runways

- (1) Where parallel non-instrument runways are intended for simultaneous use, the minimum distance between their center lines shall be:
- (i) 210 m where the higher code number is 3 or 4;
 - (ii) 150 m where the higher code number is 2; and
 - (iii) 120 m where the higher code number is 1.

Note. — Procedures for wake turbulence categorization of aircraft and wake turbulence separation minima are contained in the PANS-ATM (Doc 4444), Part 14, 4.9 and 14.5, 14.5.8, respectively.

- (2) Where parallel instrument runways are intended for simultaneous use subject to conditions specified in the PANS-ATM (Doc 4444) and the PANS-OPS (Doc 8168), Volume I, the minimum distance between their center lines shall be:
- (i) 1 035 m for independent parallel approaches;
 - (ii) 915 m for dependent parallel approaches;
 - (iii) 760 m for independent parallel departures;

- (iv) 760 m for segregated parallel operations;

Except that:

- (v) for segregated parallel operations the specified minimum distance:
- (A) may be decreased by 30 m for each 150 m that the arrival runway is staggered toward the arriving aircraft, to a minimum of 300 m; and
 - (B) shall be increased by 30 m for each 150 m that the arrival runway is staggered away from the arriving aircraft;
- (vi) for independent parallel approaches, combinations of minimum distances and associated conditions other than those specified in the PANS-ATM (Doc 4444) may be applied when it is determined that such combinations would not adversely affect the safety of aircraft operations.

Note.— Procedures and facilities requirements for simultaneous operations on parallel or near-parallel instrument runways are contained in the PANS-ATM (Doc 4444), Chapter 6 and the PANS-OPS (Doc 8168), Volume I, Part III, Section 2, and Volume II, Part I, Section 3; Part II, Section 1; and Part III, Section 3, and relevant guidance is contained in the Manual on Simultaneous Operations on Parallel or Near-Parallel Instrument Runways (SOIR) (Doc 9643).

(h) Slopes on runways

(1) Longitudinal slopes:

- (i) The slope computed by dividing the difference between the maximum and minimum elevation along the runway center line by the runway length shall not exceed:
- (A) 1 per cent where the code number is 3 or 4; and
 - (B) 2 per cent where the code number is 1 or 2.
- (ii) Along no portion of a runway shall the longitudinal slope exceed:
- (A) 1.25 per cent where the code number is 4, except that for the first and last quarter of the length of the runway the longitudinal slope should not exceed 0.8 percent;
 - (B) 1.5 per cent where the code number is 3, except that for the first and last quarter of the length of a precision approach runway category II or III the longitudinal slope should not exceed 0.8 per cent; and
 - (C) 2 per cent where the code number is 1 or 2.

(2) Longitudinal slope changes

- (i) Where slope changes cannot be avoided, a slope change between two consecutive slopes shall not exceed:
- (A) 1.5 per cent where the code number is 3 or 4; and

- (B) 2 per cent where the code number is 1 or 2.
- (ii) The transition from one slope to another shall be accomplished by a curved surface with a rate of change not exceeding:
 - (A) 0.1 per cent per 30 m (minimum radius of curvature of 30 000 m) where the code number is 4;
 - (B) 0.2 per cent per 30 m (minimum radius of curvature of 15 000 m) where the code number is 3; and
 - (C) 0.4 per cent per 30 m (minimum radius of curvature of 7 500 m) where the code number is 1 or 2.

Note — Guidance on slope changes before a runway is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 4.

(3) **Sight distance:**

- (i) Where slope changes cannot be avoided, they shall be such that there will be an unobstructed line of sight from:
 - (A) any point 3 m above a runway to all other points 3 m above the runway within a distance of at least half the length of the runway where the code letter is C, D, E or F;
 - (B) any point 2 m above a runway to all other points 2 m above the runway within a distance of at least half the length of the runway where the code letter is B; and
 - (C) any point 1.5 m above a runway to all other points 1.5 m above the runway within a distance of at least half the length of the runway where the code letter is A.

Note. — Consideration will have to be given to providing an unobstructed line of sight over the entire length of a single runway where a full-length parallel taxiway is not available. Where an aerodrome has intersecting runways, additional criteria on the line of sight of the intersection area would need to be considered for operational safety. See the Aerodrome Design Manual (Doc 9157), Part 1.

(4) **Distance between slope changes:**

- (i) Undulations or appreciable changes in slopes located close together along a runway shall be avoided by the Aerodrome Operator. The distance between the points of intersection of two successive curves should not be less than:
 - (A) the sum of the absolute numerical values of the corresponding slope changes multiplied by the appropriate value as follows:
 - (B) 30 000 m where the code number is 4;

- (C) 15 000 m where the code number is 3;and
- (D) 5 000 m where the code number is 1 or 2; or
- (ii) 45 m; whichever is greater.

Note — Guidance on implementing this specification is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 4.

(5) **Transverse slopes:**

- (i) To promote the most rapid drainage of water, the Aerodrome Operator shall ensure that the runway surface shall, if practicable, be cambered except where a single crossfall from high to low in the direction of the wind most frequently associated with rain would ensure rapid drainage. The transverse slope shall ideally be:
 - (A) 1.5 per cent where the code letter is C, D, E or F; and
 - (B) 2 per cent where the code letter is A or B;

but in any event shall not exceed 1.5 per cent or 2 per cent, as applicable, nor be less than 1 per cent except at runway or taxiway intersections where flatter slopes may be necessary. For a cambered surface the transverse slope on each side of the centerline shall be symmetrical.

Note — On wet runways with cross-wind conditions the problem of aquaplaning from poor drainage is apt to be accentuated. In Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 9, information is given concerning this problem and other relevant factors.

- (ii) The transverse slope shall be substantially the same throughout the length of a runway except at an intersection with another runway or a taxiway where an even transition shall be provided taking account of the need for adequate drainage.

Note. — Guidance on transverse slope is given in the Aerodrome Design Manual (Doc 9157), Part 3.

- (i) **Strength of runways.** The Aerodrome Operator shall ensure that a runway shall be capable of withstanding the traffic of aeroplanes the runway is intended to serve.

(j) **Surface of runways**

- (1) The Aerodrome Operator shall ensure that the surface of a runway shall be constructed without irregularities that would impair the runway surface friction characteristics or otherwise adversely affect the take-off or landing of an aeroplane.

Note 1.— Surface irregularities may adversely affect the take-off or landing of an aeroplane by causing excessive bouncing, pitching, vibration, or other difficulties in the control of an aeroplane.

Note 2 — Guidance on design tolerances and other information is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 5. Additional guidance is included in the ICAO Aerodrome Design Manual (Doc 9157), Part 3.

- (2) The Aerodrome Operator shall ensure that a paved runway shall be so constructed or resurfaced as to provide surface friction characteristics at or above the minimum friction level set by the Authority.
- (3) The surface of a paved runway shall be evaluated when constructed or resurfaced to determine that the surface friction characteristics achieve the design objectives.

Note.— Guidance on surface friction characteristics of a new or resurfaced runway is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005)Section 8. Additional guidance is included in the ICAO Airport Services Manual (Doc 9137), Part 2

- (4) Measurements of the surface friction characteristics of a new or resurfaced paved runway shall be made with a continuous friction measuring device using self-wetting features.

Note — Guidance on surface friction characteristics of new runway surfaces is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 8. Additional guidance is included in the ICAO Airport Services Manual(Doc 9137), Part 2.

- (5) The average surface texture depth of a new surface shall be not less than 1.0mm.

Note 1 — Macrottexture and microtexture are taken into consideration in order to provide the required surface friction characteristics. Guidance on surface design is given in Guidance Material“Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005),Section 8

Note 2. — Guidance on methods used to measure surface texture is given in the Airport Services Manual (Doc 9137), Part 2.

Note 3. — Guidance on design and methods for improving surface texture is given in the Aerodrome Design Manual (Doc 9157), Part 3.

- (6) The Aerodrome Operator shall ensure that when the surface is grooved or scored, the grooves or scorings shall be either perpendicular to the runway center line or parallel to non-perpendicular transverse joints, where applicable.

Note. — Guidance on methods for improving the runway surface texture is given in the Aerodrome Design Manual (Doc 9157), Part 3.

13.1.3.2 Runway Shoulders

(a) General

- (1) The Aerodrome Operator shall ensure that Runway shoulders shall be provided for a runway where the code letter is D, E or F.

(b) Width of runway shoulders

- (1) For aeroplanes with OMGWS from 9 m up to but not including 15 m, the runway shoulders shall extend symmetrically on each side of the runway so that the overall width of the runway and its shoulders is not less than:

- (i) 60 m where the code letter is D or E;
- (ii) 60 m where the code letter is F with two or three engined aeroplanes; and
- (iii) 75 m where the code letter is F, with four or more engined aeroplanes.

(c) Slopes on runway shoulders

- (1) The Aerodrome Operator shall ensure that surface of the shoulder that abuts the runway shall be flush with the surface of the runway and its transverse slope shall not exceed 2.5 per cent.

(d) Strength of runway shoulders

- (1) The Aerodrome Operator shall ensure that the portion of a runway shoulder between the runway edge and a distance of 30 m from the runway centerline shall be prepared or constructed so as to be capable, in the event of an aeroplane running off the runway, of supporting the aeroplane without inducing structural damage to the aeroplane and of supporting ground vehicles which may operate on the shoulder.

Note. — Guidance on strength of runway shoulders is given in the Aerodrome Design Manual (Doc 9157), Part 1.

(e) Surface of runway shoulders

- (1) The Aerodrome Operator shall ensure that a runway shoulder is prepared or constructed so as to resist erosion and the ingestion of the surface material by aeroplane engines.
- (2) The Aerodrome Operator shall ensure that runway shoulder for code letter F aeroplanes should be paved to a minimum overall width of runway and shoulder of not less than 60m.

Note. Guidance on surface of runway shoulders is given in the aerodrome design manual (Doc 9157) Part 1.

13.1.3.3 Runway Turn Pads

(a) General

- (1) The Aerodrome Operator shall ensure that where the end of a runway is not served by a taxiway or a taxiway turnaround and where the code letter is D, E or F, a runway turn pad shall be provided to facilitate a 180-degree turn of aeroplanes. (See Figure 13.1.3-1.)




Figure 13.1.3-1: Typical Turn Pad Layout

- (2) Where the end of a runway is not served by a taxiway or a taxiway turnaround and where the code letter is A, B or C, a runway turn pad shall be provided to facilitate a 180-degree turn of aeroplanes.

Note 1. — Such areas may also be useful if provided along a runway to reduce taxiing time and distance for aeroplanes which may not require the full length of the runway.

Note 2. — Guidance on the design of the runway turn pads is available in the Aerodrome Design Manual (Doc 9157), Part 1. Guidance on taxiway turnaround as an alternate facility is available in the Aerodrome Design Manual (Doc 9157), Part 2.

- (3) The Aerodrome Operator shall ensure that runway turn pad shall be located on either the left or right side of the runway and adjoining the runway pavement at both ends of the runway and at some intermediate locations where deemed necessary.

Note. — The initiation of the turn would be facilitated by locating the turn pad on the left side of the runway, since the left seat is the normal position of the pilot-in-command.

- (4) The Aerodrome Operator shall ensure that intersection angle of the runway turn pad with the runway shall not exceed 30 degrees.
- (5) The Aerodrome Operator shall ensure that the nose wheel steering angle to be used in the design of the runway turn pad shall not exceed 45 degrees.
- (6) the aerodrome operator shall ensure that the design of a runway turn pad shall be such that, when the cockpit of the aeroplane for which the turn pad is intended remains over the turn pad marking, the clearance distance between any wheel of the aeroplane landing gear and the edge of the turn pad shall be not less than that given by the following tabulation:

OMGWS				
	Up to but not including 4.5 m	4.5 m up to but not including 6 m	6 m up to but not including 9 m	9 m up to but not including 15 m
Clearance	1.50 m	2.25 m	3 m ^a or 4 m ^b	4 m

^a *If the turn pad is intended to be used by aeroplanes with a wheel base less than 18 m.*

^b *If the turn pad is intended to be used by aeroplanes with a wheel base equal to or greater than 18 m.*

Note. — Wheel base means the distance from the nose gear to the geometric center of the main gear.

(b) Slopes on runway turn pads

- (1) The Aerodrome Operator shall ensure that longitudinal and transverse slopes on a runway turn pad shall be sufficient to prevent the accumulation of water on the surface and facilitate rapid drainage of surface water. The slopes shall be the same as those on the adjacent runway pavement surface.

(c) Strength of runway turn pads

- (1) The Aerodrome Operator shall ensure that strength of a runway turn pad shall be at least equal to that of the adjoining runway which it serves, due consideration being given to the fact that the turn pad will be subjected to slow-moving traffic making hard turns and consequent higher stresses on the pavement.

Note. — Where a runway turn pad is provided with flexible pavement, the surface would need to be capable of withstanding the horizontal shear forces exerted by the main landing gear tires during turning maneuvers.

(d) Surface of runway turn pads

- (1) The Aerodrome Operator shall ensure that the surface of a runway turn pad shall not have surface irregularities that may cause damage to an aeroplane using the turn pad.
- (2) The surface of a runway turn pad shall be so constructed or resurfaced as to provide surface friction characteristics at least equal to that of the adjoining runway.

(e) Shoulders for runway turn pads

- (1) The Aerodrome Operator shall ensure that the runway turn pads shall be provided with shoulders of such width as is necessary to prevent surface erosion by the jet blast of the most demanding aeroplane for which the turn pad is intended, and any possible foreign object damage to the aeroplane engines.

Note. — As a minimum, the width of the shoulders would need to cover the outer engine of the most demanding aeroplane and thus may be wider than the associated runway shoulders.

- (2) The strength of runway turn pad shoulders shall be capable of withstanding the occasional passage of the aeroplane it is designed to serve without inducing structural damage to the aeroplane and to the supporting ground vehicles that may operate on the shoulder.

13.1.3.4 Runway Strips

(a) General

The Aerodrome Operator shall ensure that a runway and any associated stopways shall be included in a strip.

(b) Length of runway strips

- (1) The Aerodrome Operator shall ensure that a strip shall extend before the threshold and beyond the end of the runway or stopway for a distance of at least:
 - (i) 60 m where the code number is 2, 3 or 4;
 - (ii) 60mwherethecodenumberis1andtherunwayisaninstrumentone;and
 - (iii) 30mwherethecodenumberis1andtherunwayisanon-instrumentone

(c) Width of runway strips

- (1) The Aerodrome Operator shall ensure that a strip including a precision approach runway shall, wherever practicable, extend laterally to a distance of atleast:
 - (i) 140 m where the code number is 3 or 4;and
 - (ii) 70 m where the code number is 1 or2;

on each side of the center line of the runway and its extended center line throughout the length of the strip.

- (2) A strip including a non-precision approach runway shall extend laterally to a distance of atleast:
 - (i) 140 m where the code number is 3 or 4; and
 - (ii) 70 m where the code number is 1 or2;

on each side of the center line of the runway and its extended center line throughout the length of the strip.

- (3) A strip including a non-instrument runway shall extend on each side of the center line of the runway and its extended center line throughout the length of the strip, to a distance of atleast:
 - (i) 75 m where the code number is 3 or 4;
 - (ii) 40 m where the code number is 2; and
 - (iii) 30 m where the code number is1.

(d) Objects on runway strips

- (1) The Aerodrome Operator shall ensure that an object situated on a runway strip which may endanger aeroplanes shall be regarded as an obstacle and shall, as far as practicable, be removed.

Note 1. — See 13.1.9.9 for information regarding siting of equipment and installations on runway strips.

Note 2. — Consideration will have to be given to the location and design of drains on a runway strip to prevent damage to an aeroplane accidentally running off a runway. Suitably designed drain covers may be required. For further guidance, see the Aerodrome Design Manual (Doc 9157), Part 1.

Note 3. — Where open-air or covered storm water conveyances are installed, consideration will have to be given to ensure that their structure does not extend above the surrounding ground so as not to be considered an obstacle. See also Note 1 to 13.1.3.4(f)(3)(ii).

Note 4. — Particular attention needs to be given to the design and maintenance of an open-air storm water conveyance in order to prevent wildlife attraction, notably birds. If needed, it can be covered by a net. Guidance on wildlife control and reduction can be found GM-AGA009. Further guidance can be found PANS-Aerodromes (Doc 9981) and in the Airport Services Manual (Doc 9137), Part 3.

- (2) No fixed object, other than visual aids required for air navigation or those required for aircraft safety purposes and which are sited on the runway strip, and satisfying the relevant frangibility requirement, shall be permitted on any part of a runway strip of a precision approach runway delineated by the lower edges of the inner transitional surfaces
- (3) The Aerodrome Operator shall ensure that No mobile object shall be permitted on this part of the runway strip during the use of the runway for landing or take-off.

(e) Grading of runway strips

- (1) The Aerodrome Operator shall ensure that:

- (i) That portion of a strip of an instrument runway within a distance of at least:

- (A) 75 m where the code number is 3 or 4; and

- (B) 40 m where the code number is 1 or 2;

from the center line of the runway and its extended center line shall provide a graded area for aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

Note. — Guidance on grading of a greater area of a strip including a precision approach runway where the code number is 3 or 4 is given in Appendix A, Section 9.

- (ii) That portion of a strip of a non-instrument runway within a distance of at least:

- (A) 75m where the code number is 3 or 4;

- (B) 40 m where the code number is 2; and

- (C) 30 m where the code number is 1;

from the center line of the runway and its extended center line shall provide a graded area for aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

- (iii) The surface of that portion of a strip that abuts a runway, shoulder or stopway shall be flush with the surface of the runway, shoulder or stopway.
- (iv) That portion of a strip to at least 30 m before the start of a runway shall be prepared against blast erosion in order to protect a landing aeroplane

from the danger of an exposed edge.

Note 1. — Guidance on protection against aeroplane engine blast is available in the Aerodrome Design Manual (Doc 9157), Part 2.

- (2) Where the areas in (iv) above have paved surfaces, the Aerodrome Operator shall ensure that they shall be able to withstand the occasional passage of the critical aeroplane for runway pavement design.

(f) Slopes on runway strips

- (1) **Longitudinal slopes:** A longitudinal slope along that portion of a strip to be graded shall not exceed:

- (i) 1.5 per cent where the code number is 4;
- (ii) 1.75 per cent where the code number is 3; and
- (iii) 2 per cent where the code number is 1 or 2.

- (2) **Longitudinal slope changes:** Slope changes on that portion of a strip to be graded shall be as gradual as practicable and abrupt changes or sudden reversals of slopes avoided.

(3) **Transverse slopes**

- (i) Transverse slopes on that portion of a strip to be graded shall be adequate to prevent the accumulation of water on the surface but should not exceed:

- (A) 2.5 per cent where the code number is 3 or 4; and
- (B) 3 per cent where the code number is 1 or 2;

except that to facilitate drainage the slope for the first 3 m outward from the runway, shoulder or stopway edge should be negative as measured in the direction away from the runway and may be as great as 5 per cent.

- (ii) The transverse slopes of any portion of a strip beyond that to be graded shall not exceed an upward slope of 5 per cent as measured in the direction away from the runway.

Note 1. — Where deemed necessary for proper drainage, an open-air storm water conveyance may be allowed in the non-graded portion of a runway strip and would be placed as far as practicable from the runway.

Note 2. — The aerodrome rescue and firefighting (RFF) procedure would need to take into account the location of open air water conveyances within the non-graded portion of a runway strip.

(g) Strength of runway strips

- (1) The Aerodrome Operator shall ensure that:
- (i) That portion of a strip of an instrument runway within a distance of at least:

- (A) 75 m where the code number is 3 or 4; and
- (B) 40 m where the code number is 1 or 2;

from the center line of the runway and its extended center line shall be so prepared or constructed as to minimize hazards arising from differences in load-bearing capacity to aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

Note. — *Guidance on preparation of runway strips is given in the Aerodrome Design Manual (Doc 9157), Part 1.*

- (ii) That portion of a strip containing a non-instrument runway within a distance of at least:
 - (A) 75mwherethecodenumberis3or4;
 - (B) 40 m where the code number is 2; and
 - (C) 30 m where the code number is 1,

from the center line of the runway and its extended center line shall be so prepared or constructed as to minimize hazards arising from differences in load-bearing capacity to aeroplanes which the runway is intended to serve in the event of an aeroplane running off the runway.

13.1.3.5 Runway End Safety Areas

(a) General

- (1) A runway end safety area shall be provided at each end of a runway strip where:
 - (i) the code number is 3 or 4; and
 - (ii) the code number is 1 or 2 and the runway is an instrument one.

Note — *Guidance on runway end safety areas is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 11.*

- (2) A runway end safety area shall be provided at each end of a runway strip where the code number is 1 or 2 and the runway is a non-instrument one.

(b) Dimensions of runway end safety areas

- (1) The Aerodrome Operator shall ensure that a runway end safety area shall extend from the end of a runway strip to a distance of at least 90 m where:
 - (i) the code number is 3 or 4; and
 - (ii) the code number is 1 or 2 and the runway is an instrument one.

If an arresting system is installed, the above length may be reduced, based on the design specification of the system, subject to acceptance by Authority.

- (2) A runway end safety area may, as far as practicable, extend from the end of a runway strip to a distance of at least:

- (i) 240 m where the code number is 3 or 4; or a reduced length when an arresting system is installed;
 - (ii) 120 m where the code number is 1 or 2 and the runway is an instrument one; or a reduced length when an arresting system is installed; and
 - (iii) 30 m where the code number is 1 or 2 and the runway is a non-instrument one.
- (3) The width of a runway end safety area shall be at least twice that of the associated runway.
 - (4) The width of a runway end safety area may, wherever practicable, be equal to that of the graded portion of the associated runway strip.

Note.— *Guidance on arresting systems is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 11.*

(c) Objects on runway end safety areas

- (1) An object situated on a runway end safety area which may endanger aeroplanes shall be regarded as an obstacle and shall, as far as practicable, be removed.

Note. — *See 13.1.9.9 for information regarding siting of equipment and installations on runway end safety areas*

(d) Clearing and grading of runway end safety areas

- (1) The Aerodrome Operator shall ensure that a runway end safety area shall provide a cleared and graded area for aeroplanes which the runway is intended to serve in the event of an aeroplane undershooting or overrunning the runway.

Note. — *The surface of the ground in the runway end safety area does not need to be prepared to the same quality as the runway strip. See, however, 13.1.3.5(e)(4).*

(e) Slopes on runway end safety areas

- (1) **General:** The slopes of a runway end safety area shall be such that no part of the runway end safety area penetrates the approach or take-off climb surface
- (2) **Longitudinal slopes:** The longitudinal slopes of a runway end safety area shall not exceed a downward slope of 5 per cent. Longitudinal slope changes shall be as gradual as practicable and abrupt changes or sudden reversals of slopes avoided.
- (3) **Transverse slopes:** The transverse slopes of a runway end safety area shall not exceed an upward or downward slope of 5 per cent. Transitions between differing slopes should be as gradual as practicable.
- (4) **Strength of runway end safety areas:** A runway end safety area shall be so prepared or constructed as to reduce the risk of damage to an aeroplane undershooting or overrunning the runway, enhance aeroplane deceleration and facilitate the movement of rescue and firefighting vehicles as required in 13.1.9.2 (f)(1) to 13.1.9.2 (f)(3).

Note. — *Guidance on the strength of a runway end safety area is given in AC 14-021. Further guidance can be found in the Aerodrome Design Manual (Doc 9157), Part 1.*

13.1.3.6 Clearways

Note — The inclusion of detailed specifications for clearways in this section is not intended to imply that a clearway has to be provided in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 2 provides information on the use of clearways.

- (a) The Authority shall ensure that no person undertakes any activity within the clear zones of any aerodrome from both ends of the runways at a distance less than 1000 m by 1000 m from the runway threshold, unless otherwise approved by the Authority based on aeronautical assessment.
- (1) **Location of clearways:** The Aerodrome Operator shall ensure that the origin of a clearway shall be at the end of the take-off run available.
 - (2) **Length of clearways:** The length of a clearway shall not exceed half the length of the take-off run available.
 - (3) **Width of clearways:** A clearway shall extend laterally on each side of the extended center line of the runway to a distance of at least:
 - (i) 75 m for instrument runways; and
 - (ii) half of the width of the runway strip for non-instrument runways.
 - (4) **Slopes on clearways:** The ground in a clearway shall not project above plane having an upward slope of 1.25 percent, the lower limit of this plane being a horizontal line which:
 - (iii) is perpendicular to the vertical plane containing the runway center line; and
 - (iv) passes through a point located on the runway centerline at the end of the take-off run available.

Note. — Because of transverse or longitudinal slopes on a runway, shoulder or strip, in certain cases the lower limit of the clearway plane specified above may be below the corresponding elevation of the runway, shoulder or strip. It is not intended that these surfaces be graded to conform with the lower limit of the clearway plane nor is it intended that terrain or objects which are above the clearway plane beyond the end of the strip but below the level of the strip be removed unless it is considered they may endanger aeroplanes.

 - (v) Abrupt upward changes in slope shall be avoided when the slope on the ground in a clearway is relatively small or when the mean slope is upward. In such situations, in that portion of the clearway within a distance of 22.5 m or half the runway width whichever is greater on each side of the extended center line, the slopes, slope changes and the transition from runway to clearway shall generally conform with those of the runway with which the clearway is associated.
 - (5) **Objects on clearways:** An object situated on a clearway which may endanger aeroplanes in the air shall be regarded as an obstacle and should be removed.

Note. — See 14.9.9 for information regarding siting of equipment and installations on clearways.

13.1.3.7 Stopways

Note — The inclusion of detailed specifications for stopways in this section is not intended to imply that a stopway has to be provided. Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 2 provides information on the use of stopways.

- (a) **Width of stopways:** The Aerodrome Operator shall ensure that a stopway shall have the same width as the runway with which it is associated.
- (b) **Slopes on stopways:** Slopes and changes in slope on a stopway, and the transition from a runway to a stopway, shall comply with the specifications of 13.1.3.1(h)(1) to 13.1.3.1(h)(5) for the runway with which the stopway is associated except that:
 - (1) the limitation in 14.3.1.14 of a 0.8 per cent slope for the first and last quarter of the length of a runway need not be applied to the stopway; and
 - (2) at the junction of the stopway and runway and along the stopway the maximum rate of slope change may be 0.3 per cent per 30 m (minimum radius of curvature of 10 000 m) for a runway where the code number is 3 or 4.
- (c) **Strength of stopways**
 - (1) A stopway shall be prepared or constructed so as to be capable, in the event of an abandoned take-off, of supporting the aeroplane which the stopway is intended to serve without inducing structural damage to the aeroplane.

Note — Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 2 presents guidance relative to the support capability of a stopway.

- (d) **Surface of stopways**
 - (1) The surface of a paved stopway shall be so constructed or resurfaced as to provide surface friction characteristics at or above those of the associated runway.

13.1.3.8 Radio Altimeter Operating Area

- (a) **General.** A radio altimeter operating area shall be established in the pre-threshold area of a precision approach runway.
- (b) **Length of the area.** A radio altimeter operating area shall extend before the threshold for a distance of at least 300m.
- (c) **Width of the area.** A radio altimeter operating area shall extend laterally, on each side of the extended center line of the runway, to a distance of 60 m, except that, when special circumstances so warrant, the distance may be reduced to no less than 30 m if an aeronautical study indicates that such reduction would not affect the safety of operations of aircraft.
- (d) **Longitudinal slope changes.** Aerodrome Operator shall ensure that on a radio altimeter operating area, slope changes shall be avoided or kept to a minimum. Where slope changes cannot be avoided, the slope changes shall be as gradual as practicable and abrupt changes or sudden reversals of slopes avoided. The rate of change between two consecutive slopes shall not exceed 2 per cent per 30 m.

Note. — Guidance on radio altimeter operating area is given in Attachment A, Section 4.3, and in the Manual of All- Weather Operations, (Doc 9365), Section 5.2. Guidance on the use of radio altimeter is given in the PANS-OPS, Volume II, Part II, Section 1.

13.1.3.9 Taxiways

Note 1 — Unless otherwise indicated the requirements in this section are applicable to all types of taxiways.

Note 2. — See section 13.1.5.4(c). for a standardized scheme for the nomenclature of taxiways which may be used to improve situational awareness

Note 3. — Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 23 for specific taxiway design guidance which may assist in the prevention of runway incursions when developing a new taxiway or improving existing ones with a known runway incursion safety risk

(a) General

- (1) The Aerodrome Operator shall ensure that taxiways shall be provided to permit the safe and expeditious surface movement of aircraft.

Note. — Guidance on layout and standardized nomenclature of taxiways is given in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2. — See Attachment A, Section 22, for specific taxiway design guidance which may assist in the prevention of runway incursions when developing a new taxiway or improving existing ones with known runway incursion safety risks.

- (2) Sufficient entrance and exit taxiways for a runway shall be provided to expedite the movement of aeroplanes to and from the runway and provision of rapid exit taxiways considered when traffic volumes are high.
- (3) The design of a taxiway shall be such that, when the cockpit of the aeroplane for which the taxiway is intended remains over the taxiway center line markings, the clearance distance between the outer main wheel of the aeroplane and the edge of the taxiway shall be not less than that given by the following tabulation:

OMGWS				
	Up to but not including 4.5 m	4.5 m up to but not including 6 m	6 m up to but not including 9 m	9 m up to but not including 15 m
Clearance	1.50 m	2.25 m	3 m ^{a,b} or 4 m ^c	4 m

^a On straight portions.

^b On curved portions if the taxiway is intended to be used by aeroplanes with a wheel base of less than 18 m.

^c On curved portions if the taxiway is intended to be used by aeroplanes with a wheel base equal to or greater than 18 m.

Note. — Wheel base means the distance from the nose gear to the geometric centre of the main gear.

- (b) **Width of taxiways.** The Aerodrome Operator shall ensure that a straight portion of a taxiway shall have a width of not less than that given by the following tabulation:

Taxiway width	OMGWS			
	Up to but not including 4.5 m	4.5 m up to but not including 6 m	6 m up to but not including 9 m	9 m up to but not including 15 m
	7.5 m	10.5 m	15 m	23 m

Note. — Guidance on width of taxiways is given in the Aerodrome Design Manual (Doc 9157), Part 2.

- (c) **Taxiway curves.** The Aerodrome Operator shall ensure that changes in direction of taxiways shall be as few and small as possible. The radii of the curves shall be compatible with the maneuvering capability and normal taxiing speeds of the aeroplane for which the taxiway is intended. The design of the curve shall be such that, when the cockpit of the aeroplane remains over the taxiway center line markings, the clearance distance between the outer main wheels of the aeroplane and the edge of the taxiway shall not be less than those specified in 13.1.3.9(a)(3).

Note 1. — An example of widening taxiways to achieve the wheel clearance specified is illustrated in Figure 13.1.3-2. Guidance on the values of suitable dimensions is given in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2. — The location of taxiway center line markings and lights is specified in 13.1.5.1(h)(2)(i) and 13.1.5.3 (r)(3).

Note 3. — Compound curves may reduce or eliminate the need for extra taxiway width.




Figure: 13.1.3-2: Taxiway curve

- (d) Junctions and intersections. To facilitate the movement of aeroplanes, the Aerodrome Operator shall ensure that fillets shall be provided at junctions and intersections of taxiways with runways, aprons and other taxiways. The design of the fillets shall ensure that the minimum wheel clearances specified in 14.3.9.3 are maintained when aeroplanes are maneuvering through the junctions or intersections.

Note. — Consideration will have to be given to the aeroplane datum length when designing fillets. Guidance on the design of fillets and the definition of the term aeroplane datum length are given in the Aerodrome Design Manual (Doc 9157), Part 2.

- (e) **Taxiway minimum separation distances.** The separation distance between the center line of a taxiway and the center line of a runway, the center line of a parallel taxiway or an object shall not be less than the appropriate dimension specified in Table 13.1.3-1, except that it may be permissible to operate with lower separation distances at an existing aerodrome if an aeronautical study indicates that such lower separation distances would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes

Note 1. — Guidance on factors which may be considered in the aeronautical study is given in AC 14-007. Further guidance can be found in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2. — ILS and MLS installations may also influence the location of taxiways due to interferences to ILS and MLS signals by a taxiing or stopped aircraft. Information on critical and sensitive areas surrounding ILS and MLS installations is contained in Annex 10 — Aeronautical Telecommunications, Volume I — Radio Navigation Aids, Attachments C and G (respectively).

Note 3. — The separation distances of Table 3-1, column 10, do not necessarily provide the capability of making a normal turn from one taxiway to another parallel taxiway. Guidance for this condition is given in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 4. — The separation distance between the center line of an aircraft stand taxiway and an object shown in Table 3-1, column 13, may need to be increased when jet exhaust wake velocity may cause hazardous conditions for ground servicing.

(f) **Slopes on taxiways**

- (1) **Longitudinal slopes:** The longitudinal slope of a taxiway shall not exceed:

- (i) 1.5 per cent where the code letter is C, D, E or F; and
- (ii) 3 per cent where the code letter is A or B.

- (2) **Longitudinal slope changes:** Where slope changes on a taxiway cannot be avoided, the transition from one slope to another slope shall be accomplished by a curved surface with a rate of change not exceeding:

- (i) 1 per cent per 30 m (minimum radius of curvature of 3 000 m) where the code letter is C, D, E or F; and
- (ii) 1 per cent per 25 m (minimum radius of curvature of 2 500 m) where the code letter is A or B.

Table 13.1.3-1. Taxiway minimum separation distances

Code letter	Distance between taxiway centre line and runway centre line (metres)								Taxiway centre line to taxiway centre line (metres)	Taxiway, other than aircraft stand taxilane, centre line to object (metres)	Aircraft stand centre line to aircraft stand taxilane centre line (metres)	Aircraft stand taxilane centre line to object (metres)
	Instrument runways				Non-instrument runways							
	Code number	Code number	Code number	Code number	Code number	Code number	Code number	Code number				
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)
A	77.5	77.5	–	–	37.5	47.5	–	–	23	15.5	19.5	12
B	82	82	152	–	42	52	87	–	32	20	28.5	16.5
C	88	88	158	158	48	58	93	93	44	26	40.5	22.5
D	–	–	166	166	–	–	101	101	63	37	59.5	33.5
E	–	–	172.5	172.5	–	–	107.5	107.5	76	43.5	72.5	40
F	–	–	180	180	–	–	115	115	91	51	87.5	47.5

Note 1.— The separation distances shown in columns (2) to (9) represent ordinary combinations of runways and taxiways. The basis for development of these distances is given in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2.— The distances in columns (2) to (9) do not guarantee sufficient clearance behind a holding aeroplane to permit the passing of another aeroplane on a parallel taxiway. See the Aerodrome Design Manual (Doc 9157), Part 2.

- (3) **Sight distance:** Where a change in slope on a taxiway cannot be avoided, the change shall be such that, from any point:
- (i) 3 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 300 m from that point, where the code letter is C, D, E or F;
 - (ii) 2 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 200 m from that point, where the code letter is B; and
 - (iii) 1.5 m above the taxiway, it will be possible to see the whole surface of the taxiway for a distance of at least 150 m from that point, where the code letter is A.
- (4) **Transverse slopes:** The transverse slopes of a taxiway shall be sufficient to prevent the accumulation of water on the surface of the taxiway but shall not exceed:
- (i) 1.5 per cent where the code letter is C, D, E or F; and
 - (ii) 2 per cent where the code letter is A or B.

Note. — See 13.1.3.13 (d)(1) regarding transverse slopes on an aircraft stand taxilane.

(g) Strength of taxiways

- (1) The Aerodrome Operator shall ensure that strength of a taxiway shall be at least equal to that of the runway it serves, due consideration being given to the fact that a taxiway will be subjected to a greater density of traffic and, as a

result of slow moving and stationary aeroplanes, to higher stresses than the runway it serves.

Note. — Guidance on the relation of the strength of taxiways to the strength of runways is given in the Aerodrome Design Manual (Doc 9157), Part 3.

(h) Surface of taxiways

- (1) The Aerodrome Operator shall ensure that the surface of a taxiway shall not have irregularities that cause damage to aeroplane structures.
- (2) The surface of a paved taxiway shall be so constructed or resurfaced as to provide suitable surface friction characteristics.

(i) Rapid exit taxiways

- (1) A rapid exit taxiway shall be designed with a radius of turn-off curve of at least:
 - (i) 550 m where the code number is 3 or 4; and
 - (ii) 275mwherethecodenumberis1or2; to enable exit speeds under wet conditions of:
 - (A) 93 km/h where the code number is 3 or 4; and
 - (B) 65 km/h where the code number is 1 or 2.

Note 1. See Figure 1.1.3-3. General requirements for taxiways also apply to this type of taxiway. Guidance on the provision, location and design of rapid exit taxiways is included in the Aerodrome Design Manual (Doc 9157), Part 2.

Note 2. — The locations of rapid exit taxiways along a runway are based on several criteria described in the Aerodrome Design Manual (Doc 9157), Part 2, in addition to different speed criteria.

- (2) The radius of the fillet on the inside of the curve at a rapid exit taxiway shall be sufficient to provide a widened taxiway throat in order to facilitate early recognition of the entrance and turn-off onto the taxiway.
- (3) A rapid exit taxiway shall include a straight distance after the turn-off curve sufficient for an exiting aircraft to come to a full stop clear of any intersecting taxiway.
- (4) The intersection angle of a rapid exit taxiway with the runway shall not be greater than 45° nor less than 25° and preferably should be 30°.




Figure 13.1.3-3. Rapid exit taxiway

(j) Taxiways on bridges

- (1) The Aerodrome Operator shall ensure that the width of that portion of a taxiway bridge capable of supporting aeroplanes, as measured perpendicularly to the taxiway center line, shall not be less than the width of the graded area of the strip provided for that taxiway, unless a proven method of lateral restraint is provided which shall not be hazardous for aeroplanes for which the taxiway is intended.
- (2) Access shall be provided to allow rescue and firefighting vehicles to intervene in both directions within the specified response time to the largest aeroplane for which the taxiway bridge is intended.

Note. — If aeroplane engines overhang the bridge structure, protection of adjacent areas below the bridge from engine blast may be required.

- (3) A bridge shall be constructed on a straight section of the taxiway with a straight section on both ends of the bridge to facilitate the alignment of aeroplanes approaching the bridge.

13.1.3.10 Taxiway Shoulders

- (a)** The Aerodrome Operator shall ensure that straight portions of a taxiway where the code letter is C, D, E or F, shall be provided with shoulders which extend symmetrically on each side of the taxiway so that the overall width of the taxiway and its shoulders on straight portions is not less than:

- (1) 44 m where the code letter is F;
- (2) 38 m where the code letter is E;
- (3) 34 m where the code letter is D; and
- (4) 25 m where the code letter is C.

On taxiway curves and on junctions or intersections where increased pavement is provided, the shoulder width shall be not less than that on the adjacent straight portions of the taxiway.

Note. — *Guidance on characteristics of taxiway shoulders and on shoulder treatment is given in the Aerodrome Design Manual (Doc 9157), Part 2.*

- (b) When a taxiway is intended to be used by turbine-engined aeroplanes, the surface of the taxiway shoulder shall be so prepared as to resist erosion and the ingestion of the surface material by aeroplane engines.

13.1.3.11 Taxiway Strips

- (a) **General.** The Aerodrome Operator shall ensure that a taxiway, other than an aircraft stand taxilane, shall be included in a strip.

Note.— *Guidance on characteristics of taxiway strips is given in the Aerodrome Design Manual (Doc 9157), Part 2.*

- (b) **Width of taxiway strips.** A taxiway strip shall extend symmetrically on each side of the center line of the taxiway throughout the length of the taxiway to at least the distance from the center line given in Table 13.13-1, column 11.

- (c) **Objects on taxiway strips.** The taxiway strip shall provide an area clear of objects which may endanger taxiing aeroplanes.

Note 1. — *See 13.1.9.9 for information regarding siting of equipment and installations on taxiway strips.*

Note 2. — *Consideration will have to be given to the location and design of drains on a taxiway strip to prevent damage to an aeroplane accidentally running off a taxiway. Suitably designed drain covers may be required. For further guidance, see the Aerodrome Design Manual (Doc 9157), Part 2.*

Note 3. — *Where open-air or covered storm water conveyances are installed, consideration will have to be given to ensure that their structure does not extend above the surrounding ground so as not to be considered an obstacle. See also Note 1 to 13.1.3.11(e)(2).*

Note 4. — *Particular attention needs to be given to the design and maintenance of an open-air storm water conveyance in order to prevent wildlife attraction, notably birds. If needed, it can be covered by a net. Guidance on wildlife control and reduction can be found in the Airport Services Manual (Doc 9137), Part 3.*

- (d) **Grading of taxiway strips.** The center portion of a taxiway strip shall provide a graded area to a distance from the center line of the taxiway of not less than that given by the following tabulation:

- (1) 10.25 m where the OMGWS is up to but not including 4.5m
- (2) 11 m where the OMGWS is 4.5 m up to but not including 6 m;
- (3) 12.50 m where the OMGWS is 6 m up to but not including 9m;

- (4) 18.50 m where the OMGWS is 9 m up to but not including 15 m, where the code letter is D;
- (5) 19 m where the OMGWS is 9 m up to but not including 15 m where the code letter is E; and
- (6) 22 m where the OMGWS is 9 m up to but not including 15 m, where the code letter is F.

Note --- Guidance on width of graded portion of the taxiway is given in the Aerodrome Design Manual (Doc 9157) Part 2.

(e) Slopes on taxiway strips

- (1) The surface of the strip shall be flush at the edge of the taxiway or shoulder, if provided, and the graded portion shall not have an upward transverse slope exceeding:
 - (i) 2.5 per cent for strips where the code letter is C, D, E or F; and
 - (ii) 3 per cent for strips of taxiways where the code letter is A or B;

the upward slope being measured with reference to the transverse slope of the adjacent taxiway surface and not the horizontal. The downward transverse slope shall not exceed 5 per cent measured with reference to the horizontal.

- (2) The transverse slopes on any portion of a taxiway strip beyond that to be graded shall not exceed an upward or downward slope of 5 per cent as measured in the direction away from the taxiway.

Note 1. — Where deemed necessary for proper drainage, an open-air storm water conveyance may be allowed in the non-graded portion of a taxiway strip and would be placed as far as practicable from the taxiway.

Note 2. — The aerodrome RFF procedure would need to take into account the location of open-air storm water conveyances within the non-graded portion of a taxiway strip.

13.1.3.12 Holding Bays, Runway-Holding Positions, Intermediate Holding Positions And Road-Holding Positions

(a) General

- (1) The Aerodrome Operator shall ensure that holding bay(s) shall be provided when the traffic density is medium or heavy.
- (2) A runway-holding position or positions shall be established:
 - (i) on the taxiway, at the intersection of a taxiway and a runway; and
 - (ii) at an intersection of a runway with another runway when the former runway is part of a standard taxi-route.
- (3) A runway-holding position shall be established on a taxiway if the location or alignment of the taxiway is such that a taxiing aircraft or vehicle can infringe an obstacle limitation surface or interfere with the operation of radio navigation aids.

- (4) An intermediate holding position shall be established on a taxiway at any point other than a runway-holding position where it is desirable to define a specific holding limit.
- (5) A road-holding position shall be established at an intersection of a road with a runway.

(b) Location

- (1) The distance between a holding bay, runway-holding position established at a taxiway/runway intersection or road-holding position and the center line of a runway shall be in accordance with Table 13.1.3-2 and, in the case of a precision approach runway, such that a holding aircraft or vehicle will not interfere with the operation of radio navigation aids or penetrate the inner transitional surface.

Note – Guidance for the positioning of runway holding positions is given in Aerodrome Design Manual (Doc 9157) Part 2

- (2) At elevations greater than 700 m (2 300 ft) the distance of 90 m specified in Table 13.1.3-2 for a precision approach runway code number 4 shall be increased as follows:
 - (i) up to an elevation of 2 000 m (6 600 ft); 1 m for every 100 m (330 ft) in excess of 700 m (2 300 ft);
 - (ii) elevation in excess of 2 000 m (6 600 ft) and up to 4 000 m (13 320 ft); 13 m plus 1.5 m for every 100 m (330 ft) in excess of 2 000 m (6 600 ft);and
 - (iii) elevation in excess of 4 000 m (13 320 ft) and up to 5 000 m (16 650 ft); 43 m plus 2 m for every 100 m (330 ft) in excess of 4 000 m (13 320ft).
- (3) If a holding bay, runway-holding position or road-holding position for a precision approach runway code number 4 is at a greater elevation compared to the threshold, the distance, specified in Table 13.1.3-2 should be further increased 5 m for every meter the bay or position is higher than the threshold.
- (4) The location of a runway-holding position established in accordance with 13.1.12(a)(3) shall be such that a holding aircraft or vehicle will not infringe the obstacle free zone, approach surface, take-off climb surface or ILS/MLS critical/sensitive area or interfere with the operation of radio navigation aids.

Table 13.1.3-2. Minimum distance from the runway center line to a holding bay, runway- holding position or road- holding position

Type of runway	Code number			
	1	2	3	4
Non-instrument	30 m	40 m	75 m	75 m
Non-precision approach	40 m	40 m	75 m	75 m
Precision approach category I	60 m ^b	60 m ^b	90 m ^{a,b}	90 m ^{a,b,c}
Precision approach categories II and III	—	—	90 m ^{a,b}	90 m ^{a,b,c}
Take-off runway	30 m	40 m	75 m	75 m

1. If a holding bay, runway-holding position or road-holding position is at a lower elevation compared to the threshold, the distance may be decreased 5 m for every meter the bay or holding position is lower than the threshold, contingent upon not infringing the inner transitional surface.
2. This distance may need to be increased to avoid interference with radio navigation aids, particularly the glide path and localizer facilities. Information on critical and sensitive areas of ILS and MLS is contained in Annex 10, Volume I, Attachments C and G, respectively (see also 13.1.3.12 (b)(1)).

Note 1.— The distance of 90 m for code number 3 or 4 is based on an aircraft with a tail height of 20 m, a distance from the nose to the highest part of the tail of 52.7 m and a nose height of 10 m holding at an angle of 45° or more with respect to the runway center line, being clear of the obstacle free zone and not accountable for the calculation of OCA/H.

Note 2.— The distance of 60 m for code number 2 is based on an aircraft with a tail height of 8 m, a distance from the nose to the highest part of the tail of 24.6 m and a nose height of 5.2 m holding at an angle of 45° or more with respect to the runway center line, being clear of the obstacle free zone.

3. Where the code letter is F, this distance shall be 107.5 m.

Note 3 — For code number 4 where the width of the inner edge of the inner approach surface is more than 120m, a distance greater than 90m may be necessary to ensure that a holding aircraft is clear of the obstacle free zone. For example a distance of 100m m is based on an aircraft with a tail height of 24 m, a distance from the nose to the highest part of the tail of 62.2 m and a nose height of 10 m holding at an angle of 45° or more with respect to the runway centre line, being clear of the obstacle free zone.

13.1.3.13 Aprons

- (a) **General.** The Aerodrome Operator shall ensure that Aprons shall be provided where necessary to permit the on- and off-loading of passengers, cargo or mail as well as the servicing of aircraft without interfering with the aerodrome traffic.
- (b) **Size of aprons.** The total apron area shall be adequate to permit expeditious handling of the aerodrome traffic at its maximum anticipated density.
- (c) **Strength of aprons.** Each part of an apron shall be capable of withstanding the traffic of the aircraft it is intended to serve, due consideration being given to the fact that some portions of the apron will be subjected to a higher density of traffic and, as a result of slow moving or stationary aircraft, to higher stresses than a runway.
- (d) **Slopes on aprons**
 - (1) Slopes on an apron, including those on an aircraft stand taxilane, shall be sufficient to prevent accumulation of water on the surface of the apron but shall be kept as leveled as drainage requirements permit.
 - (2) On an aircraft stand the maximum slope shall not exceed 1 percent.

(e) Clearance distances on aircraft stands

- (1) The Aerodrome Operator shall ensure that an aircraft stand shall provide the following minimum clearances between an aircraft entering or exiting the stand and any adjacent building, aircraft on another stand and other objects:

CODE LETTER	CLEARANCE
A	3m
B	3m
C	4.5m
D	7.5m
E	7.5m
F	7.5m

- (2) When special circumstances so warrant and subject to the approval of the Authority, these clearances may be reduced at a nose-in aircraft stand, where the code letter is D, E or F:
- (i) between the terminal, including any fixed passenger bridge, and the nose of an aircraft; and
 - (ii) over any portion of the stand provided with azimuth guidance by a visual docking guidance system.

Note. — On aprons, consideration also has to be given to the provision of service roads and to maneuvering and storage area for ground equipment (see the Aerodrome Design Manual (Doc 9157), Part 2, for guidance on storage of ground equipment).

13.1.3.14 Isolated Aircraft Parking Position

- (a)** The Aerodrome Operator shall ensure that an isolated aircraft parking position shall be designated or the aerodrome control tower shall be advised of an area or areas suitable for the parking of an aircraft which is known or believed to be the subject of unlawful interference, or which for other reasons needs isolation from normal aerodrome activities.
- (b)** The isolated aircraft parking position shall be located at the maximum distance practicable and in any case never less than 100 m from other parking positions, buildings or public areas, etc. Care shall be taken to ensure that the position is not located over underground utilities such as gas and aviation fuel and, to the extent feasible, electrical or communication cables.

13.1.4 OBSTACLE RESTRICTION AND REMOVAL

Note 1 – The objectives of the specifications in this chapter are to define the airspace around aerodromes to be maintained free from obstacles so as to permit the intended aeroplane operations at the aerodromes to be conducted safely and to prevent the aerodromes from becoming unusable by the growth of obstacles around the aerodromes. This is achieved by establishing a series of obstacle limitation surfaces that define the limits to which objects may project into the airspace.

Note 2 – Objects which penetrate the obstacle limitation surfaces contained in this chapter may in certain circumstances cause an increase in the obstacle clearance altitude/height for an instrument approach procedure or any associated visual circling procedure or have other operational impact on flight procedure design. Criteria for evaluation of obstacles are contained in Procedures for Air Navigation Services – Aircraft Operations (PANS-OPS) (Doc 8168)

13.1.4.1 Obstacle Limitation Surfaces

(a) Outer horizontal surface

Note. — Guidance on the need to provide an outer horizontal surface and its characteristics is contained in the Airport Services Manual (Doc 9137), Part 6.

(b) Conical surface

- (1) **Description:** A surface sloping upwards and outwards from the periphery of the inner horizontal surface.
- (2) **Characteristics:** The limits of the conical surface shall comprise:
 - (i) a lower edge coincident with the periphery of the inner horizontal surface; and
 - (ii) an upper edge located at a specified height above the inner horizontal surface.
- (3) The slope of the conical surface shall be measured in a vertical plane perpendicular to the periphery of the inner horizontal surface.

(c) Inner horizontal surface

- (1) **Description:** Inner horizontal surface. A surface located in a horizontal plane above an aerodrome and its environs.
- (2) **Characteristics:** The radius or outer limits of the inner horizontal surface shall be measured from a reference point or points established for such purpose.

Note. — The shape of the inner horizontal surface need not necessarily be circular. Guidance on determining the extent of the inner horizontal surface is contained in the Airport Services Manual (Doc 9137), Part 6.

- (3) The height of the inner horizontal surface shall be measured above an elevation datum established for such purpose.

Note. — Guidance on determining the elevation datum is contained in the Airport Services Manual (Doc 9137), Part 6


(d) Approach Surface

- (1) **Description:** Approach surface. An inclined plane or combination of planes preceding the threshold.
- (2) **Characteristics:** The limits of the approach surface shall comprise:
 - (i) an inner edge of specified length, horizontal and perpendicular to the extended center line of the runway and located at a specified distance before the threshold;
 - (ii) two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the extended center line of the runway;
 - (iii) an outer edge parallel to the inner edge; and
 - (iv) the above surfaces shall be varied when lateral offset, offset or curved approaches are utilized, specifically, two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the extended center line of the lateral offset, offset or curved ground track.
- (3) The elevation of the inner edge shall be equal to the elevation of the midpoint of the threshold.
- (4) The slope(s) of the approach surface shall be measured in the vertical plane containing the center line of the runway and shall continue containing the center line of any lateral offset or curved ground track.

Note. — See Figure 13.1.4-2.

(e) Inner approach surface

- (1) **Description:** Inner approach surface. A rectangular portion of the approach surface immediately preceding the threshold.
- (2) **Characteristics:** The limits of the inner approach surface shall comprise:
 - (i) an inner edge coincident with the location of the inner edge of the approach surface but of its own specified length;
 - (ii) two sides originating at the ends of the inner edge and extending parallel to the vertical plane containing the center line of the runway; and
 - (iii) an outer edge parallel to the inner edge



See Figure 4-2 for inner transitional and balked landing obstacle limitation surfaces and Attachment B for a three-dimensional view

Figure 13.1.4-1. Obstacle limitation surfaces




Figure 13.1.4-2. Inner approach, inner transitional and balked landing obstacle limitation surfaces

(f) Transitional surface

- (1) **Description:** Transitional surface. A complex surface along the side of the strip and part of the side of the approach surface, that slopes upwards and outwards to the inner horizontal surface.
- (2) **Characteristics:** The limits of a transitional surface shall comprise:
 - (i) a lower edge beginning at the intersection of the side of the approach surface with the inner horizontal surface and extending down the side of the approach surface to the inner edge of the approach surface and from there along the length of the strip parallel to the runway center line; and
 - (ii) an upper edge located in the plane of the inner horizontal surface.
- (3) The elevation of a point on the lower edge shall be:
 - (i) along the side of the approach surface — equal to the elevation of the

approach surface at that point; and

- (ii) along the strip — equal to the elevation of the nearest point on the center line of the runway or its extension.

Note. — As a result of (ii) the transitional surface along the strip will be curved if the runway profile is curved, or a plane if the runway profile is a straight line. The intersection of the transitional surface with the inner horizontal surface will also be a curved or a straight line depending on the runway profile.

- (4) The slope of the transitional surface shall be measured in a vertical plane at right angles to the center line of the runway.

(g) Inner transitional surface

Note.— It is intended that the inner transitional surface be the controlling obstacle limitation surface for navigation aids, aircraft and other vehicles that must be near the runway and which is not to be penetrated except for frangible objects. The transitional surface described in 13.1.4.1(f) is intended to remain as the controlling obstacle limitation surface for buildings, etc.

- (1) **Description:** Inner transitional surface. A surface similar to the transitional surface but closer to the runway.

- (2) **Characteristics:** The limits of an inner transitional surface shall comprise:

- (i) a lower edge beginning at the end of the inner approach surface and extending down the side of the inner approach surface to the inner edge of that surface, from there along the strip parallel to the runway center line to the inner edge of the balked landing surface and from there up the side of the balked landing surface to the point where the side intersects the inner horizontal surface; and

- (ii) an upper edge located in the plane of the inner horizontal surface.

- (3) The elevation of a point on the lower edge shall be:

- (i) along the side of the inner approach surface and balked landing surface equal to the elevation of the particular surface at that point; and

- (ii) along the strip equal to the elevation of the nearest point on the center line of the runway or its extension.

Note. — As a result of ii) the inner transitional surface along the strip will be curved if the runway profile is curved or a plane if the runway profile is a straight line. The intersection of the inner transitional surface with the inner horizontal surface will also be a curved or straight line depending on the runway profile.

- (4) The slope of the inner transitional surface shall be measured in a vertical plane at right angles to the center line of the runway.

(h) Balked landing surface

- (1) **Description:** Balked landing surface. An inclined plane located at a specified distance after the threshold, extending between the inner transitional surface.

- (2) **Characteristics:** The limits of the balked landing surface shall comprise:

- (i) an inner edge horizontal and perpendicular to the center line of the runway and located at a specified distance after the threshold;
 - (ii) two sides originating at the ends of the inner edge and diverging uniformly at a specified rate from the vertical plane containing the center line of the runway; and
 - (iii) an outer edge parallel to the inner edge and located in the plane of the inner horizontal surface.
- (3) The elevation of the inner edge shall be equal to the elevation of the runway center line at the location of the inner edge.
 - (4) The slope of the balked landing surface shall be measured in the vertical plane containing the center line of the runway.

(i) Take-off climb surface

- (1) **Description:** Take-off climb surface. An inclined plane or other specified surface beyond the end of a runway or clearway.
- (2) **Characteristics:** The limits of the take-off climb surface shall comprise:
 - (i) an inner edge horizontal and perpendicular to the center line of the runway and located either at a specified distance beyond the end of the runway or at the end of the clearway when such is provided and its length exceeds the specified distance;
 - (ii) two sides originating at the ends of the inner edge, diverging uniformly at a specified rate from the take-off track to a specified final width and continuing thereafter at that width for the remainder of the length of the take-off climb surface; and
 - (iii) an outer edge horizontal and perpendicular to the specified take-off-track.
- (3) The elevation of the inner edge shall be equal to the highest point on the extended runway center line between the end of the runway and the inner edge, except that when a clearway is provided the elevation shall be equal to the highest point on the ground on the center line of the clearway.
- (4) In the case of a straight take-off flight path, the slope of the take-off climb surface shall be measured in the vertical plane containing the center line of the runway.
- (5) In the case of a take-off flight path involving a turn, the take-off climb surface shall be a complex surface containing the horizontal normals to its center line, and the slope of the center line shall be the same as that for a straight take-off flight path.

13.1.4.2 Obstacle Limitation Requirements

Note.— The requirements for obstacle limitation surfaces are specified on the basis of the intended use of a runway, i.e. take-off or landing and type of approach, and are intended to be applied when such use is made of the runway. In cases where operations are conducted to or from both directions of a runway, then the function of certain surfaces may be nullified because of more stringent requirements of another lower surface

(a) **General.** The Authority shall ensure that requirements for obstacle limitation surfaces are specified on the basis of the intended use of a runway, i.e. take-off or landing and type of approach, and are intended to be applied when such use is made of the runway. In cases where operations are conducted to or from both directions of a runway, then the function of certain surfaces may be nullified because of more stringent requirements of another lower surface.

(b) **Non-instrument runways**

(1) The Aerodrome Operator shall establish the following obstacle limitation surfaces for a non-instrument runway:

- (i) conical surface;
- (ii) inner horizontal surface;
- (iii) approach surface; and
- (iv) transitional surfaces.

(2) The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 13.1.4-1

(3) New objects or extensions of existing objects shall not be permitted above an approach or transitional surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note. — Circumstances in which the shielding principle may reasonably be applied are in the Airport Services Manual (Doc 9137), Part 6.

(4) New objects or extensions of existing objects shall not be permitted above the conical surface or inner horizontal surface except when, in the opinion of the appropriate authority, the object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

(5) Existing objects above any of the surfaces required by 13.1.4.2(b)(1) shall as far as practicable be removed except when, in the opinion of the appropriate authority, the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

(6) In considering proposed construction, account shall be taken of the possible future development of an instrument runway and consequent requirement for more stringent obstacle limitation surfaces.

(c) **Non-precision approach runways**

(1) The Aerodrome Operator shall establish the following obstacle limitation surfaces for a non-precision approach runway:

- (i) conical surface;
- (ii) inner horizontal surface;
- (iii) approach surface; and

- (iv) transitional surfaces.
- (2) The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 4-1, except in the case of the horizontal section of the approach surface .
- (3) The approach surface shall be horizontal beyond the point at which the 2.5 per cent slope intersects:
 - (i) a horizontal plane 150 m above the threshold elevation; or
 - (ii) the horizontal plane passing through the top of any object that governs the obstacle clearance altitude/height(OCA/H); whichever is the higher.
- (4) New objects or extensions of existing objects shall not be permitted above an approach surface within 3 000 m of the inner edge or above a transitional surface except when the Authority is of the opinion that the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the Airport Services Manual (Doc 9137), Part 6.

Table 13.1.4-1. Dimensions and slopes of obstacle limitation surfaces — Approach runways

Surface and dimensions* (1)	APPROACH RUNWAYS									
	RUNWAY CLASSIFICATION									
	Non-instrument Code number				Non-precision approach Code number			Precision approach category I Code number		
(2)	2 (3)	3 (4)	4 (5)	1,2 (6)	3 (7)	4 (8)	1,2 (9)	3,4 (10)	3,4 (11)	
CONICAL										
Slope	5%	5%	5%	5%	5%	5%	5%	5%	5%	5%
Height	35 m	55 m	75 m	100 m	60 m	75 m	100 m	60 m	100 m	100 m
INNER HORIZONTAL										
Height	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m	45 m
Radius	2 000 m	2 500 m	4 000 m	4 000 m	3 500 m	4 000 m	4 000 m	3 500 m	4 000 m	4 000 m
INNER APPROACH										
Width	—	—	—	—	—	—	—	90 m	120 m ^a	120 m ^a
Distance from threshold	—	—	—	—	—	—	—	60 m	60 m	60 m
Length	—	—	—	—	—	—	—	900 m	900 m	900 m
Slope	—	—	—	—	—	—	—	2.5%	2%	2%
APPROACH										
Length of inner edge	60 m	80 m	150 m	150 m	140 m	280 m	280 m	140 m	280 m	280 m
Distance from threshold	30 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m	60 m
Divergence (each side)	10%	10%	10%	10%	15%	15%	15%	15%	15%	15%
First section										
Length	1 600 m	2 500 m	3 000 m	3 000 m	2 500 m	3 000 m	3 000 m	3 000 m	3 000 m	3 000 m
Slope	5%	4%	3.33%	2.5%	3.33%	2%	2%	2.5%	2%	2%
Second section										
Length	—	—	—	—	—	3 600 m ^b	3 600 m ^b	12 000 m	3 600 m ^b	3 600 m ^b
Slope	—	—	—	—	—	2.5%	2.5%	3%	2.5%	2.5%
Horizontal section										
Length	—	—	—	—	—	8 400 m ^b	8 400 m ^b	—	8 400 m ^b	8 400 m ^b
Total length	—	—	—	—	—	15 000 m	15 000 m	15 000 m	15 000 m	15 000 m
TRANSITIONAL										
Slope	20%	20%	14.3%	14.3%	20%	14.3%	14.3%	14.3%	14.3%	14.3%
INNER TRANSITIONAL										
Slope	—	—	—	—	—	—	—	40%	33.3%	33.3%
BALKED LANDING SURFACE										
Length of inner edge	—	—	—	—	—	—	—	90 m	120 m ^a	120 m ^a
Distance from threshold	—	—	—	—	—	—	—	c	1 800 m ^d	1 800 m ^d
Divergence (each side)	—	—	—	—	—	—	—	10%	10%	10%
Slope	—	—	—	—	—	—	—	4%	3.33%	3.33%

- a. All dimensions are measured horizontally unless specified otherwise.
- b. Variable length (see 13.1.4.2 (c)(2) or 13.1.4.2(d)(5)).
- c. Distance to the end of strip.
- d. Or end of runway whichever is less.
- e. Where the code letter is F (Table 1-1), the width is increased to 140 m except for those aerodromes that accommodate a code letter F aeroplane equipped with digital avionics that provide steering commands to maintain an established track during the go-around maneuvers.

Note.— See Circulars 301 and 345, and Chapter 4 of the PANS-Aerodromes, Part I (Doc 9981) for further information.

4.

- (5) New objects or extensions of existing objects shall not be permitted above the approach surface beyond 3 000 m from the inner edge, the conical surface or inner horizontal surface except when, in the opinion of the Authority, the object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.
- (6) Existing objects above any of the surfaces required by 13.1.4.2 (c)(1) shall as far as practicable be removed except where the Authority is of the opinion that the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

(d) Precision approach runways

- (1) The Authority shall ensure that the following obstacle limitation surfaces shall be established for a precision approach runway category I:
 - (i) conical surface;
 - (ii) inner horizontal surface; approach surface; and
 - (iii) transitional surfaces.
- (2) The Authority shall ensure that the following obstacle limitation surfaces shall be established for a precision approach runway category I:
 - (i) inner approach surface;
 - (ii) inner transitional surfaces; and
 - (iii) balked landing surface.
- (3) The Authority shall ensure that following obstacle limitation surfaces shall be established for a precision approach runway category II or III:
 - (i) conical surface;
 - (ii) inner horizontal surface;
 - (iii) approach surface and inner approach surface;
 - (iv) transitional surfaces;
 - (v) inner transitional surfaces; and
 - (vi) balked landing surface.

Note 1. — See 13.1..9.9 for information regarding siting of equipment and installations on operational areas.

Note 2. — Guidance on obstacle limitation surfaces for precision approach runways is given in the Airport Services Manual (Doc 9137), Part 6.

- (4) The heights and slopes of the surfaces shall not be greater than, and their other dimensions not less than, those specified in Table 13.1.4-1, except in the case of the horizontal section of the approach surface (see 13.1.4.2 (d)(5)).
- (5) The approach surface shall be horizontal beyond the point at which the 2.5 per cent slope intersects:
 - (i) a horizontal plane 150 m above the threshold elevation; or
 - (ii) the horizontal plane passing through the top of any object that governs the obstacle clearance limit;

whichever is the higher.

- (6) Fixed objects shall not be permitted above the inner approach surface, the inner transitional surface or the balked landing surface, except for frangible objects which because of their function must be located on the strip. Mobile objects shall not be permitted above these surfaces during the use of the runway for landing.
- (7) New objects or extensions of existing objects shall not be permitted above an approach surface or a transitional surface except when, in the opinion of the Authority, the new object or extension would be shielded by an existing immovable object.

Note. — Circumstances in which the shielding principle may reasonably be applied are described in the Airport Services Manual (Doc 9137), Part 6.

- (8) New objects or extensions of existing objects shall not be permitted above the conical surface and the inner horizontal surface except when, in the opinion of the Authority, an object would be shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.
- (9) Existing objects above an approach surface, a transitional surface, the conical surface and inner horizontal surface shall as far as practicable be removed except when, in the opinion of the Authority, an object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note. — Because of transverse or longitudinal slopes on a strip, in certain cases the inner edge or portions of the inner edge of the approach surface may be below the corresponding elevation of the strip. It is not intended that the strip be graded to conform with the inner edge of the approach surface, nor is it intended that terrain or objects which are above the approach surface beyond the end of the strip, but below the level of the strip, be removed unless it is considered they may endanger aeroplanes.

(e) Runways meant for take-off

- (1) The Authority shall establish the following obstacle limitation surface for a runway meant for take-off:
 - (i) take-off climb surface.

- (2) The dimensions of the surface shall be not less than the dimensions specified in Table 13.1.4-2, except that a lesser length may be adopted for the take-off climb surface where such lesser length would be consistent with procedural measures adopted to govern the outward flight of aeroplanes.
- (3) The operational characteristics of aeroplanes for which the runway is intended shall be examined to see if it is desirable to reduce the slope specified in Table 4-2 when critical operating conditions are to be catered to. If the specified slope is reduced, corresponding adjustment in the length of the take-off climb surface shall be made so as to provide protection to a height of 300m.

Note.— When local conditions differ widely from sea level standard atmospheric conditions, it may be advisable for the slope specified in Table 4-2 to be reduced. The degree of this reduction depends on the divergence between local conditions and sea level standard atmospheric conditions, and on the performance characteristics and operational requirements of the aeroplanes for which the runway is intended.

- (4) New objects or extensions of existing objects shall not be permitted above a take-off climb surface except when, in the opinion of the Authority, the new object or extension would be shielded by an existing immovable object.

Note.— Circumstances in which the shielding principle may reasonably be applied are described in the Airport Services Manual (Doc 9137), Part 6.

- (5) If no object reaches the 2 per cent (1:50) take-off climb surface, new objects shall be limited to preserve the existing obstacle free surface or a surface down to a slope of 1.6 per cent (1:62.5).
- (6) Existing objects that extend above a take-off climb surface should as far as practicable be removed except when, in the opinion of the appropriate authority, an object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety or significantly affect the regularity of operations of aeroplanes.

Note.— Because of transverse slopes on a strip or clearway, in certain cases portions of the inner edge of the take-off climb surface may be below the corresponding elevation of the strip or clearway. It is not intended that the strip or clearway be graded to conform with the inner edge of the take-off climb surface, nor is it intended that terrain or objects which are above the take-off climb surface beyond the end of the strip or clearway, but below the level of the strip or clearway, be removed unless it is considered they may endanger aeroplanes. Similar considerations apply at the junction of a clearway and strip where differences in transverse slopes exist.

Table 13.1.4-2. Dimensions and slopes of obstacle limitation surfaces

RUNWAYS MEANT FOR TAKE-OFF

Surface and dimensions ^a (1)	Code number		
	1 (2)	2 (3)	3 or 4 (4)
TAKE-OFF CLIMB			
Length of inner edge	60 m	80 m	180 m
Distance from runway end ^b	30 m	60 m	60 m
Divergence (each side)	10%	10%	12.5%
Final width	380 m	580 m	1 200 m 1 800 m ^c
Length	1 600 m	2 500 m	15 000 m
Slope	5%	4%	2% ^d

- a. All dimensions are measured horizontally unless specified otherwise.
- b. The take-off climb surface starts at the end of the clearway if the clearway length exceeds the specified distance.
- c. 1 800 m when the intended track includes changes of heading greater than 15° for operations conducted in IMC, VMC by night.
- d. See 13.1.4.2 (e) (3) and 13.1.4.2 (e) (5)

13.1.4.3 Objects Outside The Obstacle Limitation Surfaces

- (a)** Arrangements shall be made to enable the appropriate authority to be consulted concerning proposed construction beyond the limits of the obstacle limitation surfaces that extend above a height established by that authority, in order to permit an aeronautical study of the effect of such construction on the operation of aeroplanes.
- (b)** In areas beyond the limits of the obstacle limitation surfaces, at least those objects which extend to a height of 150 m or more above ground elevation shall be regarded as obstacles, unless a special aeronautical study indicates that they do not constitute a hazard to aeroplanes.

Note.— This study may have regard to the nature of operations concerned and may distinguish between day and night operations.

13.1.4.4 Other Objects

- (a)** Objects which do not project through the approach surface but which would nevertheless adversely affect the optimum siting or performance of visual or non-visual aids shall, as far as practicable, be removed.

- (b) Anything which may, in the opinion of the appropriate authority after aeronautical study, endanger aeroplanes on the movement area or in the air within the limits of the inner horizontal and conical surfaces should be regarded as an obstacle and shall be removed in so far as practicable.

Note.— In certain circumstances, objects that do not project above any of the surfaces enumerated in 13.1.4.1 may constitute a hazard to aeroplanes as, for example, where there are one or more isolated objects in the vicinity of an aerodrome

13.1.4.5 **Shielding Principles**

- (a) In assessing whether an existing obstacle shields an obstacle, the Authority will be guided by the principles of shielding detailed below.

(1) **Obstacle Penetrating the Approach and Take-Off Climb Surfaces**

- (i) An existing obstacle within the approach and take-off climb area is called the critical obstacle. Where a number of obstacles exist closely together, the critical obstacle is the one which subtends the greatest vertical angle measured from the appropriate inner edge.
- (ii) As illustrated in the Figure below, a new obstacle may be assessed as not imposing additional restrictions if:
- (A) when located between the inner edge end and the critical obstacle, the new obstacle is below a plane sloping downwards at 10% from the top of the critical obstacle toward the inner edge;
- (B) when located beyond the critical obstacle from the inner edge end, the new obstacle is not higher than the height of the permanent obstacle; and
- (C) where there is more than one critical obstacle within the approach and take-off climb area, and the new obstacle is located between two critical obstacles, the height of the new obstacle is not above a plane sloping downwards at 10% from the top of the next critical obstacle


(2) **Obstacle Penetrating the Inner and Outer Horizontal and Conical Surfaces**

- (i) A new obstacle may be accepted if it is in the vicinity of an existing obstacle, and does not penetrate a 10% downward sloping conical shaped surface from the top of the existing obstacle, i.e. the new obstacle is shielded radically by the existing obstacle.

(3) **Obstacle Penetrating the Transitional Surfaces**

- (i) A new obstacle may be assessed as not imposing additional restrictions if it does not exceed the height of an existing obstacle which is closer to the runway strip and the new obstacle is located perpendicularly behind the existing obstacle relative to the runway center line.

(4) **Shielding Of Obstacles Penetrating the Approach And Take-Off Climb Surfaces**



13.1.5 VISUAL AIDS FOR NAVIGATION

13.1.5.1 Indicators and Signaling Devices

(a) Wind direction indicator

- (1) **Application.** The Aerodrome Operator shall ensure that an aerodrome shall be equipped with at least one wind direction indicator.
- (2) **Location.** A wind direction indicator shall be located so as to be visible from aircraft in flight or on the movement area and in such a way as to be free from the effects of air disturbances caused by nearby objects.
- (3) **Characteristics**
 - (i) The wind direction indicator shall be in the form of a truncated cone made of fabric and shall have a length of not less than 3.6m and a diameter, at the larger end, of not less than 0.9m. It shall be constructed so that it gives a clear indication of the direction of the surface wind and a general indication of the wind speed. The color or colors shall be so selected as to make the wind direction indicator clearly visible and understandable from a height of at least 300m, having regard to background. Where practicable, a single color, preferably white or orange, shall be used. Where a combination of two colors is required to give adequate conspicuity against changing backgrounds, they shall preferably be orange and white, red and white, or black and white, and should be arranged in five alternate bands, the first and last bands being the darker color.
 - (ii) The location of at least one wind direction indicator shall be marked by a circular band 15 m in diameter and 1.2 m wide. The band shall be centered about the wind direction indicator support and shall be in a color chosen to give adequate conspicuity, preferably white.
 - (iii) Provision shall be made for illuminating at least one wind indicator at an aerodrome intended for use at night.

(b) Landing direction indicator

- (1) **Location.** Where provided, a landing direction indicator shall be located in a conspicuous place on the aerodrome.
- (2) **Characteristics.**
 - (i) The landing direction indicator shall be in the form of a “T”.
 - (ii) The shape and minimum dimensions of a landing “T” shall be as shown in Figure 13.1.5-1. The color of the landing “T” shall be either white or orange, the choice being dependent on the color that contrasts best with the background against which the indicator will be viewed. Where required for use at night the landing “T” shall either be illuminated or outlined by white lights.




Figure 13.1.5-1. Landing direction indicator

(c) Signalling lamp

(1) **Application.** The Aerodrome Operator shall ensure that a signalling lamp shall be provided at any controlled aerodrome in the aerodrome control tower.

(2) **Characteristics**

- (i) The Signaling lamp shall be capable of producing red, green and white signals, and of:
 - (A) being aimed manually at any target as required;
 - (B) giving a signal in any one color followed by a signal in either of the two other colors; and
 - (C) transmitting a message in any one of the three colors by Morse Code up to a speed of at least four words per minute. When selecting the green light, use shall be made of the restricted boundary of green as specified in Appendix 1, 2.1.2.
 - (D) The beam spread shall be not less than 1° nor greater than 3° , with negligible light beyond 3° . When the signalling lamp is intended for use in the daytime the intensity of the colored light should be not less than 6 000cd.

(d) Signal panels and signal area

Note.— The inclusion of detailed specifications for a signal area in this section is not intended to imply that one has to be provided. Annex 2, Appendix 1, specifies the shape, color and use of visual ground signals. The Aerodrome Design Manual (Doc 9157), Part 4, provides guidance on their design.

(1) **Location of signal area.** Where applicable, the signal area shall be located so as to be visible for all angles of azimuth above an angle of 10° above the horizontal when viewed from a height of 300m.

(2) **Characteristics of signal area**

- (i) The signal area shall be an even horizontal surface at least 9 m square.
- (ii) The color of the signal area shall be chosen to contrast with the colors of

the signal panels used, and it shall be surrounded by a white border not less than 0.3 m wide.

13.1.5.2 **Markings**

(a) General

(1) *Interruption of runway markings*

- (i) At an intersection of two (or more) runways the markings of the more important runway, except for the runway side stripe marking, shall be displayed and the markings of the other runway(s) shall be interrupted. The runway side stripe marking of the more important runway may be either continued across the intersection or interrupted.
- (ii) The order of importance of runways for the display of runway markings shall be as follows:
 - (A) 1st — precision approach runway;
 - (B) 2nd — non-precision approach runway; and
 - (C) 3rd — non-instrument runway.

- (2) At an intersection of a runway and taxiway the markings of the runway shall be displayed and the markings of the taxiway interrupted, except that runway side stripe markings may be interrupted.

Note.— See 13.1.5.2 (h)(2)(ii) regarding the manner of connecting runway and taxiway center line markings.

(3) *Color and conspicuity*

- (i) The Aerodrome Operator shall ensure that all Runway markings shall be white.

Note 1.— It has been found that, on runway surfaces of light color, the conspicuity of white markings can be improved by outlining them in black.

Note 2.— It is preferable that the risk of uneven friction characteristics on markings be reduced in so far as practicable by the use of a suitable kind of paint.

Note 3.— Markings may consist of solid areas or a series of longitudinal stripes providing an effect equivalent to the solid areas.

- (ii) Taxiway markings, runway turn pad markings and aircraft stand markings shall be yellow.
- (iii) Apron safety lines shall be of a conspicuous color which shall contrast with that used for aircraft stand markings.
- (iv) At aerodromes where operations take place at night, pavement markings shall be made with reflective materials designed to enhance the visibility of the markings.

Note— Guidance on reflective materials is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 4.

- (4) **Unpaved taxiways.** The Aerodrome Operator shall ensure that an unpaved taxiway shall be provided, so far as practicable, with the markings prescribed for paved taxiways.

(b) Runway designation marking

(1) Application

- (i) A runway designation marking shall be provided at the thresholds of a paved runway.
- (ii) A runway designation marking shall be provided, so far as practicable, at the thresholds of an unpaved runway.
- (2) **Location.** A runway designation marking shall be located at a threshold as shown in Figure 5-2 as appropriate.

Note.— If the runway threshold is displaced from the extremity of the runway, a sign showing the designation of the runway may be provided for aeroplanes taking off.

(3) Characteristics

- (i) A runway designation marking shall consist of a two-digit number and on parallel runways shall be supplemented with a letter. On a single runway, dual parallel runways and triple parallel runways the two-digit number shall be the whole number nearest the one-tenth of the magnetic North when viewed from the direction of approach. On four or more parallel runways, one set of adjacent runways shall be numbered to the nearest one-tenth magnetic azimuth and the other set of adjacent runways numbered to the next nearest one-tenth of the magnetic azimuth. When the above rule would give a single digit number, it shall be preceded by a zero.




Figure 13.1.5-2. Runway designation, center line and threshold markings

- (ii) In the case of parallel runways, each runway designation number shall be supplemented by a letter as follows, in the order shown from left to right when viewed from the direction of approach:
- for two parallel runways: “L” “R”;
 - for three parallel runways: “L” “C” “R”;
 - for four parallel runways: “L” “R” “L” “R”;
 - for five parallel runways: “L” “C” “R” “L” “R” or “L” “R” “L” “C” “R”; and
 - for six parallel runways: “L” “C” “R” “L” “C” “R”.
- (iii) The numbers and letters shall be in the form and proportion shown in Figure 13.1.5-3. The dimensions shall be not less than those shown in Figure 13.1.5-3, but where the numbers are incorporated in the threshold marking, larger dimensions shall be used in order to fill adequately the gap between the stripes of the threshold marking.

(c) **Runway center line marking**

- (1) **Application.** A runway center line marking shall be provided on a paved runway.

- (2) **Location.** A runway center line marking shall be located along the center line of the runway between the runway designation markings as shown in Figure 13.1.5-2, except when interrupted in compliance with 13.1.5.2.(a)(1).
- (3) **Characteristics**
- (i) A runway center line marking shall consist of a line of uniformly spaced stripes and gaps. The length of a stripe plus a gap shall be not less than 50 m or more than 75 m. The length of each stripe shall be at least equal to the length of the gap or 30 m, whichever is greater.
- (ii) The width of the stripes shall be not less than:
- (A) 0.90 m on precision approach category II and III runways;
- (B) 0.45 m on non-precision approach runways where the code number is 3 or 4, and precision approach category I runways; and
- (C) 0.30 m on non-precision approach runways where the code number is 1 or 2, and on non-instrument runways.
- (d) **Threshold marking**
- (1) **Application**
- (i) The Aerodrome Operator shall ensure that threshold marking shall be provided at the threshold of a paved instrument runway, and of a paved non-instrument runway where the code number is 3 or 4 and the runway is intended for use by international commercial air transport.
- (ii) A threshold marking shall be provided at the threshold of a paved non-instrument runway where the code number is 3 or 4 and the runway is intended for use by other than international commercial air transport.
- (iii) A threshold marking shall be provided, so far as practicable, at the thresholds of an unpaved runway.
- Note.— The Aerodrome Design Manual (Doc 9157), Part 4, shows a form of marking which has been found satisfactory for the marking of downward slopes immediately before the threshold.*
- (2) **Location.** The stripes of the threshold marking shall commence 6 m from the threshold.




Figure 13.1.5-3. Form and proportions of numbers and letters for runway designation markings

(3) **Characteristics**

- (i) A runway threshold marking shall consist of a pattern of longitudinal stripes of uniform dimensions disposed symmetrically about the center line of a runway as shown in Figure 13.1.5-2 (A) and (B) for a runway width of 45 m. The number of stripes shall be in accordance with the runway width as follows:

<i>Runway width</i>	<i>Number of stripes</i>
18 m	4
23 m	6
30 m	8
45 m	12
60 m	16

except that on non-precision approach and non-instrument runways 45 m or greater in width, they may be as shown in Figure 13.1.5-2 (C).

- (ii) The stripes shall extend laterally to within 3 m of the edge of a runway or to a distance of 27 m on either side of a runway center line, whichever results in the smaller lateral distance. Where a runway designation marking is placed within a threshold marking there shall be a minimum of three stripes on each side of the center line of the runway. Where a runway designation marking is placed above a threshold marking, the stripes shall be continued across the runway. The stripes shall be at least 30 m long and approximately 1.80 m wide with spacings of approximately 1.80 m between them except that, where the stripes are continued across a runway, a double spacing shall be used to separate the two stripes nearest the center line of the runway, and in the case where the designation marking is included within the threshold marking this spacing shall be 22.5 m.

(4) **Transverse stripe**

- (i) Where a threshold is displaced from the extremity of a runway or where the extremity of a runway is not square with the runway center line, a transverse stripe as shown in Figure 5-4 (B) shall be added to the threshold marking.
- (ii) A transverse stripe shall be not less than 1.80 m wide.

(5) **Arrows**

- (i) Where a runway threshold is permanently displaced, arrows conforming to Figure 5-4 (B) shall be provided on the portion of the runway before the displaced threshold.
- (ii) When a runway threshold is temporarily displaced from the normal position, it shall be marked as shown in Figure 5-4 (A) or 5-4 (B) and all markings prior to the displaced threshold shall be obscured except the runway center line marking, which shall be converted to arrows.

Note 1.— In the case where a threshold is temporarily displaced for only a short period of time, it has been found satisfactory to use markers in the form and color of a displaced threshold marking rather than attempting to paint this marking on the runway.

Note 2.— When the runway before a displaced threshold is unfit for the surface movement of aircraft, closed markings, as described in 7.1.4, are required to be provided.




Figure 13.1.5-4. Displaced threshold markings

(e) **Aiming point marking**

(1) **Application**

- (i) An aiming point marking shall be provided at each approach end of a paved instrument runway where the code number is 2, 3 or 4.
- (ii) An aiming point marking shall be provided at each approach end of:
 - (A) a paved non-instrument runway where the code number is 3 or 4;
 - (B) a paved instrument runway where the code number is 1;
when additional conspicuity of the aiming point is desirable.

(2) **Location**

- (i) The aiming point marking shall commence no closer to the threshold than the distance indicated in the appropriate column of Table 13.1.5-1,
- (ii) except that, on a runway equipped with a visual approach slope indicator system, the beginning of the marking shall be coincident with the visual approach slope origin.
- (iii) An aiming point marking shall consist of two conspicuous stripes. The dimensions of the stripes and the lateral spacing between their inner sides

shall be in accordance with the provisions of the appropriate column of Table 13.1.5-1. Where a touchdown zone marking is provided, the lateral spacing between the markings shall be the same as that of the touchdown zone marking.

(f) Touchdown zone marking

(1) Application

- (i) A touchdown zone marking shall be provided in the touchdown zone of a paved precision approach runway where the code number is 2, 3 or 4.
- (ii) A touchdown zone marking shall be provided in the touchdown zone of a paved non precision approach or non-instrument runway where the code number is 3 or 4 and additional conspicuity of the touchdown zone is desirable.

Table 13.1.5-1. Location and dimensions of aiming point marking

Location and dimensions (1)	Landing distance available			
	Less than 800 m (2)	800 m up to but not including 1 200 m (3)	1 200 m up to but not including 2 400 m (4)	2 400 m and above (5)
Distance from threshold to beginning of marking	150 m	250 m	300 m	400 m
Length of stripe ^a	30–45 m	30–45 m	45–60 m	45–60 m
Width of stripe	4 m	6 m	6–10 m ^b	6–10 m ^b
Lateral spacing between inner sides of stripes	6 m ^c	9 m ^c	18–22.5 m	18–22.5 m

- a. The greater dimensions of the specified ranges are intended to be used where increased conspicuity is required.
- b. The lateral spacing may be varied within these limits to minimize the contamination of the marking by rubber deposits.
- c. These figures were deduced by reference to the outer main gear wheel span which is element 2 of the aerodrome reference code at Table 13.1.1-1.

(2) Location and characteristics

- (i) A touchdown zone marking shall consist of pairs of rectangular markings symmetrically disposed about the runway center line with the number of such pairs related to the landing distance available and, where the marking is to be displayed at both the approach directions of a runway, the distance between the thresholds, as follows:

Landing distance available or the distance between thresholds	Pair(s) of markings
less than 900m	1
900 m up to but not including 1200 m	2
1 200 m up to but not including 1500m	3
1500 m up to but not including 2 400 m	4
2400 m or more	6

- (ii) A touchdown zone marking shall conform to either of the two patterns shown in Figure 13.1.5-5. For the pattern shown in Figure 13.1.5-5 (A), the markings shall be not less than 22.5 m long and 3 m wide. For the pattern shown in Figure 13.1.5-5 (B), each stripe of each marking shall be not less than 22.5m long and 1.8m wide with a spacing of 1.5 m between adjacent stripes. The lateral spacing between the inner sides of the rectangles shall be equal to that of the aiming point marking where provided. Where an aiming point marking is not provided, the lateral spacing between the inner sides of the rectangles shall correspond to the lateral spacing specified for the aiming point marking in Table 13.1.5-1 (columns 2, 3, 4 or 5, as appropriate). The pairs of markings shall be provided at longitudinal spacings of 150 m beginning from the threshold, except that pairs of touchdown zone markings coincident with or located within 50 m of an aiming point marking shall be deleted from the pattern.
- (iii) On a non-precision approach runway where the code number is 2, an additional pair of touchdown zone marking stripes shall be provided 150 m beyond the beginning of the aiming point marking.

(g) Runway side stripe marking

(1) Application

- (i) A runway side stripe marking shall be provided between the thresholds of a paved runway where there is a lack of contrast between the runway edges and the shoulders or the surrounding terrain.
- (ii) A runway side stripe marking shall be provided on a precision approach runway irrespective of the contrast between the runway edges and the shoulders or the surrounding terrain.

(2) Location

- (i) A runway side stripe marking shall consist of two stripes, one placed along each edge of the runway with the outer edge of each stripe approximately on the edge of the runway, except that, where the runway is greater than 60 m in width, the stripes shall be located 30 m from the runway centerline.
- (ii) Where a runway turn pad is provided, the runway side stripe marking shall be continued between the runway and the runway turn pad.




figure 13.1.5-5. aiming point and touchdown zone markings
(illustrated for a runway with a length of 2 400 m or more)

(3) **Characteristics**

- (i) A runway side stripe shall have an overall width of at least 0.9 m on runways 30 m or more in width and at least 0.45 m on narrower runways.

(h) **Taxiway center line marking**

(1) **Application**

- (i) Taxiway center line marking shall be provided on a paved taxiway and

apron where the code number is 3 or 4 in such a way as to provide continuous guidance between the runway center line and aircraft stands.

- (ii) Taxiway center line marking shall be provided on a paved taxiway and apron where the code number is 1 or 2 in such a way as to provide continuous guidance between the runway center line and aircraft stands.

- (iii) Taxiway center line marking shall be provided on a paved runway when the runway is part of a standard taxi-route and:
 - (A) there is no runway center line marking; or
 - (B) where the taxiway center line is not coincident with the runway centerline.
- (iv) Where it is necessary to denote the proximity of a runway-holding position, enhanced taxiway center line marking shall be provided.

Note. — *The provision of enhanced taxiway center line marking may form part of runway incursion prevention measures.*

- (v) Where provided, enhanced taxiway center line marking shall be installed at each taxiway or runway intersection.

(2) **Location**

- (i) On a straight section of a taxiway the taxiway center line marking shall be located along the taxiway center line. On a taxiway curve the marking shall continue from the straight portion of the taxiway at a constant distance from the outside edge of the curve.

Note. — *See 13.1.3.9(c) and Figure 13.1.3-2.*

- (ii) At an intersection of a taxiway with a runway where the taxiway serves as an exit from the runway, the taxiway center line marking shall be curved into the runway center line marking as shown in Figures 13.1.5-6 and 13.1.5-26. The taxiway center line marking shall be extended parallel to the runway center line marking for a distance of at least 60 m beyond the point of tangency where the code number is 3 or 4, and for a distance of at least 30 m where the code number is 1 or 2.
- (iii) Where taxiway center line marking is provided on a runway in accordance with 13.1.5.2(h)(1)(iii), the marking shall be located on the centerline of the designated taxiway.
- (iv) Where provided:
 - (A) An enhanced taxiway center line marking shall extend from the runway-holding position Pattern A (as defined in Figure 13.1.5-6, Taxiway markings) to a distance of up to 47 m in the direction of travel away from the runway. See Figure 13.1.5-7 (a).




Figure 13.1.5-6. Taxiway markings

(SHOWN WITH BASIC RUNWAY MARKINGS)




Figure 13.1.5-7. Enhanced taxiway center line marking

- (B) If the enhanced taxiway center line marking intersects another runway-holding position marking, such as for a precision approach category II or III runway, that is located within 47 m of the first runway-holding position marking, the enhanced taxiway center line marking shall be interrupted 0.9 m prior to and after the intersected runway-holding position marking. The enhanced taxiway center line marking shall continue beyond the intersected runway-holding position marking for at least three dashed line segments or 47 m from start to finish, whichever is greater. See Figure 13.1.5-7 (b).
- (C) If the enhanced taxiway center line marking continues through a taxiway/taxiway intersection that is located within 47 m of the runway-holding position marking, the enhanced taxiway center line marking

shall be interrupted 1.5 m prior to and after the point where the intersected taxiway center line crosses the enhanced taxiway center line. The enhanced taxiway center line marking shall continue beyond the taxiway/taxiway intersection for at least three dashed line segments or 47 m from start to finish, whichever is greater. See Figure 13.1.5-7 (c).

- (D) Where two taxiway center lines converge at or before the runway-holding position marking, the inner dashed line shall not be less than 3 m in length. See Figure 13.1.5- 7 (d)
- (E) Where there are two opposing runway-holding position markings and the distance between the markings is less than 94 m, the enhanced taxiway center line markings shall extend over this entire distance. The enhanced taxiway center line markings shall not extend beyond either runway-holding position marking. See Figure 13.1.5-7 (e).

(3) **Characteristics**

- (i) A taxiway center line marking shall be at least 15 cm in width and continuous in length except where it intersects with a runway-holding position marking or an intermediate holding position marking as shown in Figure 5-6.
- (ii) Enhanced taxiway center line marking shall be as shown in Figure 13.1.5-7.

(i) **Runway turn pad marking**

- (1) **Application.** Where a runway turn pad is provided, a runway turn pad marking shall be provided for continuous guidance to enable an aeroplane to complete a 180-degree turn and align with the runway center line.

(2) **Location**

- (i) The runway turn pad marking shall be curved from the runway center line into the turn pad. The radius of the curve shall be compatible with the maneuvering capability and normal taxiing speeds of the aeroplanes for which the runway turn pad is intended. The intersection angle of the runway turn pad marking with the runway center line shall not be greater than 30 degrees.
- (ii) The runway turn pad marking shall be extended parallel to the runway center line marking for a distance of at least 60 m beyond the point of tangency where the code number is 3 or 4, and for a distance of at least 30 m where the code number is 1 or 2.
- (iii) A runway turn pad marking shall guide the aeroplane in such a way as to allow a straight portion of taxiing before the point where a 180-degree turn is to be made. The straight portion of the runway turn pad marking shall be parallel to the outer edge of the runway turn pad.
- (iv) The design of the curve allowing the aeroplane to negotiate a 180-degree turn shall be based on a nose wheel steering angle not exceeding 45 degrees.
- (v) The design of the turn pad marking shall be such that, when the cockpit of the aeroplane remains over the runway turn pad marking, the clearance distance between any wheel of the aeroplane landing gear and the edge of the

runway turn pad shall be not less than those specified in 13.1.3.3(a)(6).

Note. — For ease of maneuvering, consideration may be given to providing a larger wheel-to edge clearance for codes E and F aeroplanes. See 13.1.3.3(a)(7).

- (3) **Characteristics.** A runway turn pad marking shall be at least 15 cm in width and continuous in length.

(j) Runway-holding position marking

- (1) **Application and location.** Runway-holding position marking shall be displayed along a runway-holding position.

Note. — See 13.1.5.4(b) concerning the provision of signs at runway-holding positions.

(2) **Characteristics**

- (i) At an intersection of a taxiway and a non-instrument, non-precision approach or take-off runway, the runway holding position marking shall be as shown in Figure 13.1.5-6, pattern A.
- (ii) Where a single runway-holding position is provided at an intersection of a taxiway and a precision approach category I, II or III runway, the runway-holding position marking shall be as shown in Figure 5-6, pattern A. Where two or three runway-holding positions are provided at such an intersection, the runway-holding position marking closer (closest) to the runway shall be as shown in Figure 13.1.5-6, pattern A and the markings farther from the runway shall be as shown in Figure 13.1.5-6, pattern B.
- (iii) The runway-holding position marking displayed at a runway-holding position established in accordance with 13.1.3.12(a)(3) shall be as shown in Figure 13.1.5-6, pattern A.
- (iv) Until 26 November 2026, the dimensions of runway-holding position markings shall be as shown in Figure 13.1.5-8, pattern A1 (or A2) or pattern B1 (or B2), as appropriate.
- (v) As of 26 November 2026, the dimensions of runway-holding position markings shall be as shown in Figure 13.1.5-8, pattern A2 or pattern B2, as appropriate.
- (vi) Where increased conspicuity of the runway-holding position is required, the dimensions of runway-holding position marking should be as shown in Figure 13.1.5-8, pattern A2 or pattern B2, as appropriate.

Note.— An increased conspicuity of the runway-holding position can be required, notably to avoid incursion risks.




FIGURE 13.1.5-8. Runway Holding Position Markings

Note.— Patterns A1 and B1 are no longer valid after 2026.

- (vii) Where a pattern B runway-holding position marking is located on an area where it would exceed 60 m in length, the term “CAT II” or “CAT III” as appropriate shall be marked on the surface at the ends of the runway-holding position marking and at equal intervals of 45 m maximum between successive marks. The letters shall be not less than 1.8 m high and shall be placed not more than 0.9 m beyond the holding position marking.
- (viii) The runway-holding position marking displayed at a runway or runway intersection shall be perpendicular to the center line of the runway forming part of the standard taxi-route. The pattern of the marking shall be as shown in Figure 13.1.5-8, pattern A2.

(k) Intermediate holding position marking

(1) Application and location

- (i) An intermediate holding position marking shall be displayed along an intermediate holding position.
- (ii) Where an intermediate holding position marking is displayed at an intersection of two paved taxiways, it shall be located across the taxiway at sufficient distance from the near edge of the intersecting taxiway to ensure safe clearance between taxiing aircraft. It shall be coincident with

- (iii) a stop bar or intermediate holding position lights, where provided.
- (2) **Characteristics.** An intermediate holding position marking shall consist of a single broken line as shown in Figure 13.1.5-6.

(I) VOR aerodrome checkpoint marking

(1) Application

- (i) When a VOR aerodrome checkpoint is established, it shall be indicated by a VOR aerodrome checkpoint marking and sign.

Note. — See 13.1.5.4(d) for VOR aerodrome checkpoint sign.

- (ii) **Site selection**

Note. — Guidance on the selection of sites for VOR aerodrome checkpoints is given in Annex 10, Volume I, Attachment E.

- (2) **Location.** A VOR aerodrome checkpoint marking shall be centered on the spot at which an aircraft is to be parked to receive the correct VOR signal.

(3) Characteristics

- (i) A VOR aerodrome checkpoint marking shall consist of a circle 6 m in diameter and have a line width of 15 cm (see Figure 13.1.5-9 (A)).
- (ii) When it is preferable for an aircraft to be aligned in a specific direction, a line shall be provided that passes through the center of the circle on the desired azimuth. The line shall extend 6 m outside the circle in the desired direction of heading and terminate in an arrowhead. The width of the line shall be 15 cm (see Figure 13.1.5-9 (B)).




Figure 13.1.5-9 VOR aerodrome checkpoint marking

- (iii) A VOR aerodrome checkpoint marking shall preferably be white in color but shall differ from the color used for the taxiway markings.

Note. — To provide contrast, markings may be bordered with black.

(m) Aircraft stand marking

Note.— Guidance on the layout of aircraft stand markings is contained in the *Aerodrome Design Manual (Doc 9157), Part 4.*

- (1) **Application.** Aircraft stand markings shall be provided for designated parking positions on a paved apron.
- (2) **Location.** Aircraft stand markings on a paved apron shall be located so as to provide the clearances specified in 13.1.3.13(e)(i), when the nose wheel follows the stand marking.
- (3) **Characteristics**
 - (i) Aircraft stand markings shall include such elements as stand identification, lead-in line, turn bar, turning line, alignment bar, stop line and lead-out line, as are required by the parking configuration and to complement other parking aids.
 - (ii) An aircraft stand identification (letter and or number) shall be included in the lead-in line a short distance after the beginning of the lead-in line. The height of the identification shall be adequate to be readable from the cockpit of aircraft using the stand.
 - (iii) Where two sets of aircraft stand markings are superimposed on each other in order to permit more flexible use of the apron and it is difficult to identify which stand marking should be followed, or safety would be impaired if the wrong marking was followed, then identification of the aircraft for which each set of markings is intended shall be added to the stand identification.
Note. — Example: 2A-B747, 2B-F28.
 - (iv) Lead-in, turning and lead-out lines shall normally be continuous in length and have a width of not less than 15 cm. Where one or more sets of stand markings are superimposed on a stand marking, the lines shall be continuous for the most demanding aircraft and broken for other aircraft.
 - (v) The curved portions of lead-in, turning and lead-out lines shall have radii appropriate to the most demanding aircraft type for which the markings are intended.
 - (vi) Where it is intended that an aircraft proceed in one direction only, arrows pointing in the direction to be followed shall be added as part of the lead-in and lead-outlines.
 - (vii) A turn bar shall be located at right angles to the lead-in line, abeam the left pilot position at the point of initiation of any intended turn. It shall have a length and width of not less than 6 m and 15 cm, respectively, and include an arrowhead to indicate the direction of turn.
Note. — The distances to be maintained between the turn bar and the lead-in line may vary according to different aircraft types, taking into account the pilot's field of view.
 - (viii) If more than one turn bar and or stop line is required, they shall be coded.
 - (ix) An alignment bar shall be placed so as to be coincident with the extended center line of the aircraft in the specified parking position and visible to the pilot during the final part of the parking maneuver. It shall have a width of not less than 15 cm.

- (x) A stop line shall be located at right angles to the alignment bar, abeam the left pilot position at the intended point of stop. It shall have a length and width of not less than 6 m and 15 cm, respectively.

Note. — *The distances to be maintained between the stop line and the lead-in line may vary according to different aircraft types, taking into account the pilot's field of view.*

(n) Apron safety lines

Note.— *Guidance on apron safety lines is contained in the Aerodrome Design Manual (Doc 9157), Part 4.*

(1) Application

- (i) Apron safety lines shall be provided on a paved apron as required by the parking configurations and ground facilities.
- (ii) Apron safety lines shall be located so as to define the areas intended for use by ground vehicles and other aircraft servicing equipment, etc., to provide safe separation from aircraft.

(2) Characteristics

- (i) Apron safety lines shall include such elements as wing tip clearance lines and service road boundary lines as required by the parking configurations and ground facilities.
- (ii) An apron safety line shall be continuous in length and at least 10 cm in width.

(o) Road-holding position marking

- (1) **Application.** A road-holding position marking shall be provided at all road entrances to a runway.
- (2) **Location.** The road-holding position marking shall be located across the road at the holding position.
- (3) **Characteristics.** The road-holding position marking shall be in accordance with the Liberia road traffic Regulations.

(p) Mandatory instruction marking

Note.— *Guidance on mandatory instruction marking is given in the Aerodrome Design Manual (Doc 9157), Part 4.*

(1) Application

- (i) Where it is impracticable to install a mandatory instruction sign in accordance with 13.1.5.4(a), a mandatory instruction marking shall be provided on the surface of the pavement.
- (ii) Where operationally required, such as on taxiways exceeding 60 m in width, or to assist in the prevention of a runway incursion, a mandatory instruction sign shall be supplemented by a mandatory instruction marking.

(2) **Location**

- (i) The mandatory instruction marking on taxiways where the code letter is A, B, C or D shall be located across the taxiway equally placed about the taxiway center line and on the holding side of the runway-holding position marking as shown in Figure 13.1.5-10.




FIGURE 13.1.5-10. Mandatory Instruction Marking

- (ii) The mandatory instruction marking on taxiways where the code letter is E or F shall be located on both sides of the taxiway center line marking and on the holding side of the runway-holding position marking as shown in Figure 13.1.5 -10 (B). The distance between the nearest edge of the marking and the runway-holding position marking or the taxiway

center line marking shall be not less than 1 m.

- (iii) Except where operationally required, a mandatory instruction marking should not be located on a runway.

(3) **Characteristics**

- (i) A mandatory instruction marking shall consist of an inscription in white on a red background. Except for a NO ENTRY marking, the inscription shall provide information identical to that of the associated mandatory instruction sign.
- (ii) A NO ENTRY marking shall consist of an inscription in white reading NO ENTRY on a red background.

- (iii) Where there is insufficient contrast between the marking and the pavement surface, the mandatory instruction marking shall include an appropriate border, preferably white or black.
- (iv) The character height should be 4 m for inscriptions where the code letter is C, D, E or F, and 2 m where the code letter is A or B. The inscriptions shall be in the form and proportions shown in Appendix 3.
- (v) The background shall be rectangular and extend a minimum of 0.5 m laterally and vertically beyond the extremities of the inscription.

(q) Information marking

Note.— Guidance on information marking is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

(1) Application

- (i) Where an information sign would normally be installed and is impractical to install, as determined by the appropriate authority, an information marking shall be displayed on the surface of the pavement.
- (ii) Where operationally required an information sign shall be supplemented by an information marking.
- (iii) An information (location or direction) marking shall be displayed prior to and following complex taxiway intersections and where operational experience has indicated the addition of a taxiway location marking could assist flight crew ground navigation.
- (iv) An information (location) marking shall be displayed on the pavement surface at regular intervals along taxiways of great length.

(2) Location. The information marking shall be displayed across the surface of the taxiway or apron where necessary and positioned so as to be legible from the cockpit of an approaching aircraft.

(3) Characteristics

- (i) An information marking shall consist of:
 - (A) an inscription in yellow upon a black background, when it replaces or supplements a location sign; and
 - (B) an inscription in black upon a yellow background, when it replaces or supplements a direction or destination sign.
- (ii) Where there is insufficient contrast between the marking background and the pavement surface, the marking shall include:
 - (A) a black border where the inscriptions are in black; and
 - (B) a yellow border where the inscriptions are in yellow.
- (iii) The character height shall be 4 m. The inscriptions shall be in the form and proportions shown in Appendix 3.

13.1.5.3 **Lights**

(a) General

(1) *Lights Which May Endanger The Safety Of Aircraft*

- (i) No person shall install or use a non-aeronautical ground light near an aerodrome which might endanger the safety of aircraft without prior authorization from the Authority.
- (ii) Where following the conduct of an aeronautical safety risk assessment, the Authority is of the opinion that the non-aeronautical ground light poses a danger to aircraft, the non-aeronautical ground light shall be extinguished, screened or otherwise modified so as to eliminate the source of danger.

(2) *Laser Emissions Which May Endanger The Safety Of Aircraft*

- (i) The Authority shall establish the following protected zones shall be established around aerodromes to protect the safety of aircraft against the hazardous effects of laser emitters:
 - (A) a laser-beam free flight zone(LFFZ)
 - (B) a laser-beam critical flight zone(LCFZ)
 - (C) a laser-beam sensitive flight zone(LSFZ).

Note 1.— Figures 13.1.5-11, 13.1.5-12 and 13.1.5-13 may be used to determine the exposure levels and distances that adequately protect flight operations.

Note 2.— The restrictions on the use of laser beams in the three protected flight zones, LFFZ, LCFZ and LSFZ, refer to visible laser beams only. Laser emitters operated by the authorities in a manner compatible with flight safety are excluded. In all navigable airspace, the irradiance level of any laser beam, visible or invisible, is expected to be less than or equal to the maximum permissible exposure (MPE) unless such emission has been notified to the authority and permission obtained.

Note 3.— The protected flight zones are established in order to mitigate the risk of operating laser emitters in the vicinity of aerodromes.

Note 4.— Further guidance on how to protect flight operations from the hazardous effects of laser emitters is contained in the Manual on Laser Emitters and Flight Safety (Doc 9815).

Note 5.— See also Annex 11 — Air Traffic Services, Chapter 2.




Figure 13.1.5-11. Protected flight zones




Figure 13.1.5-12. Multiple runway laser-beam free flight zone




Figure 13.1.5-13. Protected flight zones with indication of maximum irradiance levels for visible laser beams

(3) ***lights which may cause confusion***

(i) Where the Authority is of the opinion that a non-aeronautical ground light, by reason of its intensity, configuration or color, might prevent, or cause confusion in the clear interpretation of aeronautical ground lights, it shall extinguish, screen or otherwise modify the said ground light so as to eliminate such a possibility. In particular, attention shall be directed to a non-aeronautical ground light visible from the air within the areas described hereunder:

- (A) Instrument runway — code number 4: within the areas before the threshold and beyond the end of the runway extending at least 4 500 m in length from the threshold and runway end and 750 m either side of the extended runway center line in width.
- (B) Instrument runway — code number 2 or 3: as in(A), except that the length should be at least 3 000m.
- (C) Instrument runway — code number 1; and non-instrument runway: within the approach area.

(4) ***Aeronautical Ground Lights which may Cause Confusion to Mariners***

Note — In the case of aeronautical ground lights near navigable waters, consideration needs to be given to ensure that the lights do not cause confusion to mariners.

(5) ***Light fixtures and supporting structures***

Note — See section 13.1.9.2(7) for information regarding siting and construction of equipment and installations on operational areas, and the ICAO Aerodrome Design Manual(Doc 9157), Part 6 (in preparation) for guidance on frangibility of light fixtures and supporting structures.

(6) **Elevated Approach Lights**

- (i) Elevated approach lights and their supporting structures shall be frangible except that, in that portion of the approach lighting system beyond 300 m from the threshold:
 - (A) where the height of a supporting structure exceeds 12 m, the frangibility requirement shall apply to the top 12 m only; and
 - (B) where a supporting structure is surrounded by non-frangible objects, only that part of the structure that extends above the surrounding objects shall be frangible.
- (ii) When an approach light fixture or supporting structure is not in itself sufficiently conspicuous, it shall be suitably marked.

(7) **Elevated Lights**

- (i) Elevated runway, stopway and taxiway lights shall be frangible. Their height shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

(8) **Surface Lights**

- (i) Light fixtures inset in the surface of runways, stopways, taxiways and aprons shall be so designed and fitted as to withstand being run over by the wheels of an aircraft without damage either to the aircraft or to the lights themselves.
- (ii) The temperature produced by conduction or radiation at the interface between an installed inset light and an aircraft tire shall not exceed 160°C during a 10-minute period of exposure.

Note. — Guidance on measuring the temperature of inset lights is given in the Aerodrome Design Manual (Doc 9157), Part 4.

(9) **Light Intensity And Control**

Note.— In dusk or poor visibility conditions by day, lighting can be more effective than marking. For lights to be effective in such conditions or in poor visibility by night, they must be of adequate intensity. To obtain the required intensity, it will usually be necessary to make the light directional, in which case the arcs over which the light shows will have to be adequate and so orientated as to meet the operational requirements. The runway lighting system will have to be considered as a whole, to ensure that the relative light intensities are suitably matched to the same end. See Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 15, and the ICAO Aerodrome Design Manual (Doc 9157), Part 4.)

- (i) The intensity of runway lighting shall be adequate for the minimum conditions of visibility and ambient light in which use of the runway is intended, and compatible with that of the nearest section of the approach lighting system when provided.

Note.— While the lights of an approach lighting system may be of higher intensity than the runway lighting, it is good practice to avoid abrupt changes in intensity as these could give a pilot a false impression that the visibility is changing during approach.

- (ii) Where a high-intensity lighting system is provided, a suitable intensity control

shall be incorporated to allow for adjustment of the light intensity to meet the prevailing conditions. Separate intensity controls or other suitable methods shall be provided to ensure that the following systems, when installed, can be operated at compatible intensities:

- (A) approach lighting system;
 - (B) runway edge lights;
 - (C) runway threshold lights;
 - (D) runway end lights;
 - (E) runway center line lights;
 - (F) runway touchdown zone lights; and
 - (G) taxiway center line lights.
- (iii) On the perimeter of and within the ellipse defining the main beam in ICAO Annex 14, Vol. I, Appendix 2, Figures A2-1 to A2-10, the maximum light intensity value shall not be greater than three times the minimum light intensity value measured in accordance with ICAO Annex 14, Vol. I, Appendix 2, collective notes for Figures A2-1 to A2-11 and A2-26, Note 2.
- (iv) On the perimeter of and within the rectangle defining the main beam in ICAO Annex 14 Vol. I, Appendix 2, Figures A2-12 to A2-20, the maximum light intensity value shall not be greater than three times the minimum light intensity value measured in accordance with ICAO Annex 14 Vol. I, Appendix 2, collective notes for Figures A2-12 to A2-21, Note 2.

(b) Emergency Lighting

- (1) **Application.** The Aerodrome Operator shall ensure that at an aerodrome provided with runway lighting and without a secondary power supply, sufficient emergency lights shall be conveniently available for installation on at least the primary runway in the event of failure of the normal lighting system.

Note. — Emergency lighting may also be useful to mark obstacles or delineate taxiways and apron areas.

- (2) **Location.** When installed on a runway the emergency lights shall, as a minimum, conform to the configuration required for a non-instrument runway.
- (3) **Characteristics.** The color of the emergency lights shall conform to the color requirements for runway lighting, except that, where the provision of colored lights at the threshold and the runway end is not practicable, all lights may be variable white or as close to variable white as practicable.

(c) Aeronautical Beacons

(1) Application

- (i) Where operationally necessary an aerodrome beacon or an identification beacon shall be provided by the Aerodrome Operator at each aerodrome intended for use at night.

- (ii) The operational requirement shall be determined having regard to the requirements of the air traffic using the aerodrome, the conspicuity of the aerodrome features in relation to its surroundings and the installation of other visual and non-visual aids useful in locating the aerodrome.

(2) **Aerodrome Beacon**

- (i) An aerodrome beacon shall be provided at an aerodrome intended for use at night if one or more of the following conditions exist:
 - (ii) aircraft navigate predominantly by visual means;
 - (iii) reduced visibilities are frequent; or
 - (iv) it is difficult to locate the aerodrome from the air due to surrounding lights or terrain.

(3) **Location**

- (i) The aerodrome beacon shall be located on or adjacent to the aerodrome in an area of low ambient background lighting.
- (ii) The location of the beacon shall be such that the beacon is not shielded by objects in significant directions and does not dazzle a pilot approaching to land.

(4) **Characteristics**

- (i) The aerodrome beacon shall show either colored flashes alternating with white flashes, or white flashes only. The frequency of total flashes shall be from 20 to 30 per minute. Where used, the colored flashes emitted by beacons at land aerodromes shall be green, and colored flashes emitted by beacons at water aerodromes shall be yellow. In the case of a combined water and land aerodrome, colored flashes, if used, shall have the color characteristics of whichever section of the aerodrome is designated as the principal facility.
- (ii) The light from the beacon shall show at all angles of azimuth. The vertical light distribution shall extend upwards from an elevation of not more than 1° to an elevation determined by the appropriate authority to be sufficient to provide guidance at the maximum elevation at which the beacon is intended to be used, and the effective intensity of the flash shall be not less than 2 000cd.

Note. — At locations where a high ambient background lighting level cannot be avoided, the effective intensity of the flash may be required to be increased by a factor up to a value of 10.

(5) **Identification Beacon**

- (i) **Application:** The Aerodrome Operator shall ensure that an identification beacon shall be provided at an aerodrome which is intended for use at night and cannot be easily identified from the air by other means.

- (ii) **Location**

- (A) The identification beacon shall be located on the aerodrome in an area of

low ambient background lighting.

(B) The location of the beacon shall be such that the beacon is not shielded by objects in significant directions and does not dazzle a pilot approaching to land.

(C) **Characteristics**

1. An identification beacon at a land aerodrome shall show at all angles of azimuth. The vertical light distribution shall extend upwards from an elevation of not more than 1° to an elevation determined by the appropriate authority to be sufficient to provide guidance at the maximum elevation at which the beacon is intended to be used, and the effective intensity of the flash shall be not less than 2 000cd.

Note. — At locations where a high ambient background lighting level cannot be avoided, the effective intensity of the flash may be required to be increased by a factor up to a value of 10.

2. An identification beacon shall show flashing-green at a land aerodrome and flashing- yellow at a water aerodrome.
3. The identification characters shall be transmitted in the International Morse Code.
4. The speed of transmission shall be between six and eight words per minute, the corresponding range of duration of the Morse dots being from 0.15 to 0.2 seconds per dot.

(d) **Approach Lighting Systems**

(1) **Application**

- (i) **Non-instrument runway:** — Where physically practicable, a simple approach lighting system as specified in 13.1.5.3(d)(2)(i)(A) to 13.1.5.3(d)(2)(i)(C) shall be provided to serve a non- instrument runway where the code number is 3 or 4 and intended for use at night, except when the runway is used only in conditions of good visibility and sufficient guidance is provided by other visual aids.

Note. — A simple approach lighting system can also provide visual guidance by day.

- (ii) **Non-precision approach runway:** —Where physically practicable, a simple approach runway, except when the runway is used only in conditions of good visibility or sufficient guidance is provided by other visual aids.

Note. — It is advisable to give consideration to the installation of a precision approach category I lighting system or to the addition of a runway lead-in lighting system.

- (iii) **Precision approach runway category I:** — Where physically practicable, a precision approach category I lighting system as specified in 13.1.5.3(d)(3)(i)(A) to 13.1.5.3(d)(3)(ii)(H) shall be provided to serve a precision

approach runway category I.

- (iv) **Precision approach runway categories II and III:** — A precision approach category II and III lighting system as specified in 13.1.5.3(d)(4)(i)(A) to 13.1.5.3(d)(4)(ii)(J) shall be provided to serve a precision approach runway category II or III.

(2) **Simple approach lighting system**

(i) **Location**

- (A) A simple approach lighting system shall consist of a row of lights on the extended center line of the runway extending, whenever possible, over a distance of not less than 420 m from the threshold with a row of lights forming a crossbar 18 m or 30 m in length at a distance of 300 m from the threshold.
- (B) The lights forming the crossbar shall be as nearly as practicable in a horizontal straight line at right angles to, and bisected by, the line of the center line lights. The lights of the crossbar shall be spaced so as to produce a linear effect, except that, when a crossbar of 30 m is used, gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6m.

Note 1. — Spacings for the crossbar lights between 1 m and 4 m are in use. Gaps on each side of the center line may improve directional guidance when approaches are made with a lateral error, and facilitate the movement of rescue and firefighting vehicles.

Note 2 — See Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 13 for guidance on installation tolerances.

- (C) The lights forming the center line shall be placed at longitudinal intervals of 60 m, except that, when it is desired to improve the guidance, an interval of 30 m may be used. The innermost light shall be located either 60 m or 30 m from the threshold, depending on the longitudinal interval selected for the center line lights.
- (D) If it is not physically possible to provide a center line extending for a distance of 420 m from the threshold, it shall be extended to 300 m so as to include the crossbar. If this is not possible, the center line lights shall be extended as far as practicable, and each center line light shall then consist of a barrette at least 3 m in length. Subject to the approach system having a crossbar at 300 m from the threshold, an additional crossbar may be provided at 150 m from the threshold.
- (E) The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:
- no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
 - no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft.

- Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

(ii) **Characteristics**

- (A) The Aerodrome Operator shall ensure that the lights of a simple approach lighting system shall be fixed lights and the color of the lights shall be such as to ensure that the system is readily distinguishable from other aeronautical ground lights, and from extraneous lighting if present. Each center line light shall consist of either:

- a single source; or
- a barrette at least 3 m in length.

Note 1. — When the barrette as in bullet point 2 above is composed of lights approximating to point sources, a spacing of 1.5 m between adjacent lights in the barrette has been found satisfactory.

Note 2. — It may be advisable to use barrettes 4 m in length if it is anticipated that the simple approach lighting system will be developed into a precision approach lighting system.

Note 3. — At locations where identification of the simple approach lighting system is difficult at night due to surrounding lights, sequence flashing lights installed in the outer portion of the system may resolve this problem.

- (B) Where provided for a non-instrument runway, the lights shall show at all angles in azimuth necessary to a pilot on base leg and final approach. The intensity of the lights shall be adequate for all conditions of visibility and ambient light for which the system has been provided.
- (C) Where provided for a non-precision approach runway, the lights shall show at all angles in azimuth necessary to the pilot of an aircraft which on final approach does not deviate by an abnormal amount from the path defined by the non-visual aid. The lights shall be designed to provide guidance during both day and night in the most adverse conditions of visibility and ambient light for which it is intended that the system should remain usable.

(3) **Precision approach category I lighting system**

(i) **Location**

- (A) A precision approach category I lighting system shall consist of a row of lights on the extended center line of the runway extending, wherever possible, over a distance of 900 m from the runway

Note — The installation of an approach lighting system of less than 900 m in length may result in operational limitations on the use of the runway. See Guidance Material GM-AGA005 Section 13

- (B) threshold with a row of lights forming a crossbar 30 m in length at a distance of 300 m from the runway threshold.

Note. — The installation of an approach lighting system of less than 900 m in length may result in operational limitations on the use of the runway. Guidance can be found in Aerodrome Design Manual Doc 9157.

- (C) The lights forming the crossbar shall be as nearly as practicable in a horizontal straight line at right angles to, and bisected by, the line of the center line lights. The lights of the crossbar shall be spaced so as to produce a linear effect, except that gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6m.

Note 1. — Spacings for the crossbar lights between 1 m and 4 m are in use. Gaps on each side of the center line may improve directional guidance when approaches are made with a lateral error, and facilitate the movement of rescue and firefighting vehicles.

Note 2 — See Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 13 for guidance on installation tolerances.

- The lights forming the center line shall be placed at longitudinal intervals of 30 m with the innermost light located 30 m from the threshold.
- The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:
 - no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
 - no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft. Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

(ii) **Characteristics**

- (A) The center line and crossbar lights of a precision approach category I lighting system shall be fixed lights showing variable white. Each center line light position shall consist of either:
- a single light source in the innermost 300 m of the center line, two light sources in the central 300 m of the center line and three light sources in the outer 300 m of the center line to provide distance information; or a barrette.
- (B) Where the serviceability level of the approach lights specified as a
- (C) maintenance objective in 13.1.10.5(c)(10) can be demonstrated, each center line light position may consist of either: a single light source; or a barrette.
- (D) The barrettes shall be at least 4 m in length. When barrettes are composed of lights approximating to point sources, the lights shall be uniformly

spaced at intervals of not more than 1.5m.

- (E) If the center line consists of barrettes as described in 13.1.5.3(d)(3)(ii)(A₂) or 13.1.5.3(d)(3)(ii)(B₂), each barrette shall be supplemented by a flashing light, except where such lighting is considered unnecessary taking into account the characteristics of the system and the nature of the meteorological conditions.
- (F) Each flashing light as described in 13.1.5.3(d)(3)(ii)(D) shall be flashed twice a second in sequence, beginning with the outermost
- (G) light and progressing toward the threshold to the innermost light of
- (H) the system. The design of the electrical circuit shall be such that these lights can be operated independently of the other lights of the approach lighting system.
- (I) If the center line consists of lights as described in 13.1.5.3(d)(3)(ii)(A₁) or 13.1.5.3(d)(3)(ii)(B₁), additional crossbars of lights to the crossbar provided at 300 m from the threshold shall be provided at 150 m, 450 m, 600 m and 750 m from the threshold. The lights forming each crossbar shall be as nearly as practicable in a horizontal straight line at right angles to, and bisected by, the line of the center line lights. The lights shall be spaced so as to produce a linear effect, except that gaps may be left on each side of the center line. These gaps shall be kept to a minimum to meet local requirements and each shall not exceed 6m.
- (J) Where the additional crossbars described in 13.1.5.3(d)(3)(ii)(F) are incorporated in the system, the outer ends of the crossbars shall lie on two straight lines that either are parallel to the line of the center line lights or converge to meet the runway center line 300 m from threshold.
- (K) The lights shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, Figure A2-1.

Note — The flight path envelopes used in the design of these lights are given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Figure A-8.

(4) **Precision approach category II and III lighting system**

(i) **Location**

- (A) The approach lighting system shall consist of a row of lights on the extended center line of the runway, extending, wherever possible, over a distance of 900 m from the runway threshold. In addition, the system shall have two side rows of lights, extending 270 m from the threshold, and two crossbars, one at 150 m and one at 300 m from the threshold, all as shown in Figure 13.1.5-14.
- (B) Where the serviceability level of the approach lights specified as maintenance objectives in 14.10.5.7 can be demonstrated, the system may have two side rows of lights, extending 240 m from the threshold, and two crossbars, one at 150 m and one at 300 m from the threshold, all as shown in Figure 13.1.5-15.

Note. — The length of 900 m is based on providing guidance for operations under category I, II and III conditions. Reduced lengths may support category II and III operations but may impose limitations on category I operations.

- (C) The lights forming the center line shall be placed at longitudinal intervals of 30 m with the innermost lights located 30 m from the threshold.
- (D) The lights forming the side rows shall be placed on each side of the
- (E) center line, at a longitudinal spacing equal to that of the center line lights and with the first light located 30 m from the threshold. Where the serviceability level of the approach lights specified as maintenance objectives in 13.1.10.5(c)(7) can be demonstrated, lights forming the side rows may be placed on each side of the center line, at a longitudinal spacing of 60 m with the first light located 60 m from the threshold. The lateral spacing (or gauge) between the innermost lights of the side rows shall be not less than 18 m nor more than 22.5 m, and preferably 18 m, but in any event shall be equal to that of the touchdown zone lights.
- (F) The crossbar provided at 150 m from the threshold shall fill in the gaps between the center line and side row lights.
- (G) The crossbar provided at 300 m from the threshold shall extend on both sides of the center line lights to a distance of 15 m from the centerline.
- (H) If the center line beyond a distance of 300 m from the threshold consists of lights as described in 13.1.5.3(d)(4)(ii)(B) or 13.1.5.3(d)(4)(ii)(C), additional crossbars of lights shall be provided at 450m, 600 m and 750 m from the threshold.




Figure 13.1.5-14: Inner 300 m approach and runway lighting for precision approach runways, categories II and III




Figure 13.1.5-15. Inner 300 m approach and runway lighting for precision approach runways, categories II and III, where the serviceability levels of the lights specified as maintenance objectives in 13.1.10 can be demonstrated

- (I) Where the additional crossbars described in (7) are incorporated in the

system, the outer ends of these crossbars shall lie on two straight lines that either are parallel to the center line or converge to meet the runway center line 300 m from the threshold.

- (J) The system shall lie as nearly as practicable in the horizontal plane passing through the threshold, provided that:
- no object other than an ILS or MLS azimuth antenna shall protrude through the plane of the approach lights within a distance of 60 m from the center line of the system; and
 - no light other than a light located within the central part of a crossbar or a center line barrette (not their extremities) shall be screened from an approaching aircraft.
- (K) Any ILS or MLS azimuth antenna protruding through the plane of the lights shall be treated as an obstacle and marked and lighted accordingly.

(ii) **Characteristics**

- (A) The center line of a precision approach category II and III lighting system for the first 300 m from the threshold shall consist of barrettes showing variable white, except that, where the threshold is displaced 300 m or more, the center line may consist of single light sources showing variable white. Where the serviceability level of the approach lights specified as maintenance objectives in 13.1.10.5(c)(7) can be demonstrated, the center line of a precision approach category II and III lighting system for the first 300 m from the threshold may consist of either:

- barrettes, where the center line beyond 300 m from the threshold consists of barrettes as described in 13.1.5.3(d)(4)(ii) (C1); or
-
- alternate single light sources and barrettes, where the center line beyond 300 m from the threshold consists of single light sources as described in 13.1.5.3(d)(4)(ii)(C2), with the innermost single light source located 30 m and the innermost barrette located 60 m from the threshold; or
-
- single light sources where the threshold is displaced 300 m or more;

all of which shall show variable white.

- (B) Beyond 300 m from the threshold each center line light position shall consist of either:

a barrette as used on the inner 300 m; or

two light sources in the central 300 m of the center line and three light sources in the outer 300 m of the center line; all of which shall show variable white.

- (C) Where the serviceability level of the approach lights specified as maintenance objectives in 13.1.10.5(c)(7) can be demonstrated, beyond 300 m from the threshold each center line light position may consist of either:

a barrette; or

a single light source; all of which shall show variable white.

- (D) The barrettes shall be at least 4 m in length. When barrettes are composed of lights approximating to point sources, the lights shall be uniformly spaced at intervals of not more than 1.5m.
- (E) If the center line beyond 300 m from the threshold consists of barrettes as described in 13.1.5.3(d)(4)(ii)(B1) or 13.1.5.3(d)(4)(ii)(C1), each barrette beyond 300 m shall be supplemented by a flashing light, except where such lighting is considered unnecessary taking into account the characteristics of the system and the nature of the meteorological conditions.
- (F) Each flashing light as described in 13.1.5.3(d)(4)(ii)(E) shall be flashed twice a second in sequence, beginning with the outermost light and progressing toward the threshold to the innermost light of the system. The design of the electrical circuit shall be such that these lights can be operated independently of the other lights of the approach lighting system.
- (G) The side row shall consist of barrettes showing red. The length of a side row barrette and the spacing of its lights shall be equal to those of the touchdown zone light barrettes.
- (H) The lights forming the crossbars shall be fixed lights showing variable white. The lights shall be uniformly spaced at intervals of not more than 2.7 m.
- (I) The intensity of the red lights shall be compatible with the intensity of the white lights.
- (J) The lights shall be in accordance with the specifications of Appendix 2, Figures A2-1 and A2-2.

(e) Visual Approach Slope Indicator Systems

(1) Application

- (i) A visual approach slope indicator system shall be provided to serve the approach to a runway whether or not the runway is served by other visual approach aids or by non-visual aids, where one or more of the
- (ii) following conditions exist:
 - (A) the runway is used by turbojet or other aeroplanes with similar approach guidance requirements;
 - (B) the pilot of any type of aeroplane may have difficulty in judging the approach due to:

inadequate visual guidance such as is experienced during an approach over water or featureless terrain by day or in the absence of sufficient extraneous lights in the approach area by night; or

misleading information such as is produced by deceptive surrounding terrain or runway slopes;

- (C) the presence of objects in the approach area may involve serious hazard if an aeroplane descends below the normal approach path, particularly if there are no non-visual or other visual aids to give warning of such objects;
- (D) physical conditions at either end of the runway present a serious hazard in the event of an aeroplane undershooting or overrunning the runway; and
- (E) terrain or prevalent meteorological conditions are such that the aeroplane may be subjected to unusual turbulence during approach.

Note — Guidance on the priority of installation of visual approach slope indicator systems is contained in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 14.




Figure 13.1.5-16. Visual approach slope indicator systems

- (iii) The standard visual approach slope indicator systems shall consist of the following:
 - (A) T-VASIS and AT-VASIS conforming to the specifications contained in 13.1.5.3(e)(2)(i)(A) to 13.1.5.3(e)(2)(iv)(E) inclusive;
 - (B) PAPI and APAPI systems conforming to the specifications contained in 13.1.5.3(e)(3)(i)(A) to 13.1.5.3(e)(3)(iv)(F) inclusive; as shown in Figure 13.1.5-16.
- (iv) PAPI, T-VASIS or AT-VASIS shall be provided where the code number is 3 or 4 when one or more of the conditions specified in 13.1.5.3(e)(1)(i) exist.

Note- As of 1 January 2020, the use of T-VASIS and AT-VASIS as standard visual approach slope indicator systems shall be discontinued.

- (v) PAPI or APAPI shall be provided where the code number is 1 or 2 when one or

more of the conditions specified in 13.1.5.3(e)(1)(i) exist.

- (vi) Where a runway threshold is temporarily displaced from the normal position and one or more of the conditions specified in 13.1.5.3(e)(1)(i) exist, a PAPI shall be provided except that where the code number is 1 or 2 an APAPI may be provided.

(2) **T-VASIS and AT-VASIS**

(i) **Description**

- (A) The T-VASIS shall consist of twenty light units symmetrically disposed about the runway center line in the form of two wing bars of four light units each, with bisecting longitudinal lines of six lights, as shown in Figure 13.1.5-17.
- (B) The AT-VASIS shall consist of ten light units arranged on one side of the runway in the form of a single wing bar of four light units with a bisecting longitudinal line of six lights.
- (C) The light units shall be constructed and arranged in such a manner that the pilot of an aeroplane during an approach will:
- when above the approach slope, see the wing bar(s) white, and one, two or three fly-down lights, the more fly-down lights being visible the higher the pilot is above the approach slope;
 - when on the approach slope, see the wing bar(s) white; and
 - when below the approach slope, see the wing bar(s) and one, two or three fly-up lights white, the more fly-up lights being visible the lower the pilot is below the approach slope; and when well below the approach slope, see the wing bar(s) and the three fly-up lights red. When on or above the approach slope, no light shall be visible from the fly-up light units;
 - when on or below the approach slope, no light shall be visible from the fly-down light units.

(ii) **Siting**

- (A) The light units shall be located as shown in Figure 13.1.5-17, subject to the installation tolerances given therein.

Note. — The siting of T-VASIS will provide, for a 3° slope and a nominal eye height over the threshold of 15 m (see 13.1.5.3(e)(2)(i)(A) and 13.1.5.3(e)(2)(iv)(B), a pilot's eye height over threshold of 13 m to 17 m when only the wing bar lights are visible. If increased eye height at the threshold is required (to provide adequate wheel clearance), then the approaches may be flown with one or more fly-down lights visible. The pilot's eye height over the threshold is then of the following order:

Wing bar lights and one fly-down light visible 17 m to 22m

Wing bar lights and two fly-down lights visible 22 m to 28 m

Wing bar lights and three fly-down lights visible 28 m to 54 m.

(iii) **Characteristics of the light units**

- (A) The systems shall be suitable for both day and night operations.
- (B) The light distribution of the beam of each light unit shall be of fan shape showing over a wide arc in azimuth in the approach direction. The wing bar light units shall produce a beam of white light from $1^{\circ}54'$ vertical angle up to 6° vertical angle and a beam of red light from 0° to $1^{\circ}54'$ vertical angle. The fly-down light units shall produce a white beam extending from an elevation of 6° down to approximately the approach slope, where it shall have a sharp cut-off. The fly-up light units shall produce a white beam from approximately the approach slope down to $1^{\circ}54'$ vertical angle and a red beam below a $1^{\circ}54'$ vertical angle. The angle of the top of the red beam in the wing bar units and fly-up units may be increased to comply with 13.1.5.3(e)(2)(iv)(D).
- (C) The light intensity distribution of the fly-down, wing bar and fly-up light units shall be as shown in Appendix 2, Figure A2-22.
- (D) The color transition from red to white in the vertical plane shall be such as to appear to an observer, at a distance of not less than 300 m, to occur over a vertical angle of not more than $15'$.
- (E) At full intensity the red light shall have a Y coordinate not exceeding 0.320.
- (F) A suitable intensity control shall be provided to allow adjustments to meet the prevailing conditions and to avoid dazzling the pilot during approach and landing.

(G)




Figure 13.1.5-17: Sitting of light units for T-VASIS

- (H) The light units forming the wing bars, or the light units forming a fly-down or a fly-up matched pair, shall be mounted so as to appear to the pilot of an approaching aeroplane to be substantially in a horizontal line. The light units shall be mounted as low as possible and shall be frangible.
 - (I) The light units shall be so designed that deposits of condensation, dirt, etc., on optically transmitting or reflecting surfaces shall interfere to the least possible extent with the light signals and shall in no way affect the elevation of the beams or the contrast between the red and white signals. The construction of the light units shall be such as to minimize the probability of the slots being wholly or partially blocked by snow or ice where these conditions are likely to be countered.
- (iv) **Approach slope and elevation setting of light beams**
- (A) The approach slope shall be appropriate for use by the aeroplanes using the approach.
 - (B) When the runway on which a T-VASIS is provided is equipped with an ILS and/or MLS, the siting and elevations of the light units shall be such that the visual approach slope conforms as closely as possible with the glide path of the ILS and/or the minimum glide path of the MLS, as appropriate.
 - (C) The elevation of the beams of the wing bar light units on both sides of the runway shall be the same. The elevation of the top of the beam of the fly-up light unit nearest to each wing bar, and that of the bottom of the beam of the fly down light unit nearest to each wing bar, shall be equal and shall correspond to the approach slope. The cut-off angle of the top of the beams of successive fly-up light units shall decrease by 5' of arc in angle of elevation at each successive unit away from the wing bar. The cut-in angle of the bottom of the beam of the fly-down light units shall increase by 7' of arc at each successive unit away from the wing bar (see Figure 13.1.5-18).
 - (D) The elevation setting of the top of the red light beams of the wing bar and fly-up light units shall be such that, during an approach, the pilot of an aeroplane to whom the wing bar and three fly-up light units are visible would clear all objects in the approach area by a safe margin if any such light did not appear.
 - (E) The azimuth spread of the light beam shall be suitably restricted where an object located outside the obstacle protection surface of the system, but within the lateral limits of its light beam, is found to extend above the plane of the obstacle protection surface and an aeronautical study indicates that the object could adversely affect the safety of operations. The extent of the restriction shall be such that the object remains outside the confines of the light beam.
Note. — See 13.1.5.3(e)(3)(v)(A), to 13.1.5.3(e)(3)(v)(E), concerning the related obstacle protection surface.




Figure 13.1.5-18: Light beams and elevation settings of T-VASIS and AT-VASIS

(3) **PAPI AND APAPI**

(i) **Description**

- (A) The PAPI system shall consist of a wing bar of four sharp transition multi-lamp (or paired single lamp) units equally spaced. The system shall be located on the left side of the runway unless it is physically impracticable to do so.

Note. — Where a runway is used by aircraft requiring visual roll guidance which is not provided by other external means, then a second wing bar may be provided on the opposite side of the runway.

- (B) The APAPI system shall consist of a wing bar of two sharp transition multi-lamp (or paired single lamp) units. The system shall be located on the left side of the runway unless it is physically impracticable to do so.

Note. — Where a runway is used by aircraft requiring visual roll guidance which is not provided by other external means, then a second wing bar may be provided on the opposite side of the runway.

- (C) The wing bar of a PAPI shall be constructed and arranged in such a manner that a pilot making an approach will:

- when on or close to the approach slope, see the two units nearest the runway as red and the two units farthest from the runway as white;
- when above the approach slope, see the one unit nearest the runway as red and the three units farthest from the runway as white; and when further above the approach slope, see all the units as white; and
- when below the approach slope, see the three units nearest the

runway as red and the unit farthest from the runway as white; and when further below the approach slope, see all the units as red.

(D) The wing bar of an APAPI shall be constructed and arranged in such a manner that a pilot making an approach will:

- when on or close to the approach slope, see the unit nearer the runway as red and the unit farther from the runway as white;
- when above the approach slope, see both the units as white; and
- when below the approach slope, see both the units as red.

(ii) **Siting**

(A) The light units shall be located as in the basic configuration illustrated in Figure 13.1.5-19, subject to the installation tolerances given therein. The units forming a wing bar shall be mounted so as to appear to the pilot of an approaching aeroplane to be substantially in a horizontal line. The light units shall be mounted as low as possible and shall be frangible.

(iii) **Characteristics of the light units**

(A) The system shall be suitable for both day and night operations.

(B) The color transition from red to white in the vertical plane shall be such as to appear to an observer, at a distance of not less than 300 m, to occur within a vertical angle of not more than 3°.

(C) At full intensity the red light shall have a Y coordinate not exceeding 0.320.

(D) The light intensity distribution of the light units shall be as shown in Appendix 2, Figure A2-23.

Note. — See the Aerodrome Design Manual (Doc 9157), Part 4, for additional guidance on the characteristics of light units.

(E) Suitable intensity control shall be provided so as to allow adjustment to meet the prevailing conditions and to avoid dazzling the pilot during approach and landing.

(F) Each light unit shall be capable of adjustment in elevation so that the lower limit of the white part of the beam may be fixed at any desired angle of elevation between 1°30' and at least 4°30' above the horizontal.

(G) The light units shall be so designed that deposits of condensation, dust, dirt, etc., on optically transmitting or reflecting surfaces shall interfere to the least possible extent with the light signals and shall not affect the contrast between the red and white signals and the elevation of the transition sector.




Figure 13.1.5-19. Siting of PAPI and APAPI




Figure 13.1.5-20 Light beams and angle of elevation setting of PAPI and APAPI

Table 13.1.5-2. Wheel clearance over threshold for PAPI and APAPI

Eye-to-wheel height of aeroplane in the approach configuration ^a	Desired wheel clearance (metres) ^{b,f}	Minimum wheel clearance (metres) ^d
(1)	(2)	(3)
up to but not including 3 m	6	3*
3 m up to but not including 5 m	9	4
5 m up to but not including 8 m	9	5
8 m up to but not including 14 m	9	6

a. In selecting the eye-to-wheel height group, only aeroplanes meant to use the system on a regular basis shall be considered. The most demanding amongst such aeroplanes shall determine the eye-to-wheel height group.

b. Where practicable the desired wheel clearances shown in column (2) shall be provided.

c. The wheel clearances in column (2) may be reduced to no less than those in column (3) where an aeronautical study indicates that such reduced wheel clearances are acceptable.

d. When a reduced wheel clearance is provided at a displaced threshold it shall be ensured that the corresponding desired wheel clearance specified in column (2) will be available when an aeroplane at the top end of the eye-to-wheel height group chosen overflies the extremity of the runway.

e. This wheel clearance may be reduced to 1.5 m on runways used mainly by light-weight non-turbojet aeroplanes.

(iv) **Approach slope and elevation setting of light units**

- (A) The approach slope as defined in Figure 13.1.5-20 shall be appropriate for use by the aeroplanes using the approach.
- (B) When the runway is equipped with an ILS and/or MLS, the siting and the angle of elevation of the light units shall be such that the visual approach slope conforms as closely as possible with the glide path of the ILS and/or the minimum glide path of the MLS, as appropriate.
- (C) The angle of elevation settings of the light units in a PAPI wing bar shall be such that, during an approach, the pilot of an aeroplane observing a signal of one white and three reds will clear all objects in the approach area by a safe margin (see Table 13.1.5-2).
- (D) The angle of elevation settings of the light units in an APAPI wing bar shall be such that, during an approach, the pilot of an aeroplane observing the lowest onslope signal, i.e. one white and one red, will clear all objects in the approach area by a safe margin (see Table 5-2).
- (E) The azimuth spread of the light beam shall be suitably restricted where an object located outside the obstacle protection surface of the PAPI or APAPI system, but within the lateral limits of its light beam, is found to extend above the plane of the obstacle protection surface and an aeronautical study indicates that the object could adversely affect the safety of operations. The extent of the restriction shall be such that the object remains outside the confines of the light beam.
- Note.* — See 13.1.5.3(e)(3)(v)(A), to 13.1.5.3(e)(3)(v)(E), concerning the related obstacle protection surface.
- (F) Where wing bars are installed on each side of the runway to provide roll guidance, corresponding units shall be set at the same angle so that the signals of each wing bar change symmetrically at the same time.

(v) **Obstacle Protection Surface**

The following specifications shall be applicable to T-VASIS, AT-VASIS, PAPI and APAPI.

- (A) An obstacle protection surface shall be established when it is intended to provide a visual approach slope indicator system.
- (B) The characteristics of the obstacle protection surface, i.e. origin, divergence, length and slope, shall correspond to those specified in the relevant column of Table 13.1.5-3 and in Figure 13.1.5-21.
- (C) New objects or extensions of existing objects shall not be permitted above an obstacle protection surface except when, in the opinion of the appropriate authority, the new object or extension would be shielded by an existing immovable object.

Note. — Circumstances in which the shielding principle may reasonably be applied are described in the Airport Services Manual (Doc 9137), Part 6

- (D) Existing objects above an obstacle protection surface shall be removed except when, in the opinion of the appropriate authority, the object is shielded by an existing immovable object, or after aeronautical study it is determined that the object would not adversely affect the safety of operations of aeroplanes.

Table 13.1.5-3. Dimensions and slopes of the obstacle protection surface

Surface dimensions	Runway type/code number							
	Non-instrument Code number				Instrument Code number			
	1	2	3	4	1	2	3	4
Length of inner edge	60 m	80 m ^a	150 m	150 m	150 m	150 m	300 m	300 m
Distance from the visual approach slope indicator system ^e	D ₁ +30 m	D ₁ +60 m	D ₁ +60 m	D ₁ +60 m	D ₁ +60 m	D ₁ +60 m	D ₁ +60 m	D ₁ +60 m
Divergence (each side)	10%	10%	10%	10%	15%	15%	15%	15%
Total length	7 500 m	7 500 m ^b	15 000 m	15 000 m	7 500 m	7 500 m ^b	15 000 m	15 000 m
<i>Slope</i>								
a) T-VASIS and AT-VASIS	– ^c	1.9°	1.9°	1.9°	–	1.9°	1.9°	1.9°
b) PAPI ^d	–	A–0.57°	A–0.57°	A–0.57°	A–0.57°	A–0.57°	A–0.57°	A–0.57°
c) APAPI ^d	A–0.9°	A–0.9°	–	–	A–0.9°	A–0.9°	–	–
<p>a. This length is to be increased to 150 m for a T-VASIS or AT-VASIS.</p> <p>b. This length is to be increased to 15 000 m for a T-VASIS or AT-VASIS.</p> <p>c. No slope has been specified if a system is unlikely to be used on runway type/code number indicated.</p> <p>d. Angles as indicated in Figure 5-20.</p> <p>e. D₁ is the distance of the visual approach slope indicator system from threshold prior to any displacement to remedy object penetration of the OPS (refer Figure 5-19). The start of the OPS is fixed to the visual approach slope indicator system location, such that displacement of the PAPI results in an equal displacement of the start of the OPS. See 5.3.5.46 e).</p>								




Figure 13.1.5-21. obstacle protection surface for visual approach slope indicator system

(E) Where an aeronautical study indicates that an existing object extending above an obstacle protection surface (OPS) could adversely affect the safety of operations of aeroplanes, the Aerodrome Operator shall take one or more of the following measures:

- remove the object;
- suitably raise the approach slope of the system;
- reduce the azimuth spread of the system so that the object is outside the confines of the beam;
- displace the axis of the system and its associated obstacle protection surface by no more than 5°; and
- suitably displace the system upwind of the threshold such that the object no longer penetrates the OPS.

Note 1. — Guidance on this issue is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

Note 2. — The displacement of the system upwind of the threshold reduces the operational landing distance.

(f) Circling Guidance Lights

- (1) **Application.** Circling guidance lights shall be provided when existing approach and runway lighting systems do not satisfactorily permit identification of the runway and/or approach area to a circling aircraft in the conditions for which it is intended the runway be used for circling approaches.
- (2) **Location**
 - (i) The location and number of circling guidance lights shall be adequate to enable a pilot, as appropriate, to:
 - (A) join the downwind leg or align and adjust the aircraft's track to the runway at a required distance from it and to distinguish the threshold in passing; and
 - (B) keep in sight the runway threshold and/or other features which will make it possible to judge the turn on to base leg and final approach, taking into account the guidance provided by other visual aids.
 - (ii) Circling guidance lights shall consist of:
 - (A) lights indicating the extended center line of the runway and/or parts of any approach lighting system; or
 - (B) lights indicating the position of the runway threshold; or
 - (C) lights indicating the direction or location of the runway; or a combination of such lights as is appropriate to the runway under consideration.

Note. — Guidance on installation of circling guidance lights is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (3) **Characteristics**
 - (i) Circling guidance lights shall be fixed or flashing lights of an intensity and beam spread adequate for the conditions of visibility and ambient light in which it is intended to make visual circling approaches. The flashing lights shall be white, and the steady lights either white or gaseous discharge lights.
 - (ii) The lights shall be designed and be installed in such a manner that they will not dazzle or confuse a pilot when approaching to land, taking off or taxiing.

(g) Runway Lead-In Lighting Systems

- (1) **Application.** A runway lead-in lighting system shall be provided where it is desired to provide visual guidance along a specific approach path, for reasons such as avoiding hazardous terrain or for purposes of noise abatement.

Note. — Guidance on providing lead-in lighting systems is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (2) **Location**
 - (i) A runway lead-in lighting system shall consist of groups of lights positioned so as to define the desired approach path and so that one group may be sighted from the preceding group. The interval between adjacent groups should not exceed approximately 1 600 m.

Note. — Runway lead-in lighting systems may be curved, straight or a combination thereof.

- (ii) A runway lead-in lighting system shall extend from a point as determined by the appropriate authority, up to a point where the approach lighting system, if provided, or the runway or the runway lighting system is in view.

(3) **Characteristics**

- (i) Each group of lights of a runway lead-in lighting system shall consist of at least three flashing lights in a linear or cluster configuration. The system may be augmented by steady burning lights where such lights would assist in identifying the system.
- (ii) The flashing lights and the steady burning lights shall be white.
- (iii) Where practicable, the flashing lights in each group shall flash in sequence towards the runway.

(h) **Runway Threshold Identification Lights**

- (1) **Application.** Runway threshold identification lights shall be installed:

- (i) at the threshold of a non-precision approach runway when additional threshold conspicuity is necessary or where it is not practicable to provide other approach lighting aids; and
- (ii) where a runway threshold is permanently displaced from the runway extremity or temporarily displaced from the normal position and additional threshold conspicuity is necessary.

- (2) **Location.** Runway threshold identification lights shall be located symmetrically about the runway center line, in line with the threshold and approximately 10 m outside each line of runway edge lights.

(3) **Characteristics**

- (i) Runway threshold identification lights shall be flashing white lights with a flash frequency between 60 and 120 per minute.
- (ii) The lights shall be visible only in the direction of approach to the runway.

(i) **Runway Edge Lights**

(1) **Application**

- (i) Runway edge lights shall be provided for a runway intended for use at night or for a precision approach runway intended for use by day or night.
- (ii) Runway edge lights shall be provided on a runway intended for take-off with an operating minimum below an RVR of the order of 800 m by day.

(2) **Location**

- (i) Runway edge lights shall be placed along the full length of the runway and shall be in two parallel rows equidistant from the center line.

- (ii) Runway edge lights shall be placed along the edges of the area declared for use as the runway or outside the edges of the area at a distance of not more than 3m.
- (iii) Where the width of the area which could be declared as runway exceeds 60 m, the distance between the rows of lights shall be determined taking into account the nature of the operations, the light distribution characteristics of the runway edge lights, and other visual aids serving the runway.
- (iv) The lights shall be uniformly spaced in rows at intervals of not more than 60 m for an instrument runway, and at intervals of not more than 100 m for a non-instrument runway. The lights on opposite sides of the runway axis shall be on lines at right angles to that axis. At intersections of runways, lights may be spaced irregularly or omitted, provided that adequate guidance remains available to the pilot.

(3) **Characteristics**

- (i) Runway edge lights shall be fixed lights showing variable white, except that:
 - (A) in the case of a displaced threshold, the lights between the beginning of the runway and the displaced threshold shall show red in the approach direction; and
 - (B) a section of the lights 600 m or one-third of the runway length, whichever is the less, at the remote end of the runway from the end at which the take-off run is started, may show yellow.
- (ii) The runway edge lights shall show at all angles in azimuth necessary to provide guidance to a pilot landing or taking off in either direction. When the runway edge lights are intended to provide circling guidance, they shall show at all angles in azimuth (see 13.1.5.3(f)(1)).
- (iii) In all angles of azimuth required in 13.1.5.3(i)(3)(ii), runway edge lights shall show at angles up to 15° above the horizontal with an intensity adequate for the conditions of visibility and ambient light in which use of

the runway for take-off or landing is intended. In any case, the intensity shall be at least 50 cd except that at an aerodrome without extraneous lighting, the intensity of the lights may be reduced to not less than 25 cd to avoid dazzling the pilot.

- (iv) Runway edge lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-9 or A2-10.

(j) **Runway Threshold And Wing Bar Lights**

(See ICAO Annex 14 Vol. I, Figure 5-22)

- (1) **Application of runway threshold lights.** Runway threshold lights shall be provided for a runway equipped with runway edge lights, except on a non-instrument or non-precision approach runway where the threshold is displaced and wing bar lights are provided.
- (2) **Location of runway threshold lights**
 - (i) When a threshold is at the extremity of a runway, the threshold lights shall be

placed in a row at right angles to the runway axis as near to the extremity of the runway as possible and, in any case, not more than 3 m outside the extremity.

- (ii) When a threshold is displaced from the extremity of a runway, threshold lights shall be placed in a row at right angles to the runway axis at the displaced threshold.
- (iii) Threshold lighting shall consist of:
 - (A) on a non-instrument or non-precision approach runway, at least six lights;
 - (B) on a precision approach runway category I, at least the number of lights that would be required if the lights were uniformly spaced at intervals of 3 m between the rows of runway edge lights; and
 - (C) on a precision approach runway category II or III, lights uniformly spaced between the rows of runway edge lights at intervals of not more than 3m.
- (iv) The lights prescribed in 13.1.5.3(j)(2)(iii)(A) & (B) shall be either:
 - (A) equally spaced between the rows of runway edge lights; or
 - (B) symmetrically disposed about the runway center line in two groups, with the lights uniformly spaced in each group and with a gap between the groups equal to the gauge of the touchdown zone marking or lighting, where such is provided, or otherwise not more than half the distance between the rows of runway edge lights.

(3) ***Application of wing bar lights***

- (i) Wing bar lights shall be provided on a precision approach runway when

additional conspicuity is considered desirable.
- (ii) Wing bar lights shall be provided on a non-instrument or non-precision approach runway where the threshold is displaced and runway threshold lights are required, but are not provided.

- (4) ***Location of wing bar lights.*** Wing bar lights shall be symmetrically disposed about the runway center line at the threshold in two groups, i.e. wing bars. Each wing bar shall be formed by at least five lights extending at least 10 m outward from, and at right angles to, the line of the runway edge lights, with the innermost light of each wing bar in the line of the runway edge lights.




FIGURE 5-22. ARRANGEMENT OF RUNWAY THRESHOLD AND RUNWAY END LIGHTS

(5) **Characteristics of runway threshold and wing bar lights**

- (i) Runway threshold and wing bar lights shall be fixed unidirectional lights showing green in the direction of approach to the runway. The intensity and beam spread of the lights shall be adequate for the conditions of visibility and ambient light in which use of the runway is intended.
- (ii) Runway threshold lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-3.
- (iii) Threshold wing bar lights on a precision approach runway shall be in accordance with the specifications of Appendix 2, Figure A2-4.

(k) **Runway End Lights**

Note.—see **Figure 13.1.5-22**

- (1) **Application.** Runway end lights shall be provided for a runway equipped with runway edge lights.
Note.— When the threshold is at the runway extremity, fittings serving as threshold lights may be used as runway endlights.

(2) **Location**

- (i) Runway end lights shall be placed on a line at right angles to the runway axis as near to the end of the runway as possible and, in any case, not more than 3 m outside the end.
- (ii) Runway end lighting shall consist of at least six lights. The lights shall be either:
 - (A) equally spaced between the rows of runway edge lights; or
 - (B) symmetrically disposed about the runway center line in two groups with the lights uniformly spaced in each group and with a gap between the groups of not more than half the distance between the rows of runway edge lights.
For a precision approach runway category III, the spacing between runway end lights, except between the two innermost lights if a gap is used, shall not exceed 6m.

(3) **Characteristics**

- (i) Runway end lights shall be fixed unidirectional lights showing red in the direction of the runway. The intensity and beam spread of the lights shall be adequate for the conditions of visibility and ambient light in which use of the runway is intended.
- (ii) Runway end lights on a precision approach runway shall be in accordance with the specifications as stated herein.

(1) **Runway Center Line Lights**

(1) **Application**

- (i) Runway center line lights shall be provided on a precision approach runway category II or III.
- (ii) Runway center line lights should be provided on a precision approach runway category I, particularly when the runway is used by aircraft with high landing speeds or where the width between the runway edge lights is greater than 50 m.
- (iii) Runway center line lights shall be provided on a runway intended to be used for take-off with an operating minimum below an RVR of the order of 400m.
- (iv) Runway center line lights shall be provided on a runway intended to be used for takeoff with an operating minimum of an RVR of the order of 400 m or higher when used by aeroplanes with a very high take-off speed, particularly where the width between the runway edge lights is greater than 50m.

(2) **Location**

- (i) Runway center line lights shall be located along the center line of the runway, except that the lights may be uniformly offset to the same side of the runway center line by not more than 60 cm where it is not practicable to locate them along the center line. The lights shall be located from the threshold to the end at longitudinal spacing of approximately 15 m. Where the serviceability level

of the runway center line lights specified as maintenance objectives in 13.1.10.5(c)(7) or 13.1.10.5(c)(11), as appropriate, can be demonstrated and the runway is intended for use in runway visual range conditions of 350 m or greater, the longitudinal spacing may be approximately 30m.

Note.— Existing center line lighting where lights are spaced at 7.5 m need not be replaced.

- (ii) Center line guidance for take-off from the beginning of a runway to a displaced threshold shall be provided by:
 - (A) an approach lighting system if its characteristics and intensity settings afford the guidance required during take-off and it does not dazzle the pilot of an aircraft taking off; or
 - (B) runway center line lights; or
 - (C) barrettes of at least 3 m in length and spaced at uniform intervals of 30 m, as shown in Figure 13.1.5-23, designed so that their photometric characteristics and intensity setting afford the guidance required during take-off without dazzling the pilot of an aircraft taking off.
- (iii) Where necessary, provision should be made to extinguish those center line lights specified in b) or reset the intensity of the approach lighting system or barrettes when the runway is being used for landing. In no case should only the single source runway center line lights show from the beginning of the runway to a displaced threshold when the runway is being used for landing.

(3) **Characteristics**

- (i) Runway center line lights shall be fixed lights showing variable white

from the threshold to the point 900 m from the runway end; alternate red and variable white from 900 m to 300 m from the runway end; and red from 300 m to the runway end, except that for runways less than

- (ii) 1800 m in length, the alternate red and variable white lights shall extend from the midpoint of the runway usable for landing to 300 m from the runway end.




Figure 13.1.5-23. Example of approach and runway lighting for runway with displaced thresholds.

Note.— Care is required in the design of the electrical system to ensure that failure of part of the electrical system will not result in a false indication of the runway distance remaining.

- (iii) Runway center line lights shall be in accordance with the specifications ICAO Annex 14 Vol. I, Appendix 2, Figure A2-6 or A2-7.

(m) Runway Touchdown Zone Lights

- (1) **Application.** Touchdown zone (TDZ) lights shall be provided in the touchdown zone of a precision approach runway category II or III.
- (2) **Location.** Touchdown zone lights shall extend from the threshold for a longitudinal distance of 900 m, except that, on runways less than 1 800 m in length, the system shall be shortened so that it does not extend beyond the midpoint of the runway. The pattern shall be formed by pairs of barrettes symmetrically located about the runway center line. The lateral spacing between the innermost lights of a pair of barrettes shall be equal to the lateral spacing selected for the touchdown zone marking. The longitudinal spacing between pairs of barrettes shall be either 30 m or 60m.

Note. — To allow for operations at lower visibility minima, it may be advisable to use a 30 m longitudinal spacing between barrettes.

(3) **Characteristics**

- (i) A barrette shall be composed of at least three lights with a spacing between the lights of not more than 1.5m.
- (ii) A barrette shall be not less than 3 m nor more than 4.5 m in length.
- (iii) Touchdown zone lights shall be fixed unidirectional lights showing variable white.
- (iv) Touchdown zone lights shall be in accordance with the specifications of Appendix 2, Figure A2-5.

(n) **Simple Touchdown Zone Lights**

Note.— The purpose of simple touchdown zone lights is to provide pilots with enhanced situational awareness in all visibility conditions and to help enable pilots to decide whether to commence a go-around if the aircraft has not landed by a certain point on the runway. It is essential that pilots operating at aerodromes with simple touchdown zone lights be familiar with the purpose of these lights.

- (1) **Application.** Except where TDZ lights are provided in accordance with paragraph (m) above, at an aerodrome where the approach angle is greater than 3.5 degrees and/or the Landing Distance Available combined with other factors increases the risk of an overrun, simple touchdown zone lights shall be provided.

(2) **Location**

- (i) Simple touchdown zone lights shall be a pair of lights located on each side of the runway center line 0.3 m beyond the upwind edge of the final touchdown zone marking. The lateral spacing between the inner lights of the two pairs of lights shall be equal to the lateral spacing selected for the touchdown zone marking. The spacing between the lights of the same pair shall not be more than 1.5 m or half the width of the touchdown zone marking, whichever is greater. (See Figure 13.1.5-24.)
- (ii) Where provided on a runway without TDZ markings, simple touchdown zone lights shall be installed in such a position that provides the equivalent TDZ information.

(3) **Characteristics**

- (i) Simple touchdown zone lights shall be fixed unidirectional lights showing variable white, aligned so as to be visible to the pilot of a landing aeroplane in the direction of approach to the runway.
- (ii) Simple touchdown zone lights shall be in accordance with the specifications in Appendix 2, Figure A2-5.

Note. — As a good operating practice, simple touchdown zone lights are supplied with power on a separate circuit to other runway lighting so that they may be used when other lighting is switched off.




FIGURE 13.1.5-24. SIMPLE TOUCHDOWN ZONE LIGHTING

(o) **Rapid exit taxiway indicator lights**

Note.— The purpose of rapid exit taxiway indicator lights (RETILs) is to provide pilots with distance-to-go information to the nearest rapid exit taxiway on the runway, to enhance situational awareness in low visibility conditions and enable pilots to apply braking action for more efficient roll-out and runway exit speeds. It is essential that pilots operating at aerodromes with runway(s) displaying rapid exit taxiway indicator lights be familiar with the purpose of these lights.

(1) **Application**

- (i) Rapid exit taxiway indicator lights shall be provided on a runway intended for use in runway visual range conditions less than a value of 350 m and/or where the traffic density is heavy.

Note.— See Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 16.

- (ii) Rapid exit taxiway indicator lights shall not be displayed in the event of any

lamp failure or other failure that prevents the display of the light pattern depicted in Figure 13.1.5-25, in full.

(2) **Location**

- (i) A set of rapid exit taxiway indicator lights shall be located on the runway on the same side of the runway center line as the associated rapid exit taxiway, in the configuration shown in Figure 13.1.5-25. In each set, the lights shall be located 2 m apart and the light nearest to the runway center line shall be displaced 2 m from the runway centerline.
- (ii) Where more than one rapid exit taxiway exists on a runway, the set of rapid exit taxiway indicator lights for each exit shall not overlap when displayed.




Figure 13.1.5-25: Rapid exit taxiway indicator lights (RETILs)

(3) **Characteristics**

- (i) Rapid exit taxiway indicator lights shall be fixed unidirectional yellow lights, aligned so as to be visible to the pilot of a landing aeroplane in the direction of approach to the runway.
- (ii) Rapid exit taxiway indicator lights shall be in accordance with the specifications in Appendix 2, Figure A2-6 or Figure A2-7, as appropriate.
- (iii) Rapid exit taxiway indicator lights shall be supplied with power on a separate circuit to other runway lighting so that they may be used when other lighting is switched off.

(p) **Stopway Lights**

- (1) **Application.** Stopway lights shall be provided for a stopway intended for use at night.
- (2) **Location.** Stopway lights shall be placed along the full length of the stopway and shall be in two parallel rows that are equidistant from the center line and coincident with the rows of the runway edge lights. Stopway lights shall also be provided across the end of a stopway on a line at right angles to the stopway axis as near to the end of the stopway as possible and, in any case, not more than 3 m outside the end.
- (3) **Characteristics.** Stopway lights shall be fixed unidirectional lights showing red in the direction of the runway.

(q) Taxiway Center Line Lights

(1) Application

- (i) Taxiway center line lights shall be provided on an exit taxiway, taxiway, and apron intended for use in runway visual range conditions less than a value of 350m in such a manner as to provide continuous guidance between the runway center line and aircraft stands, except that these lights need not be provided where the traffic density is light and taxiway edge lights and centerline marking provide adequate guidance.
- (ii) Taxiway center line lights shall be provided on a taxiway intended for use at night in runway visual range conditions of 350 m or greater, and particularly on complex taxiway intersections and exit taxiways, except that these lights need not be provided where the traffic density is light and taxiway edge lights and center line marking provide adequate guidance.

Note.— Where there may be a need to delineate the edges of a taxiway, e.g. on a rapid exit taxiway, narrow taxiway or in snow conditions, this may be done with taxiway edge lights or markers.

- (iii) Taxiway center line lights shall be provided on an exit taxiway, taxiway, and apron in all visibility conditions where specified as components of an advanced surface movement guidance and control system in such a manner as to provide continuous guidance between the runway center line and aircraft stands.
- (iv) Taxiway center line lights shall be provided on a runway forming part of a standard taxi-route and intended for taxiing in runway visual range conditions less than a value of 350 m, except that these lights need not be provided where the traffic density is light and taxiway edge lights and centerline marking provide adequate guidance.

Note. — See 13.1.8.2(c) for provisions concerning the interlocking of runway and taxiway lighting systems.

- (v) Taxiway center line lights shall be provided in all visibility conditions on a runway forming part of a standard taxi-route where specified as components of an advanced surface movement guidance and control system.

(2) Characteristics

- (i) Except as provided for in (iii) below, taxiway center line lights on a taxiway other than an exit taxiway and on a runway forming part of a standard taxi-route shall be fixed lights showing green with beam dimensions such that the

light is visible only from aeroplanes on or in the vicinity of the taxiway.

- (ii) Taxiway center line lights on an exit taxiway shall be fixed lights. Alternate taxiway center line lights shall show green and yellow from their beginning near the runway center line to the perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway; and thereafter all lights shall show green (Figure 13.1.5-26). The first light in the exit center line shall always show green, and the light nearest to the perimeter shall always show yellow.

Note 1. — Care is necessary to limit the light distribution of green lights on or near a runway so as to avoid possible confusion with threshold lights.

Note 2. — For yellow filter characteristics see ICAO Annex 14, Vol. I, Appendix 1, 2.2.

Note 3. — The size of the ILS/MLS critical/sensitive area depends on the characteristics of the associated ILS/MLS and other factors. Guidance is provided in Annex 10, Volume I, Attachments C and G.

Note 4. — See 13.1.5.4(c) for specifications on runway vacated signs.

- (iii) Where it is necessary to denote the proximity to a runway, taxiway center line lights shall be fixed lights showing alternating green and yellow from the perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway, to the runway and continue alternating green and yellow until:

- (A) their end point near the runway center line; or
- (B) in the case of the taxiway center line lights crossing the runway, to the opposite perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farthest from the runway.

Note 1. — Care is necessary to limit the light distribution of green lights on or near a runway so as to avoid possible confusion with threshold lights.

Note 2. — The provisions of 13.1.5.3(r)(2)(iii) (c) can form part of effective runway incursion prevention measures.




Figure 13.1.5-26. Taxiway lighting

- (iv) Taxiway center line lights shall be in accordance with the specifications of:
 - (A) ICAO Annex 14, Vol. I, Appendix 2, Figure A2-12, A2-13, or A2-14, for taxiways intended for use in runway visual range conditions of less than a value of 350 m; and
 - (B) ICAO Annex 14, Vol. I, Appendix 2, Figure A2-15 or A2-16, for other taxiways.
- (v) Where higher intensities are required, from an operational point of view, taxiway center line lights on rapid exit taxiways intended for use in runway

visual range conditions less than a value of 350 m shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, Figure A2-12. The number of levels of brilliancy settings for these lights shall be the same as that for the runway center line lights.

- (vi) Where taxiway center line lights are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, taxiway center line lights shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, Figure A2-17, A2-18 or A2-19.

Note. — *High-intensity center line lights should only be used in case of an absolute necessity and following a specific study.*

- (3) **Location.** Taxiway center line lights shall normally be located on the taxiway center line marking, except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.

(4) **Taxiway center line lights on taxiways**

(i) **Location**

- (A) Taxiway center line lights on a straight section of a taxiway shall be spaced at longitudinal intervals of not more than 30 m, except that:

1. larger intervals not exceeding 60 m may be used where, because of the prevailing meteorological conditions, adequate guidance is provided by such spacing;
2. intervals less than 30 m should be provided on short straight sections; and
3. on a taxiway intended for use in RVR conditions of less than a value of 350 m, the longitudinal spacing should not exceed 15m.

- (B) Taxiway center line lights on a taxiway curve shall continue from the straight portion of the taxiway at a constant distance from the

outside edge of the taxiway curve. The lights shall be spaced at intervals such that a clear indication of the curve is provided.

- (C) On a taxiway intended for use in RVR conditions of less than a value of 350 m, the lights on a curve shall not exceed a spacing of 15 m, and on a curve of less than 400 m radius the lights shall be spaced at intervals of not greater than 7.5 m. This spacing should extend for 60 m before and after the curve.

Note 1. — *Spacings on curves that have been found suitable for a taxiway intended for use in RVR conditions of 350 m or greater are:*

Curve radius	Light spacing
up to 400 m	7.5m

401 m to 899 m	15m
900 m or greater	30 m.

Note 2 — See section 3.9.6 and ICAO Annex 14, Vol. I, Figure 3-2.

(5) **Taxiway Center Line Lights on Rapid Exit Taxiways**

(i) **Location**

- (A) Taxiway center line lights on a rapid exit taxiway shall commence at a point at least 60 m before the beginning of the taxiway center line curve and continue beyond the end of the curve to a point on the center line of the taxiway where an aeroplane can be expected to reach normal taxiing speed. The lights on that portion parallel to the runway center line shall always be at least 60 cm from any row of runway center line lights, as shown in ICAO Annex 14, Vol. I, Figure 13.1.5-26.
- (B) The lights shall be spaced at longitudinal intervals of not more than 15 m, except that, where runway center line lights are not provided, a greater interval not exceeding 30 m may be used.

(6) **Taxiway center line lights on other exit taxiways**

(i) **Location**

- (A) Taxiway center line lights on exit taxiways other than rapid exit taxiways shall commence at the point where the taxiway center line marking begins to curve from the runway center line, and follow the curved taxiway center line marking at least to the point where the marking leaves the runway. The first light shall be at least 60 cm from any row of runway center line lights, as shown in ICAO Annex 14, Vol. I, Figure 13.1.5-27.
- (B) The lights shall be spaced at longitudinal intervals of not more than 7.5 m.

(7) **Taxiway Center Line Lights on Runways**

- (i) **Location.** Taxiway center line lights on a runway forming part of a standard taxi-route and intended for taxiing in runway visual range conditions less than a value of 350m shall be spaced at longitudinal intervals not exceeding 15 m.




Figure 13.1.5-27. Offset runway and taxiway center line lights

(r) Taxiway Edge Lights

(1) Application

- (i) Taxiway edge lights shall be provided at the edges of a runway turn pad, holding bay, apron, etc., intended for use at night and on a taxiway not provided with taxiway center line lights and intended for use at night, except that taxiway edge lights need not be provided where, considering the nature of the operations, adequate guidance can be achieved by surface illumination or other means.

Note.— See 13.1.5.5(d) for taxiway edge markers.

- (ii) Taxiway edge lights shall be provided on a runway forming part of a standard taxi- route and intended for taxiing at night where the runway is not provided with taxiway centerline lights.

Note. — See 13.1.8.2(c) for provisions concerning the interlocking of runway and taxiway lighting systems.

(2) Location

- (i) Taxiway edge lights on a straight section of a taxiway and on a runway forming part of a standard taxi-route shall be spaced at uniform longitudinal intervals of not more than 60 m. The lights on a curve shall be spaced at intervals less than 60 m so that a clear indication of the curve is provided.

Note. — Guidance on the spacing of taxiway edge lights on curves is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (ii) Taxiway edge lights on a holding bay, apron, etc., should be spaced at uniform longitudinal intervals of not more than 60 m.

- (iii) Taxiway edge lights on a runway turn pad shall be spaced at uniform longitudinal intervals of not more than 30m.
- (iv) The lights shall be located as near as practicable to the edges of the taxiway, runway turn pad, holding bay, apron or runway, etc., or outside the edges at a distance of not more than 3m.

(3) **Characteristics**

- (i) Taxiway edge lights shall be fixed lights showing blue. The lights shall show up to at least 75° above the horizontal and at all angles in azimuth necessary to provide guidance to a pilot taxiing in either direction. At an intersection, exit or curve the lights shall be shielded as far as practicable so that they cannot be seen in angles of azimuth in which they may be confused with other lights.
- (ii) The intensity of taxiway edge lights shall be at least 2 cd from 0° to 6° vertical, and 0.2 cd at any vertical angles between 6° and 75°.

(s) **Runway Turn Pad Lights**

(1) **Application**

- (i) Runway turn pad lights shall be provided for continuous guidance on a runway turn pad intended for use in runway visual range conditions less than a value of 350 m, to enable an aeroplane to complete a 180-degree turn and align with the runway center line.
- (ii) Runway turn pad lights shall be provided on a runway turn pad intended for use at night.

(2) **Location**

- (i) Runway turn pad lights shall normally be located on the runway turn pad marking, except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.
- (ii) Runway turn pad lights on a straight section of the runway turn pad marking shall be spaced at longitudinal intervals of not more than 15m.
- (iii) Runway turn pad lights on a curved section of the runway turn pad marking shall not exceed a spacing of 7.5m.

(3) **Characteristics**

- (i) Runway turn pad lights shall be unidirectional fixed lights showing green with beam dimensions such that the light is visible only from aeroplanes on or approaching the runway turn pad.
- (ii) Runway turn pad lights shall be in accordance with the specifications of Annex 14 volume 1, Appendix 2, Figure A2-13, A2-14 or A2-15, as appropriate.

(t) **Stop Bars**

(1) **Application**

- (i) A stop bar shall be provided at every runway-holding position serving a runway when it is intended that the runway will be used in runway visual range

conditions less than a value of 350 m, except where:

- (A) appropriate aids and procedures are available to assist in preventing inadvertent incursions of traffic onto the runway; or
- (B) operational procedures exist to limit, in runway visual range conditions less than a value of 550 m, the number of:
 - 1. aircraft on the maneuvering area to one at a time; and
 - 2. vehicles on the maneuvering area to the essential minimum.

Note 1. — A stop bar is intended to be controlled either manually or automatically by air traffic services.

Note 2. — Runway incursions may take place in all visibility or weather conditions. The provision of stop bars at runway holding positions and their use at night and in visibility conditions greater than 550 m runway visual range can form part of effective runway incursion prevention measures.

- (ii) Where there is more than one stop bar associated with a taxiway or runway intersection, only one shall be illuminated at any given time.
 - (iii) A stop bar shall be provided at an intermediate holding position when it is desired to supplement markings with lights and to provide traffic control by visual means.
- (2) **Location.** Stop bars shall be located across the taxiway at the point where it is desired that traffic stop. Where the additional lights specified in (ii) above are provided, these lights shall be located not less than 3 m from the taxiway edge.
- (3) **Characteristics**
- (i) Stop bars shall consist of lights spaced at uniform intervals of no more than 3 m across the taxiway, showing red in the intended direction(s) of approach to the intersection or runway-holding position.

Note. — Where necessary to enhance conspicuity of an existing stop bar, extra lights are installed uniformly.

- (ii) A pair of elevated lights shall be added to each end of the stop bar where the in pavement stop bar lights might be obscured from a pilot's view, for example, by snow or rain, or where a pilot may be required to stop the aircraft in a position so close to the lights that they are blocked from view by the structure of the aircraft.
- (iii) Stop bars installed at a runway-holding position shall be unidirectional and shall show red in the direction of approach to the runway.
- (iv) Where the additional lights specified in 13.1.5.3(t)(3)(ii) are provided, these lights shall have the same characteristics as the lights in the stop bar, but shall be visible to approaching aircraft up to the stop bar position.
- (v) The intensity in red light and beam spreads of stop bar lights shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figures A2-12 through A2-16, as appropriate.

- (vi) Where stop bars are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, the intensity in red light and beam spreads of stop bar lights

shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, Figure A2-17, A2-18 or A2-19.

Note. — *High-intensity stop bars should only be used in case of an absolute necessity and following a specific study.*

- (vii) Where a wide beam fixture is required, the intensity in red light and beam spreads of stop bar lights shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, Figure A2-17 or A2-19.

- (viii) The lighting circuit shall be designed so that:

- (A) stop bars located across entrance taxiways are selectively switchable;
- (B) stop bars located across taxiways intended to be used only as exit taxiways are switchable selectively or in groups;
- (C) when a stop bar is illuminated, any taxiway center line lights installed beyond the stop bar shall be extinguished for a distance of at least 90 m; and
- (D) stop bars are interlocked with the taxiway center line lights so that when the center line lights beyond the stop bar are illuminated the stop bar is extinguished and vice versa.

Note 2 — *Care is required in the design of the electrical system to ensure that all of the lights of a stop bar will not fail at the same time. Guidance on this issue is given in the ICAO Aerodrome Design Manual (Doc 9157), Part 5.*

(u) Intermediate Holding Position Lights

(1) Application

- (i) Except where a stop bar has been installed, intermediate holding position lights shall be provided at an intermediate holding position intended for use in runway visual range conditions less than a value of 350m.

Note. — *See 13.1.5.2(k) for specifications on intermediate holding position marking.*

- (ii) Intermediate holding position lights shall be provided at an intermediate holding position where there is no need for stop-and-go signals as provided by a stopbar.

- (2) **Location.** Intermediate holding position lights shall be located along the intermediate holding position marking at a distance of 0.3 m prior to the marking.

- (3) **Characteristics.** Intermediate holding position lights shall consist of three fixed unidirectional lights showing yellow in the direction of approach to the intermediate holding position with a light distribution similar to taxiway center line lights if provided. The lights shall be disposed symmetrically about and at
- (4) right angle to the taxiway center line, with individual lights spaced 1.5 m apart.

(v) **Runway Guard Lights**

(1) **Application**

- (i) Runway guard lights, Configuration A, shall be provided at each taxiway or runway intersection associated with a runway intended for use in:
 - (A) runway visual range conditions less than a value of 550 m where a stop bar is not installed; and
 - (B) runway visual range conditions of values between 550 m and 1 200 m where the traffic density is heavy.

Note 1.— Runway guard lights, Configuration B may supplement Configuration A when deemed necessary

Note 2.— Guidance on the design, operation and the location of runway guard lights Configuration B is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (ii) As part of runway incursion prevention measures, runway guard lights, Configuration A or B, shall be provided at each taxiway/runway intersection where runway incursion hot spots have been identified, and used under all weather conditions during day and night.
- (iii) Configuration B runway guard lights shall not be collocated with a stopbar.
- (iv) Where more than one runway-holding positions exist at a runway/taxiway intersection, only the set of runway guard lights associated with the operational runway-holding position shall be illuminated.

(2) **Location**

- (v) Runway guard lights, Configuration A, shall be located at each side of the taxiway on the holding-side of the runway holding position marking
- (vi) Runway guard lights, Configuration B, shall be located across the taxiway on the holding-side of the runway holding position marking .




Figure 13.1.5-29. Runway guard lights

(3) **Characteristics**

- (i) Runway guard lights, Configuration A, shall consist of two pairs of yellow lights.
- (ii) Where there is a need to enhance the contrast between the on and off state of runway guard lights, Configuration A, intended for use during the day, a visor of sufficient size to prevent sunlight from entering the lens without interfering with the function of the fixture shall be located above each lamp.

Note. — Some other device or design, e.g. specially designed optics, may be used in lieu of the visor.

- (iii) Runway guard lights, Configuration B, shall consist of yellow lights spaced at intervals of 3 m across the taxiway.
- (iv) The light beam shall be unidirectional and aligned so as to be visible to the pilot of an aeroplane taxiing to the holding position.

Note. — For guidance on orientation and aiming of runway guard lights, see the *Aerodrome Design Manual (Doc 9157) Part 4*

- (v) The intensity in yellow light and beam spreads of lights of Configuration A shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-24.
- (vi) Where runway guard lights are intended for use during the day, the intensity

in yellow light and beam spreads of lights of Configuration A shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-25.

- (vii) Where runway guard lights are specified as components of an advanced surface movement guidance and control system where higher light

intensities are required, the intensity in yellow light and beam spreads of lights of Configuration A shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-25

Note. — Higher light intensities may be required to maintain ground movement at a certain speed in low visibilities.

- (viii) The intensity in yellow light and beam spreads of lights of Configuration B shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-12.
- (ix) Where runway guard lights are intended for use during the day, the intensity in yellow light and beam spreads of lights of Configuration B shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-20.
- (x) Where runway guard lights are specified as components of an advanced surface movement guidance and control system where higher light intensities are required, the intensity in yellow light and beam spreads of lights of Configuration B shall be in accordance with the specifications in ICAO Annex 14, Vol. I, Appendix 2, Figure A2-20.
- (xi) The lights in each unit of Configuration A shall be illuminated alternately.
- (xii) For Configuration B, adjacent lights shall be alternately illuminated and alternative lights shall be illuminated in unison.
- (xiii) The lights shall be illuminated between 30 and 60 cycles per minute and the light suppression and illumination periods shall be equal and opposite in each light.

Note. — The optimum flash rate is dependent on the rise and fall times of the lamps used. Runway guard lights, Configuration A, installed on 6.6 ampere series circuits have been found to look best when operated at 45 to 50 flashes per minute per lamp. Runway guard lights, Configuration B, installed on 6.6 ampere series circuits have been found to look best when operated at 30 to 32 flashes per minute per lamp.

(w) Apron Floodlighting

(See also sections 13.1.5.3(r)(1)(i) and 13.1.5.3(s)(1)(i))

- (1) **Application.** Apron floodlighting shall be provided on an apron, and on a designated isolated aircraft parking position intended to be used at night.

Note 1. — The designation of an isolated aircraft parking position is specified in 13.1.3.14.

Note 2. — Guidance on apron floodlighting is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (2) **Location.** The Aerodrome Operator shall ensure that Apron floodlights shall be located so as to provide adequate illumination on all apron service areas, with a minimum of glare to pilots of aircraft in flight and on the ground, aerodrome and apron controllers, and personnel on the apron. The arrangement and aiming of floodlights shall be such that an aircraft stand receives light from two or more directions to minimize shadows.
- (3) **Characteristics**
- (i) The spectral distribution of apron floodlights shall be such that the colors used for aircraft marking connected with routine servicing, and for surface and obstacle marking, can be correctly identified.
- (ii) The average illuminance shall be at least the following:
- (A) **Aircraft stand:**
- horizontal illuminance — 20 lux with a uniformity ratio (average to minimum) of not more than 4 to 1; and
 - vertical illuminance — 20 lux at a height of 2 m above the apron in relevant directions.
- (B) **Other apron areas:**
- horizontal illuminance — 50 per cent of the average illuminance on the aircraft stands with a uniformity ratio (average to minimum) of not more than 4 to 1.

(x) **Visual Docking Guidance System**

- (1) **Application.** A visual docking guidance system shall be provided when it is intended to indicate, by a visual aid, the precise positioning of an aircraft on an aircraft stand and other alternative means, such as marshallers, are not practicable.

Note. — The factors to be considered in evaluating the need for a visual docking guidance system are in particular: the number and type(s) of aircraft using the aircraft stand, weather conditions, space available on the apron and the precision required for maneuvering into the parking position due to aircraft servicing installation, passenger loading bridges, etc. See the Aerodrome Design Manual (Doc9157), Part 4 — Visual Aids for guidance on the selection of suitable systems.

- (2) **Characteristics**
- (i) The Visual Docking Guidance system shall provide both azimuth and stopping guidance.
- (ii) The azimuth guidance unit and the stopping position indicator shall be adequate for use in all weather, visibility, background lighting and pavement conditions for which the system is intended, both by day and night, but shall not dazzle the pilot.

Note. — Care is required in both the design and on-site installation of the system to ensure that reflection of sunlight, or other light in the vicinity, does not degrade the clarity and conspicuity of the visual cues provided by the system.

- (iii) The azimuth guidance unit and the stopping position indicator shall be of a design such that:
 - (A) a clear indication of malfunction of either or both is available to the pilot; and
 - (B) they can be turned off.
 - (iv) The azimuth guidance unit and the stopping position indicator shall be located in such a way that there is continuity of guidance between the aircraft stand markings, the aircraft stand maneuvering guidance lights, if present, and the visual docking guidance system.
 - (v) The accuracy of the system shall be adequate for the type of loading bridge and fixed aircraft servicing installations with which it is to be used.
 - (vi) The system shall be usable by all types of aircraft for which the aircraft stand is intended, preferably without selective operation.
 - (vii) If selective operation is required to prepare the system for use by a particular type of aircraft, then the system shall provide an identification of the selected aircraft type to both the pilot and the system operator as a means of ensuring that the system has been set properly.
- (3) ***Azimuth guidance unit***
- (i) ***Location***
 - (A) The azimuth guidance unit shall be located on or close to the extension of the stand center line ahead of the aircraft so that its signals are visible from the cockpit of an aircraft throughout the docking maneuver and aligned for use at least by the pilot occupying the left seat.
 - (B) The azimuth guidance unit shall be aligned for use by the pilots occupying both the left and right seats.
 - (ii) ***Characteristics***
 - (A) The azimuth guidance unit shall provide unambiguous left or right guidance which enables the pilot to acquire and maintain the lead-in line without over-controlling.
 - (B) When azimuth guidance is indicated by color change, green shall be used to identify the center line and red for deviations from the centerline.
- (4) ***Stopping position indicator***
- (i) ***Location***

- (A) The stopping position indicator shall be located in conjunction with, or sufficiently close to, the azimuth guidance unit so that a pilot can observe both the azimuth and stop signals without turning the head.
- (B) The stopping position indicator shall be usable at least by the pilot occupying the left seat.
- (C) The stopping position indicator shall be usable by the pilots occupying both the left and right seats.

(ii) **Characteristics**

- (A) The stopping position information provided by the indicator for a particular aircraft type shall account for the anticipated range of variations in pilot eye height and/or viewing angle.
- (B) The stopping position indicator shall show the stopping position for the aircraft for which guidance is being provided and shall provide closing rate information to enable the pilot to gradually decelerate the aircraft to a full stop at the intended stopping position.
- (C) The stopping position indicator shall provide closing rate information over a distance of at least 10m.
- (D) When stopping guidance is indicated by color change, green shall be used to show that the aircraft can proceed and red to show that the stop point has been reached, except that for a short distance prior to the stop point a third color may be used to warn that the stopping point is close.

(y) **Advanced Visual Docking Guidance System**

(1) **Application**

- (i) An A-VDGS shall be provided where it is operationally desirable to confirm the correct aircraft type for which guidance is being provided and/or to indicate the stand center line in use, where more than one is provided for.

Note. — An A-VDGS may provide docking guidance information in three stages: the acquisition of the aircraft by the system, the azimuth alignment of the aircraft, and the stopping position information.

- (ii) The A-VDGS shall be suitable for use by all types of aircraft for which the aircraft stand is intended.
- (iii) The A-VDGS shall be used only in conditions in which its operational
- (iv) performance is specified.

Note 1. — The use of the A-VDGS in conditions such as weather, visibility and background lighting, both by day and night, would need to be specified.

Note 2. — Care is required in both the design and on-site installation of the system to ensure that glare, reflection of sunlight, or other light in the vicinity, does not degrade the clarity and conspicuity of the visual cues provided by the system.

- (v) The docking guidance information provided by an A-VDGS shall not conflict with that provided by a conventional visual docking guidance system on an aircraft stand if both types are provided and are in operational use. A method of indicating that the A- VDGS is not in operational use or is unserviceable shall be provided.
- (2) **Location.** The A-VDGS shall be located such that unobstructed and unambiguous guidance is provided to the person responsible for, and persons assisting, the docking of the aircraft throughout the docking maneuver.

Note. — Usually the pilot-in-command is responsible for the docking of the aircraft. However, in some circumstances, another person could be responsible and this person may be the driver of a vehicle that is towing the aircraft.

(3) **Characteristics**

- (i) The A-VDGS shall provide, at minimum, the following guidance information at the appropriate stage of the docking manoeuvre:
 - (A) an emergency stop indication;
 - (B) the aircraft type and model for which the guidance is provided;
 - (C) an indication of the lateral displacement of the aircraft relative to the stand center line;
 - (D) the direction of azimuth correction needed to correct a displacement from the stand center line;
 - (E) an indication of the distance to the stop position;
 - (F) an indication when the aircraft has reached the correct stopping position; and
 - (G) a warning indication if the aircraft goes beyond the appropriate stop position.
- (ii) The A-VDGS shall be capable of providing docking guidance information for all aircraft taxi speeds encountered during the docking manoeuvre.

Note. — See the Aerodrome Design Manual (Doc 9157), Part 4, for an indication of the maximum aircraft speeds relative to distance to the stopping position.

- (iii) The time taken from the determination of the lateral displacement to its display shall not result in a deviation of the aircraft, when operated in normal conditions, from the stand center line greater than 1 m.
- (iv) The information on displacement of the aircraft relative to the stand center line and distance to the stopping position, when displayed, shall be provided with the accuracy specified in Table 13.1.5-4.

- (v) Symbols and graphics used to depict guidance information shall be intuitively representative of the type of information provided.

Note. — The use of color would need to be appropriate and need to follow signal convention, i.e. red, yellow and green mean hazard, caution and normal/correct conditions, respectively. The effects of color contrasts would also need to be considered.

- (vi) Information on the lateral displacement of the aircraft relative to the stand center line shall be provided at least 25 m prior to the stop position.

Note. — The indication of the distance of the aircraft from the stop position may be color-coded and presented at a rate and distance proportional to the actual closure rate and distance of the aircraft approaching the stop point.

- (vii) Continuous closure distance and closure rate shall be provided from at least 15 m prior to the stop position.

- (viii) Where provided, closure distance displayed in numerals shall be provided in meter integers to the stop position and displayed to 1 decimal place at least 3 m prior to the stop position.

Table 13.1.5-4. A-VDGS recommended displacement accuracy

Guidance information	Maximum deviation at stop position (stop area)	Maximum deviation at 9 m from stop position	Maximum deviation at 15 m from stop position	Maximum deviation at 25 m from stop position
Azimuth	±250 mm	±340 mm	±400 mm	±500 mm
Distance	±500 mm	±1 000 mm	±1 300 mm	Not specified

- (ix) Throughout the docking maneuver, an appropriate means shall be provided on the A-VDGS to indicate the need to bring the aircraft to an immediate halt. In such an event, which includes a failure of the A-VDGS, no other information shall be displayed.

- (x) Provision to initiate an immediate halt to the docking procedure shall be made available to personnel responsible for the operational safety of the stand.

- (xi) The word “stop” in red characters shall be displayed when an immediate cessation of the docking maneuver is required.

(z) Aircraft Stand Manoeuvring Guidance Lights

- (1) **Application.** Aircraft stand maneuvering guidance lights shall be provided to facilitate the positioning of an aircraft on an aircraft stand on a paved apron intended for use in poor visibility conditions, unless adequate guidance is provided by other means.
- (2) **Location.** Aircraft stand maneuvering guidance lights shall be collocated with the aircraft stand markings.
- (3) **Characteristics**

- (i) Aircraft stand maneuvering guidance lights, other than those indicating a stop position, shall be fixed yellow lights, visible throughout the segments within which they are intended to provide guidance.
- (ii) The lights used to delineate lead-in, turning and lead-out lines shall be spaced at intervals of not more than 7.5 m on curves and 15 m on straight sections.
- (iii) The lights indicating a stop position shall be fixed unidirectional lights showing red.
- (iv) The intensity of the lights shall be adequate for the condition of visibility and ambient light in which the use of the aircraft stand is intended.
- (v) The lighting circuit shall be designed so that the lights may be switched on to indicate that an aircraft stand is to be used and switched off to indicate that it is not to be used.

(aa) Road-Holding Position Light

(1) Application

- (i) A road-holding position light shall be provided at each road-holding position serving a runway when it is intended that the runway will be used in runway visual range conditions less than a value of 350 m.
- (ii) A road-holding position light shall be provided at each road-holding position serving a runway when it is intended that the runway will be used in runway visual range conditions of values between 350 m and 550m.

- (2) **Location.** A road-holding position light shall be located adjacent to the holding position marking 1.5 m (± 0.5 m) from one edge of the road, i.e. left or right as appropriate to the local traffic Regulations.

Note. — See 13.1.9.9 for the mass and height limitations and frangibility requirements of navigation aids located on runway strips.

(3) Characteristics

- (i) The road-holding position light shall comprise:
 - (A) a controllable red (stop)/green (go) traffic light; or
 - (B) a flashing-redlight.

Note. — It is intended that the lights specified in sub-paragraph a) be controlled by the air traffic services.

- (ii) The road-holding position light beam shall be unidirectional and aligned so as to be visible to the driver of a vehicle approaching the holding position.
- (iii) The intensity of the light beam shall be adequate for the conditions of visibility and ambient light in which the use of the holding position is intended, but shall not dazzle the driver.

Note. — The commonly used traffic lights are likely to meet the requirements in (ii) and (iii) above.

- (iv) The flash frequency of the flashing-red light shall be between 30 and 60 flashes per minute.

(bb) No-Entry Bar

Note 2.— Runway incursions may take place in all visibility or weather conditions. The use of no-entry bars can form part of effective runway incursion prevention measure.

- (1) **Application.** A no-entry bar shall be provided across a taxiway which is intended to be used as an exit only taxiway to assist in preventing inadvertent access of traffic to that taxiway.
- (2) **Location.** A no-entry bar shall be located across the taxiway at the end of an exit only taxiway where it is desired to prevent traffic from entering the taxiway in the wrong direction. A no-entry bar shall be co-located with a no-entry sign and/or a no-entry marking.
- (3) **Characteristics**
 - (i) A no-entry bar shall consist of unidirectional lights spaced at uniform intervals of more than 3m showing red in the intended direction(s) of approach to the runway.

Note. — Where necessary to enhance conspicuity, extra lights are installed uniformly.

- (ii) A pair of elevated lights shall be added to each end of the no-entry bar where the in- pavement no entry bar lights might be obscured from a
 - (iii) pilot's view, for example, by snow or rain, or where a pilot may be required to stop the aircraft in a position so close to the lights that they are blocked from view by the structure of the aircraft.
- (iv) The intensity in red light and beam spreads of no-entry bar lights shall be in accordance with the specifications in Appendix 2, Figures A2-12 through A2-16, as appropriate.
- (v) Where no-entry bars are specified as components of an advanced surface movement guidance and control system and where, from an operational point of view, higher intensities are required to maintain ground movements at a certain speed in very low visibilities or in bright daytime conditions, the intensity in red light and beam spreads of no-entry bar lights shall be in accordance with the specifications of Appendix 2, Figure A2-17, A2-18 or A2-19.

Note. — High-intensity no-entry bars are typically used only in case of an absolute necessity and following a specific study.

- (vi) Where a wide beam fixture is required, the intensity in red light and beam spreads of no-entry bar lights shall be in accordance with the specifications of Appendix 2, Figure A2-17 or A2-19.

- (vii) Taxiway centre line lights installed beyond the no-entry bar, looking in the direction of the runway, shall not be visible when viewed from the taxiway

(cc) Runway Status Lights

(1) Location

- (i) Where provided, RELs shall be offset 0.6 m from the taxiway center line on the opposite side to the taxiway center line lights and begin 0.6 m before the runway- holding position extending to the edge of the runway. An additional single light shall be placed on the runway 0.6 m from the runway center line and aligned with the last two taxiway RELs.

Note. — Where two or more runway-holding positions are provided, the runway-holding position referred is that closest to the runway.

- (ii) RELs shall consist of at least five light units and shall be spaced at a minimum of 3.8 m and a maximum of 15.2 m longitudinally, depending upon the taxiway length involved, except for a single light installed near the runway centerline.

- (iii) Where provided, THLs shall be offset 1.8 m on each side of the runway center line lights and extend, in pairs, starting at a point 115 m from the beginning of the runway and, thereafter, every 30 m for at least 450m.

Note. — Additional THLs may be similarly provided at the starting point of the take-off roll.

(2) Characteristics

- (i) Where provided, RELs shall consist of a single line of fixed in pavement lights showing red in the direction of aircraft approaching the runway.
- (ii) RELs shall illuminate as an array at each taxiway/runway intersection where they are installed less than two seconds after the system determines a warning is needed.
- (iii) Intensity and beam spread of RELs shall be in accordance with the specifications of Appendix 2, Figures A2-12 and A2-14.

Note. — Consideration for reduced beam width may be required for some REL lights at acute angled runway/taxiway intersections to ensure the RELs are not visible to aircraft on the runway.

- (iv) Where provided, THLs shall consist of two rows of fixed in pavement lights showing red facing the aircraft taking off.
- (v) THLs shall illuminate as an array on the runway less than two seconds after the system determines a warning is needed.
- (vi) Intensity and beam spread of THLs shall be in accordance with the specifications of ICAO Annex 14, Vol. I, Appendix 2, FigureA2-26.
- (vii) RELs and THLs shall be automated to the extent that the only control over each system will be to disable one or both systems.

13.1.5.4 Signs

(a) General

- (1) The Aerodrome Operator shall ensure that signs shall be either fixed message signs or variable message signs.

Note. — Guidance on signs is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

(2) Application

- (i) Signs shall be provided to convey a mandatory instruction, information on a specific location or destination on a movement area or to provide other information to meet the requirements of 13.1.9.8(a).

Note.— See 13.1.5.2(q) for specifications on information marking.

- (ii) A variable message sign shall be provided where:

- (A) the instruction or information displayed on the sign is relevant only during a certain period of time; and/or
- (B) there is a need for variable predetermined information to be displayed on the sign to meet the requirements of 13.1.9.8(a).

(3) Characteristics

- (i) Signs shall be frangible. Those located near a runway or taxiway shall be sufficiently low to preserve clearance for propellers and the engine pods of jet aircraft. The installed height of the sign shall not exceed the dimension shown in the appropriate column of Table 13.15-5.
- (ii) Signs shall be rectangular, as shown in ICAO Annex 14, Vol. I Figures 13.1.5-30 and 13.1.5-31 with the longer side horizontal.
- (iii) The only signs on the movement area utilizing red shall be mandatory instruction signs.
- (iv) The inscriptions on a sign shall be in accordance with the provisions of ICAO Annex 14, Vol. I, Appendix 4.

Table 13.1.5-5. Location distances for taxiing guidance signs including runway exit signs

Code number	Legend	Sign height (mm)		Installed (max.)	Perpendicular distance from defined taxiway pavement edge to near side of sign	Perpendicular distance from defined runway pavement edge to near side of sign
		Face (min.)				
1 or 2	200	300		700	5–11 m	3–10 m
1 or 2	300	450		900	5–11 m	3–10 m
3 or 4	300	450		900	11–21 m	8–15 m
3 or 4	400	600		1 100	11–21 m	8–15 m


Runway designation of a runway extremity (Example)	25	Indicates a runway-holding position at a runway extremity
Runway designation of both extremities of a runway (Example)	25-07	Indicates a runway-holding position located at taxiway/runway intersection other than runway extremity
Category I hold position (Example)	25 CAT I	Indicates a category I runway-holding position at the threshold of runway 25
Category II hold position (Example)	25 CAT II	Indicates a category II runway-holding position at the threshold of runway 25
Category III hold position (Example)	25 CAT III	Indicates a category III runway-holding position at the threshold of runway 25
Category II and III hold position (Example)	25 CAT II/III	Indicates a joint category II and III runway-holding position at the threshold of runway 25
Category I, II and III hold position (Example)	25 CAT I/II/III	Indicates a joint category I, II and III runway-holding position at the threshold of runway 25
NO ENTRY		Indicates that entry to an area is prohibited
Runway-holding position (Example)	B2	Indicates a runway-holding position (in accordance with 3.12.3)

Figure 13.1.5-30. Mandatory instruction signs




Figure 13.1.5-31. Information signs

- (v) Signs shall be illuminated in accordance with the provisions of ICAO Annex 14, Vol. I, Appendix 4 when intended for use:
- (A) in runway visual range conditions less than a value of 800 m; or
 - (B) at night in association with instrument runways; or
 - (C) at night in association with non-instrument runways where the code number is 3 or 4.

- (vi) Signs shall be retroreflective and/or illuminated in accordance with the provisions of ICAO Annex 14, Vol. I, Appendix 4 when intended for use at night in association with non-instrument runways where the code number is 1 or 2.
- (vii) A variable message sign shall show a blank face when not in use.
- (viii) In case of failure, a variable message sign shall not provide information that could lead to unsafe action from a pilot or a vehicle driver.
- (ix) The time interval to change from one message to another on a variable message sign should be as short as practicable and should not exceed 5 seconds.

(b) Mandatory instruction signs

(1) Application

- (i) A mandatory instruction sign shall be provided by the Aerodrome Operator to identify a location beyond which an aircraft taxiing or vehicle shall not proceed unless authorized by the aerodrome control tower.

Note. — See Figure 13.1.5-30 for pictorial representation of mandatory instruction signs and Figure 13.1.5-32 for examples of locating signs at taxiway/runway intersections.

- (ii) Mandatory instruction signs shall include runway designation signs, category I, II or III holding position signs, runway-holding position signs, road-holding position signs and NO ENTRY signs.

Note. — See 13.1.5.3(b)(1)(vii) for specifications on road-holding position signs.

- (iii) A pattern “A” runway-holding position marking shall be supplemented at a taxiway/runway intersection or a runway/runway intersection with a runway designation sign.
- (iv) A pattern “B” runway-holding position marking shall be supplemented with a category I, II or III holding position sign.
- (v) A pattern “A” runway-holding position marking at a runway-holding position established in accordance with 13.1.3.12(a)(3) shall be supplemented with a runway-holding position sign.

Note. — See 13.1.5.2 (j) for specifications on runway-holding position marking.

- (vi) A runway designation sign at a taxiway/runway intersection shall be supplemented with a location sign in the outboard (farthest from the taxiway) position, as appropriate.

Note. — See 13.1.5.3(b)(v) for characteristics of location signs.

- (vii) A NO ENTRY sign shall be provided when entry into an area is prohibited.




Figure 13.1.5-32. Examples of sign positions at taxiway/runway intersections

Note.— Distance X is established in accordance with Table 3-2. Distance Y is established at the edge of the ILS/MLS critical/sensitive area.

(2) **Location**

- (i) A runway designation sign at a taxiway/runway intersection or a runway/runway intersection shall be located on each side of the runway-holding position marking facing the direction of approach to the runway.
- (ii) A category I, II or III holding position sign shall be located on each side of the runway-holding position marking facing the direction of the approach to the critical area.
- (iii) A NO ENTRY sign shall be located at the beginning of the area to which entrance is prohibited on each side of the taxiway as viewed by the pilot.

- (iv) A runway-holding position sign shall be located on each side of the runway-holding position established in accordance with 13.1.3.12(a)(3), facing the approach to the obstacle limitation surface or ILS/MLS critical/sensitive area, as appropriate.

(3) **Characteristics**

- (i) A mandatory instruction sign shall consist of an inscription in white on a red background.
- (ii) Where, owing to environmental or other factors, the conspicuity of the inscription on a mandatory instruction sign needs to be enhanced, the outside edge of the white inscription shall be supplemented by a black outline measuring 10 mm in width for runway code numbers 1 and 2, and 20mm in width for runway code numbers 3 and 4.
- (iii) The inscription on a runway designation sign shall consist of the runway designations of the Intersecting runway properly oriented with respect to the viewing position of the sign, except that a runway designation sign installed in the vicinity of a runway extremity may show the runway designation of the concerned runway extremity only.
- (iv) The inscription on a category I, II, III, joint II/III or joint I/II/III holding position sign shall consist of the runway designator followed by CAT I, CAT II, CAT III, CAT II/III or CAT I/II/III, as appropriate.
- (v) The inscription on a NO ENTRY sign shall be in accordance with Figure 13.1.5-30.
- (vi) The inscription on a runway-holding position sign at a runway-holding position established in accordance with 13.1.3.12(a)(3) shall consist of the taxiway designation and a number.
- (vii) Where installed, the inscriptions/symbol of Figure 5-30 shall be used.

(c) **Information Signs**

Note.— See Figure 13.15-31 for pictorial representations of information signs.

(1) **Application**

- (i) An information sign shall be provided where there is an operational need to identify by a sign, a specific location, or routing (direction or destination) information.
- (ii) Information signs shall include: direction signs, location signs, destination signs, runway exit signs, runway vacated signs and intersection take-off signs.
- (iii) A runway exit sign shall be provided where there is an operational need to identify a runway exit.
- (iv) A runway vacated sign shall be provided where the exit taxiway is not provided with taxiway center line lights and there is a need to indicate to a pilot leaving a runway the perimeter of the ILS/MLS critical/sensitive area or the lower edge of the inner transitional surface, whichever is farther from the runway centerline.

Note. — See 13.1.5.3(q) for specifications on color coding taxiway center line lights.

- (v) An intersection take-off sign shall be provided when there is an operational need to indicate the remaining take-off run available (TORA) for intersection take-offs.
- (vi) Where necessary, a destination sign shall be provided to indicate the direction to a specific destination on the aerodrome, such as cargo area, general aviation, etc.
- (vii) A combined location and direction sign shall be provided when it is intended to indicate routing information prior to a taxiway intersection.
- (viii) A direction sign shall be provided when there is an operational need to identify the designation and direction of taxiways at an intersection.
- (ix) A location sign shall be provided at an intermediate holding position.
- (x) A location sign shall be provided in conjunction with a runway designation sign except at a runway/runway intersection.
- (xi) A location sign shall be provided in conjunction with a direction sign, except that it may be omitted where an aeronautical study indicates that it is not needed.
- (xii) Where necessary, a location sign shall be provided to identify taxiways exiting an apron or taxiways beyond an intersection.
- (xiii) Where a taxiway ends at an intersection such as a “T” and it is necessary to identify this, a barricade, direction sign and/or other appropriate visual aid shall be used.

(2) **Location**

- (i) Except as specified in 13.1.5.4(c)(2)(iii) and 13.1.5.4(c)(2)(xi) information signs shall, wherever practicable, be located on the left-hand side of the taxiway in accordance with Table 13.1.5-5.
- (ii) At a taxiway intersection, information signs shall be located prior to the intersection and in line with the intermediate holding position marking. Where there is no intermediate holding position marking, the signs shall be installed at least 60 m from the center line of the intersecting taxiway where the code number is 3 or 4, and at least 40 m where the code number is 1 or 2.

Note. — A location sign installed beyond a taxiway intersection may be installed on either side of a taxiway.

- (iii) A runway exit sign shall be located on the same side of the runway as the exit is located (i.e. left or right) and positioned in accordance with Table 13.1.5-5.
- (iv) A runway exit sign shall be located prior to the runway exit point in line with a position at least 60 m prior to the point of tangency where the code number is 3 or 4, and at least 30 m where the code number is 1 or 2.

- (v) A runway vacated sign shall be located at least on one side of the taxiway. The distance between the sign and the center line of a runway shall be not less than the greater of the following:
 - (A) the distance between the center line of the runway and the perimeter of the ILS/MLS critical/sensitive area; or
 - (B) the distance between the center line of the runway and the lower edge of the inner transitional surface.
 - (vi) Where provided in conjunction with a runway vacated sign, the taxiway location sign shall be positioned outboard of the runway vacated sign.
 - (vii) An intersection take-off sign shall be located at the left-hand side of the entry taxiway. The distance between the sign and the center line of the runway shall be not less than 60 m where the code number is 3 or 4, and not less than 45 m where the code number is 1 or 2.
 - (viii) A taxiway location sign installed in conjunction with a runway designation sign shall be positioned outboard of the runway designation sign.
 - (ix) A destination sign shall not normally be collocated with a location or direction sign.
 - (x) An information sign other than a location sign shall not be collocated with a mandatory instruction sign.
 - (xi) A direction sign, barricade and/or other appropriate visual aid used to identify a “T” intersection shall be located on the opposite side of the intersection facing the taxiway.
- (3) **Characteristics**
- (i) An information sign other than a location sign shall consist of an inscription in black on a yellow background.
 - (ii) A location sign shall consist of an inscription in yellow on a black background and where it is a stand-alone sign shall have a yellow border.
 - (iii) The inscription on a runway exit sign shall consist of the designator of
 - (iv) the exit taxiway and an arrow indicating the direction to follow.
 - (v) The inscription on a runway vacated sign shall depict the pattern A runway-holding position marking as shown in Figure 13.1.5-31.
 - (vi) The inscription on an intersection take-off sign shall consist of a numerical message indicating the remaining take-off run available in meters plus an arrow, appropriately located and oriented, indicating the direction of the take-off as shown in Figure 13.1.5-31.
 - (vii) The inscription on a destination sign shall comprise an alpha, alphanumerical or numerical Message identifying the destination plus an arrow indicating the direction to proceed as shown in Figure 13.1.5-31.
 - (viii) The inscription on a direction sign shall comprise an alpha or alphanumerical message identifying the taxiway(s) plus an arrow or arrows appropriately oriented as shown in Figure 13.1.5-31.

- (ix) The inscription on a location sign shall comprise the designation of the location taxiway, runway or other pavement the aircraft is on or is entering and shall not contain arrows.
- (x) Where it is necessary to identify each of a series of intermediate holding positions on the same taxiway, the location sign shall consist of the taxiway designation and a number.
- (xi) Where a location sign and direction signs are used in combination:
 - (A) all direction signs related to left turns shall be placed on the left side of the location sign, and all direction signs related to right turns shall be placed on the right side of the location sign, except that where the junction consists of one intersecting taxiway, the location sign may alternatively be placed on the left- hand side;
 - (B) the direction signs shall be placed such that the direction of the arrows departs increasingly from the vertical with increasing deviation of the corresponding taxiway;
 - (C) an appropriate direction sign shall be placed next to the location sign where the direction of the location taxiway changes significantly beyond the intersection; and
 - (D) adjacent direction signs shall be delineated by a vertical black line as shown in Figure 13.1.5-31.
- (xii) A taxiway shall be identified by a designator that is used only once on an aerodrome comprising a single letter, two letters or a combination of a letter or letters followed by a number.

When designating taxiways, the use of words such as inner and outer shall be avoided wherever possible
- (xiii) When designating taxiways, the use of the letters I, O or X shall not be used to avoid confusion with the numerals 1, 0 and closed marking.
- (xiv) The use of numbers alone on the maneuvering area shall be reserved for the designation of runways.
- (xv) Apron stand designators shall not be the same as taxiway designators

(d) VOR Aerodrome Checkpoint Sign

- (1) **Application.** When a VOR aerodrome checkpoint is established, it shall be indicated by a VOR aerodrome Checkpoint marking and sign.

Note. — See 13.1.5.2(l) for VOR aerodrome checkpoint marking.

- (2) **Location.** A VOR aerodrome checkpoint sign shall be located as near as possible to the checkpoint and so that the inscriptions are visible from the cockpit of an aircraft properly positioned on the VOR aerodrome check point marking.
- (3) **Characteristics**
 - (i) A VOR aerodrome checkpoint sign shall consist of an inscription in black on a

yellow background.

- (ii) The inscriptions on a VOR checkpoint sign shall be in accordance with one of the alternatives shown in Figure 13.1.5-33 in which:

- VOR** is an abbreviation identifying this as a VOR checkpoint;
- 116.3** is an example of the radio frequency of the VOR concerned;
- 147°** is an example of the VOR bearing, to the nearest degree, which should be indicated at the VOR checkpoint; and
- 4.3NM** is an example of the distance in nautical miles to a DME collocated with the VOR concerned




Figure 13.1.5-33. VOR aerodrome checkpoint sign

Note.— Tolerances for the bearing value shown on the sign are given in Annex 10, Volume I, Attachment E. It will be noted that a checkpoint can only be used operationally when periodic checks show it to be consistently within ± 2 degrees of the stated bearing.

(e) Aerodrome identification sign

- (1) **Application.** An aerodrome identification sign shall be provided at an aerodrome where there is insufficient alternative means of visual identification.
- (2) **Location.** The aerodrome identification sign shall be placed on the aerodrome so as to be legible, in so far as is practicable, at all angles above the horizontal.
- (3) **Characteristics**
 - (i) The aerodrome identification sign shall consist of the name of the aerodrome.
 - (ii) The color selected for the sign shall give adequate conspicuity when viewed against its background.
 - (iii) The characters shall have a height of not less than 3 m.

(f) Aircraft stand identification signs

- (1) **Application.** An aircraft stand identification marking shall be supplemented with an aircraft stand identification sign where feasible.

- (2) **Location.** An aircraft stand identification sign shall be located so as to be clearly visible from the cockpit of an aircraft prior to entering the aircraft stand.
- (3) **Characteristics.** An aircraft stand identification sign shall consist of an inscription in black on a yellow background.

(g) Road-Holding Position Sign

- (1) A road-holding position sign shall be provided at all road entrances to a runway.
- (2) **Location.** The road-holding position sign shall be located 1.5 m from one edge of the road (left or right as appropriate to the local traffic Directives) at the holding position.
- (3) **Characteristics**
 - (i) A road-holding position sign shall consist of an inscription in white on a red background.
 - (ii) The inscription on a road-holding position sign shall be in English language, be in conformity with the local traffic Regulations and include the following:
 - (A) a requirement to stop; and
 - (B) where appropriate:
 - a requirement to obtain ATC clearance; and
 - location designator.

Note. — Examples of road-holding position signs are contained in the Aerodrome Design Manual (Doc 9157), Part 4.

- (iii) A road-holding position sign intended for night use shall be retro reflective or illuminated.

13.1.5.5 **Markers**

(a) General

- (1) Markers shall be frangible. Those located near a runway or taxiway shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

Note 1. — Anchors or chains, to prevent markers which have broken from their mounting from blowing away, are sometimes used.

Note 2. — Guidance on frangibility of markers is given in the Aerodrome Design Manual (Doc 9157), Part 6

(b) Unpaved Runway Edge Markers

- (1) **Application.** Markers shall be provided when the extent of an unpaved runway is not clearly indicated by the appearance of its surface compared with that of the surrounding ground.
- (2) **Location.** Where runway lights are provided, the markers shall be incorporated in the light fixtures. Where there are no lights, markers of flat rectangular or conical shape should be placed so as to delimit the runway clearly.
- (3) **Characteristics.** The flat rectangular markers shall have a minimum size of 1 m by 3 m and shall be placed with their long dimension parallel to the runway center line. The conical markers shall have a height not exceeding 50cm.

(c) Stopway Edge Markers

- (1) **Application.** Stopway edge markers shall be provided when the extent of a stopway is not clearly indicated by its appearance compared with that of the surrounding ground.
- (2) **Characteristics.** The stopway edge markers shall be sufficiently different from any runway edge markers used to ensure that the two types of markers cannot be confused.

Note. — Markers consisting of small vertical boards camouflaged on the reverse side, as viewed from the runway, have proved operationally acceptable.

(d) Taxiway Edge Markers

- (1) **Application.** Taxiway edge markers shall be provided on a taxiway where the code number is 1 or 2 and taxiway center line or edge lights or taxiway center line markers are not provided.
- (2) **Location.** Taxiway edge markers shall be installed at least at the same locations as would the taxiway edge lights had they been used.
- (3) **Characteristics**
 - (i) A taxiway edge marker shall be retro reflective blue.
 - (ii) The marked surface as viewed by the pilot shall be a rectangle and shall have a minimum viewing area of 150cm².
 - (iii) Taxiway edge markers shall be frangible. Their height shall be sufficiently low to preserve clearance for propellers and for the engine pods of jet aircraft.

(e) Taxiway Center Line Markers

- (1) **Application**
 - (i) Taxiway center line markers shall be provided on a taxiway where the code number is 1 or 2 and taxiway centerline or edge lights or taxiway edge markers are not provided.
 - (ii) Taxiway center line markers shall be provided on a taxiway where the code

number is 3 or 4 and taxiway center line lights are not provided if there is a need to improve the guidance provided by the taxiway center line marking.

(2) **Location**

- (i) Taxiway center line markers shall be installed at least at the same location as would taxiway center line lights had they been used.

Note. — See 13.5.3.17.12 for the spacing of taxiway center line lights.

- (ii) Taxiway center line markers shall normally be located on the taxiway center line marking except that they may be offset by not more than 30 cm where it is not practicable to locate them on the marking.

(3) **Characteristics**

- (i) A taxiway center line marker shall be retro reflective green.
- (ii) The marked surface as viewed by the pilot shall be a rectangle and shall have a minimum viewing area of 20cm².
- (iii) Taxiway center line markers shall be so designed and fitted as to withstand being run over by the wheels of an aircraft without damage either to the aircraft or to the markers themselves.

(f) **Unpaved Taxiway Edge Markers**

- (1) **Application.** Where the extent of an unpaved taxiway is not clearly indicated by its appearance compared with that of the surrounding ground, markers shall be provided.
- (2) **Location.** Where taxiway lights are provided, the markers shall be incorporated in the light fixtures. Where there are no lights, markers of conical shape shall be placed so as to delimit the taxiway clearly.

(g) **Boundary Markers**

- (1) **Application.** Boundary markers shall be provided at an aerodrome where the landing area has no runway.
- (2) **Location.** Boundary markers shall be spaced along the boundary of the landing area at intervals of not more than 200 m, if the type shown in
- (3) Figure 13.1.5-34 is used, or approximately 90 m, if the conical type is used with a marker at any corner.
- (4) **Characteristics.** Boundary markers shall be of a form similar to that shown in Figure 13.1.5- 34, or in the form of a cone not less than 50 cm high and not less than 75 cm in diameter at the base. The markers shall be colored to contrast with the background against which they will be seen. A single color, orange or red, or two contrasting colors, orange and white or alternatively red and white, shall be used, except where such colors merge with the background.




Figure 13.1.5-34. Boundary markers

13.1.6 VISUAL AIDS FOR DENOTING OBSTACLES

13.1.6.1 Objects To Be Marked and/or Lighted

Note 1 - The marking and/or lighting of obstacles is intended to reduce hazards to aircraft by indicating the presence of the obstacles. It does not necessarily reduce operating limitations which may be imposed by an obstacle.

Note 2.— An autonomous aircraft detection system may be installed on or near an obstacle (or group of obstacles such as wind farms), designed to operate the lighting only when the system detects an aircraft approaching the obstacle, in order to reduce light exposure to local residents. Guidance on the design and installation of an autonomous aircraft detection system is available in the Aerodrome Design Manual (Doc 9157), Part 4. The availability of such guidance is not intended to imply that such a system has to be provided.

(a) Objects within the lateral boundaries of the obstacle limitation surfaces

- (1) Vehicles and other mobile objects, excluding aircraft, on the movement area of an aerodrome are obstacles and shall be marked and, if the vehicles and aerodrome are used at night or in conditions of low visibility, lighted, except that aircraft servicing equipment and vehicles used only on aprons may be exempt.
- (2) Elevated aeronautical ground lights within the movement area shall be marked so as to be conspicuous by day. Obstacle lights shall not be installed on elevated ground lights or signs in the movement area.
- (3) All obstacles within the distance specified in Table 13.1.3-1, column 11 or 12, from the center line of a taxiway, an apron taxiway or aircraft stand taxilane shall be marked and, if the taxiway, apron taxiway or aircraft stand taxilane is used at night, lighted.
- (4) A fixed obstacle that extends above a take-off climb surface within 3 000 m of the inner edge of the take-off climb surface shall be marked and, if the runway is used at night, lighted, except that:
 - (i) such marking and lighting may be omitted when the obstacle is shielded by another fixed obstacle;
 - (ii) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150m;
 - (iii) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
 - (iv) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates the lighthouse light to be sufficient.
- (5) A fixed object, other than an obstacle, adjacent to a take-off climb surface shall be marked and, if the runway is used at night, lighted, if such marking and lighting is considered necessary to ensure its avoidance, except that the marking may be omitted when:
 - (i) the object is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150 m;

or

- (ii) the object is lighted by high-intensity obstacle lights by day.
- (6) A fixed obstacle that extends above an approach surface within 3 000 m of the inner edge or above a transitional surface shall be marked and, if the runway is used at night, lighted, except that:
- (i) such marking and lighting may be omitted when the obstacle is shielded by another fixed obstacle;
 - (ii) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150m;
 - (iii) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
 - (iv) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates the lighthouse light to be sufficient.
- (7) A fixed obstacle that extends above a horizontal surface shall be marked and, if the aerodrome is used at night, lighted, except that:
- (i) such marking and lighting may be omitted when:
 - (A) the obstacle is shielded by another fixed obstacle; or
 - (B) for a circuit extensively obstructed by immovable objects or terrain, procedures have been established to ensure safe vertical clearance below prescribed flight paths; or
 - (C) an aeronautical study shows the obstacle not to be of operational significance;
 - (ii) the marking may be omitted when the obstacle is lighted by medium-intensity obstacle lights, Type A, by day and its height above the level of the surrounding ground does not exceed 150m;
 - (iii) the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day; and
 - (iv) the lighting may be omitted where the obstacle is a lighthouse and an aeronautical study indicates the lighthouse light to be sufficient.
- (8) A fixed object that extends above an obstacle protection surface shall be marked and, if the runway is used at night, lighted.

Note. — See [13.5.3.5](#) for information on the obstacle protection surface.

- (9) Other objects inside the obstacle limitation surfaces shall be marked and/or lighted if an aeronautical study indicates that the object could constitute a hazard to aircraft (this includes objects adjacent to visual routes e.g. waterway or highway).

Note. — See note in [13.4.4.2](#).

- (10) Overhead wires, cables, etc., crossing a river, waterway, valley or highway shall be marked and their supporting towers marked and lighted if an aeronautical study indicates that the wires or cables could constitute a hazard to aircraft.

(b) Objects outside the lateral boundaries of the obstacle limitation surfaces

- (1) Obstacles in accordance with 13.4.3.2 shall be marked and lighted, except that the marking may be omitted when the obstacle is lighted by high-intensity obstacle lights by day.
- (2) Other objects outside the obstacle limitation surfaces shall be marked and/or lighted if an aeronautical study indicates that the object could constitute a hazard to aircraft (this includes objects adjacent to visual routes e.g. waterway, highway).
- (3) Overhead wires, cables, etc., crossing a river, waterway, valley or highway shall be marked and their supporting towers marked and lighted if an aeronautical study indicates that the wires or cables could constitute a hazard to aircraft.

13.1.6.2 **Marking And Lighting Of Objects**

(a) General

- (1) The presence of objects which must be lighted, as specified in 14.6.1, shall be indicated by low-, medium- or high intensity obstacle lights, or a combination of such lights.
- (2) Low-intensity obstacle lights, Types A B, C, D and E, medium-intensity obstacle lights, Types A, B and C, high-intensity obstacle lights Type A and B, shall be in accordance with the specifications in Table 13.1.6-1 and Appendix 1.
- (3) The number and arrangement of low-, medium- or high-intensity obstacle lights at each level to be marked shall be such that the object is indicated from every angle in azimuth. Where a light is shielded in any direction by another part of the object, or by an adjacent object, additional lights shall be provided on that adjacent object or the part of the object that is shielding the light, in such a way as to retain the general definition of the object to be lighted. If the shielded light does not contribute to the definition of the object to be lighted, it may be omitted.

(b) Mobile Objects

- (1) **Marking.** All mobile objects to be marked shall be colored or display flags.
- (2) **Marking by color.** When mobile objects are marked by color, a single conspicuous color, preferably red or yellowish green for emergency vehicles and yellow for service vehicles, shall be used.
- (3) **Marking by flags**
 - (i) Flags used to mark mobile objects shall be displayed around, on top of, or around the highest edge of the object. Flags shall not increase the hazard presented by the object they mark.
 - (ii) Flags used to mark mobile objects shall not be less than 0.9 m on each side and shall consist of a chequered pattern, each square having sides

- (iii) of not less than 0.3 m. The colors of the pattern shall contrast each with the other and with the background against which they will be seen. Orange and white or alternatively red and white shall be used, except where such colors merge with the background.

Table 13.1.6-1. Characteristics of obstacle lights

1 Light Type	2 Colour	3 Signal type/ (flash rate)	4 Peak intensity (cd) at given Background Luminance (b)			7 Light Distribution Table
			5 Day (Above 500 cd/m ²)	5 Twilight (50-500 cd/m ²)	6 Night (Below 50 cd/m ²)	
			Low-intensity, Type A (fixed obstacle)	Red	Fixed	
Low-intensity, Type B (fixed obstacle)	Red	Fixed	N/A	N/A	32	Table 13.1.6-2
Low-intensity, Type C (mobile obstacle)	Yellow/Blue (a)	Flashing (60-90 fpm)	N/A	40	40	Table 13.1.6-2
Low-intensity, Type D (follow-me vehicle)	Yellow	Flashing (60-90 fpm)	N/A	200	200	Table 13.1.6-2
Low-intensity, Type E	Red	Flashing (c)	N/A	N/A	32	Table 6-2 (Type B)
Medium-intensity, Type A	White	Flashing (20-60 fpm)	20 000	20 000	2 000	Table 13.1.6-3
Medium-intensity, Type B	Red	Flashing (20-60 fpm)	N/A	N/A	2 000	Table 13.1.6-3
Medium-intensity, Type C	Red	Fixed	N/A	N/A	2 000	Table 6-3
High-intensity, Type A	White	Flashing (40-60 fpm)	200 000	20 000	2 000	Table 13.1.6-3
High-intensity, Type B	White	Flashing (40-60 fpm)	100 000	20 000	2 000	Table 13.1.6-3

- a) See 13.1.6.2(b)(4)(ii)
- b) For flashing lights, effective intensity as determined in accordance with the *Aerodrome Design Manual* (Doc 9157), Part 4.
- c) For wind turbine application, to flash at the same rate as the lighting on the nacelle.

Table 13.1.6-2. Light distribution for low-intensity obstacle lights

	Minimum intensity (a)	Maximum intensity (a)	Vertical beam spread (f)	
			Minimum beam spread	Intensity
Type A	10 cd (b)	N/A	10°	5 cd
Type B	32 cd (b)	N/A	10°	16 cd
Type C	40 cd (b)	400 cd	12° (d)	20 cd
Type D	200 cd (c)	400 cd	N/A (e)	N/A

Note. — This table does not include recommended horizontal beam spreads. 13.1.6.2(a)(3) requires 360° coverage around an obstacle. Therefore, the number of lights needed to meet this requirement will depend on the horizontal beam spreads of each light as well as the shape of the obstacle. Thus, with narrower beam spreads, more lights will be required.

- a) 360° horizontal. For flashing lights, the intensity is read into effective intensity, as determined in accordance with the Aerodrome Design Manual (Doc 9157), Part4.
- b) Between 2 and 10° vertical. Elevation vertical angles are referenced to the horizontal when the light is leveled.
- c) Between 2 and 20° vertical. Elevation vertical angles are referenced to the horizontal when the light is leveled.
- d) Peak intensity should be located at approximately 2.5° vertical.
- e) Peak intensity should be located at approximately 17° vertical.
- f) Beam spread is defined as the angle between the horizontal plane and the directions for which the intensity exceeds that mentioned in the “intensity” column.

Table 13.1.6-3. Light distribution for medium- and high-intensity obstacle lights according to benchmark intensities of Table 13.1.6-1

Benchmark intensity	Minimum requirements					Recommendations				
	Vertical elevation angle (b)			Vertical beam spread (c)		Vertical elevation angle (b)			Vertical beam spread (c)	
	0°		-1°			0°	-1°	-10°		
	Minimum average intensity (a)	Minimum intensity (a)	Minimum intensity (a)	Minimum beam spread	Intensity (a)	Maximum intensity (a)	Maximum intensity (a)	Maximum intensity (a)	Maximum beam spread	Intensity (a)
200 000	200 000	150 000	75 000	3°	75 000	250 000	112 500	7 500	7°	75 000
100 000	100 000	75 000	37 500	3°	37 500	125 000	56 250	3 750	7°	37 500
20 000	20 000	15 000	7 500	3°	7 500	25 000	11 250	750	N/A	N/A
2 000	2 000	1 500	750	3°	750	2 500	1 125	75	N/A	N/A

Note. — This table does not include recommended horizontal beam spreads. 13.1.6.2(a)(3) requires 360° coverage around an obstacle. Therefore, the number of lights needed to meet this requirement will depend on the horizontal beam spreads of each light as well as the shape of the obstacle. Thus, with narrower beam spreads, more lights will be required.

- a) 360° horizontal. All intensities are expressed in Candela. For flashing lights, the intensity is read into effective intensity, as determined in accordance with the *Aerodrome Design Manual* (Doc 9157), Part 4.
- b) Elevation vertical angles are referenced to the horizontal when the light unit is leveled.
- c) Beam spread is defined as the angle between the horizontal plane and the directions for which the intensity exceeds that mentioned in the “intensity” column.

Note. — An extended beam spread may be necessary under specific configuration and justified by an aeronautical study.

(4) **Lighting**

- (i) Low-intensity obstacle lights, Type C, shall be displayed on vehicles and other mobile objects excluding aircraft.

Note. — See ICAO Annex 2 for lights to be displayed by aircraft.

- (ii) Low-intensity obstacle lights, Type C, displayed on vehicles associated with emergency or security shall be flashing-blue and those displayed on other vehicles shall be flashing- yellow.
- (iii) Low-intensity obstacle lights, Type D, shall be displayed on follow-me vehicles.
- (iv) Low-intensity obstacle lights on objects with limited mobility such as aerobridges shall be fixed-red, and as a minimum be in accordance with the specifications for low- intensity obstacle lights, Type A, in Table 6-1. The intensity of the lights shall be sufficient to ensure conspicuity considering the intensity of the adjacent lights and the general levels of illumination against which they would normally be viewed.

(c) **Fixed Objects**

Note.— The fixed objects of wind turbines are addressed separately in 13.1.6.2(d) and the fixed objects of overhead wires, cables, etc., and supporting towers are addressed separately in 13.1.6.2(e).

- (1) **Marking.** All fixed objects to be marked shall, whenever practicable, be colored, but if this is not practicable, markers or flags shall be displayed on or above them, except that objects that are sufficiently conspicuous by their shape, size or color need not be otherwise marked.
- (2) **Marking by color**

- (i) An object shall be colored to show a chequered pattern if it has essentially unbroken surfaces and its projection on any vertical plane equals or exceeds 4.5 m in both dimensions. The pattern shall consist of rectangles of not less than 1.5 m and not more than 3 m on a side, the corners being of the darker color. The colors of the pattern should contrast each with the other and with the background against which they will be seen. Orange and white or alternatively red and white should be used, except where such colors merge with the background. (See Figure6-1.
- (ii) An object shall be colored to show alternating contrasting bands if:
 - (A) it has essentially unbroken surfaces and has one dimension, horizontal or vertical, greater than 1.5 m, and the other dimension, horizontal or vertical, less than 4.5 m; or
 - (B) it is of skeletal type with either a vertical or a horizontal dimension greater than 1.5 m.
- (iii) The bands shall be perpendicular to the longest dimension and have a width approximately 1/7 of the longest dimension or 30 m, whichever is less. The colors of the bands shall contrast with the background against which they will be seen. Orange and white shall be used, except where such colors are not conspicuous when viewed against the background. The bands on the extremities of the object shall be of the darker color. (See Figures 13.1.6-1 and 13.1.6-2.)

Note. — Table 6-4 shows a formula for determining band widths and for having an odd number of bands, thus permitting both the top and bottom bands to be of the darker color.




Figure 13.1.6-1. Basic marking patterns

Table 13.1.6-4 Marking band widths

Longest dimension		Band width
Greater than	Not exceeding	
1.5 m	210 m	1/7 of longest dimension
210 m	270 m	1/9 " " "
270 m	330 m	1/11 " " "
330 m	390 m	1/13 " " "
390 m	450 m	1/15 " " "
450 m	510 m	1/17 " " "
510 m	570 m	1/19 " " "
570 m	630 m	1/21 " " "

- (iv) An object should be colored in a single conspicuous color if its projection on any vertical plane has both dimensions less than 1.5 m. Orange or red should be used, except where such colors merge with the background.

Note.— Against some backgrounds it may be found necessary to use a different color from orange or red to obtain sufficient contrast.

(3) **Marking by flags**

- (i) Flags used to mark fixed objects shall be displayed around, on top of, or around the highest edge of, the object. When flags are used to mark extensive objects or groups of closely spaced objects, they shall be displayed at least every 15 m. Flags shall not increase the hazard presented by the object they mark.
- (ii) Flags used to mark fixed objects shall not be less than 0.6 m on each side.
- (iii) Flags used to mark fixed objects shall be orange in color or a combination of two triangular sections, one orange and the other white, or one red and the other white, except that where such colors merge with the background, other conspicuous colors should be used.




Figure 13.1.6-2. Examples of marking and lighting of tall structures

(4) **Marking by markers**

- (i) Markers displayed on or adjacent to objects shall be located in conspicuous positions so as to retain the general definition of the object and shall be recognizable in clear weather from a distance of at least

1 000 m for an object to be viewed from the air and 300 m for an object to be

viewed from the ground in all directions in which an aircraft is likely

- (ii) to approach the object. The shape of markers shall be distinctive to the extent necessary to ensure that they are not mistaken for markers employed to convey other information, and they shall be such that the hazard presented by the object they mark is not increased.
- (iii) A marker shall be of one color. When installed, white and red, or white and orange markers shall be displayed alternately. The color selected should contrast with the background against which it will be seen.

(5) **Lighting**

- (i) In the case of an object to be lighted, one or more low-, medium- or high-intensity obstacle lights shall be located as close as practicable to the top of the object.

Note. — Recommendations on how a combination of low-, medium- and/or high-intensity lights on obstacles should be displayed are given in Appendix 6.

- (ii) In the case of chimney or other structure of like function, the top lights shall be placed sufficiently below the top so as to minimize contamination by smoke, etc. (See Figure 13.1.6- 2).
- (iii) In the case of a tower or antenna structure indicated by high-intensity obstacle lights by day with an appurtenance, such as a rod or an antenna, greater than 12 m where it is not practicable to locate a high-intensity obstacle light on the top of the appurtenance, such a light shall be located at the highest practicable point and, if practicable, a medium-intensity obstacle light, Type A, mounted on the top.
- (iv) In the case of an extensive object or of a group of closely spaced objects to be lighted that are:
 - (A) penetrating a horizontal obstacle limitation surface (OLS) or located outside an OLS, the top lights shall be so arranged as to at least indicate the points or edges of the object highest in relation to the obstacle limitation surface or above the ground, and so as to indicate the general definition and the extent of the objects; and
 - (B) penetrating a sloping OLS, the top lights shall be so arranged as to at least indicate the points or edges of the object highest in relation to the OLS, and so as to indicate the general definition and the extent of the objects. If two or more edges are of the same height, the edge nearest the landing area shall be marked.
- (v) When the obstacle limitation surface concerned is sloping and the highest point above the OLS is not the highest point of the object, additional obstacle lights shall be placed on the highest point of the object.
- (vi) Where lights are applied to display the general definition of an extensive object or a group of closely spaced objects, and
 - (A) low-intensity lights are used, they shall be spaced at longitudinal intervals not exceeding 45 m; and

(B) medium-intensity lights are used, they shall be spaced at longitudinal intervals not exceeding 900 m.

(vii) High-intensity obstacle lights, Type A, and medium-intensity obstacle lights, Types A and B, located on an object shall flash simultaneously.

(viii) The installation setting angles for high-intensity obstacle lights, Type A, shall be in accordance with Table 13.1.6-5.

Note. — *High-intensity obstacle lights are intended for day use as well as night use. Care is needed to ensure that these lights do not create disconcerting dazzle. Guidance on the design, location and operation of high-intensity obstacle lights is given in the Aerodrome Design Manual (Doc 9157), Part 4.*

(ix) Where the use of high-intensity obstacle lights, Type A, or medium-intensity obstacle lights, Type A, at night may dazzle pilots in the vicinity of an aerodrome (within approximately 10 000 m radius) or cause significant environmental concerns, a dual obstacle lighting system shall be provided. This system shall be composed of high-intensity obstacle lights, Type A, or medium-intensity obstacle lights, Type A, as appropriate, for daytime and twilight use and medium-intensity obstacle lights, Type B or C, for night-time use.

(6) **Lighting of objects with a height less than 45 m above ground level**

(i) Low-intensity obstacle lights, Type A or B, shall be used where the object is a less extensive one and its height above the surrounding ground is less than 45m.

(ii) Where the use of low-intensity obstacle lights, Type A or B, would be inadequate or an early special warning is required, then medium- or high-intensity obstacle lights shall be used.

(iii) Low-intensity obstacle lights, Type B, shall be used either alone or in combination with medium-intensity obstacle lights, Type B, in accordance with 6.2.3.22.

(iv) Medium-intensity obstacle lights, Type A, B or C, should be used where the object is an extensive one. Medium-intensity obstacle lights, Types A and C, should be used alone, whereas medium-intensity obstacle lights, Type B, shall be used either alone or in combination with low-intensity obstacle lights, Type B.

Note. — *A group of buildings is regarded as an extensive object.*

(7) **Lighting of objects with a height 45 m to a height less than 150 m above ground level**

(i) Medium-intensity obstacle lights, Type A, B or C, shall be used. Medium-intensity obstacle lights, Types A and C, shall be used alone, whereas

- (ii) medium-intensity obstacle lights, Type B, shall be used either alone or in combination with low-intensity obstacle lights, Type B.
 - (iii) Where an object is indicated by medium-intensity obstacle lights, Type A, and the top of the object is more than 105 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 105m.
 - (iv) Where an object is indicated by medium-intensity obstacle lights, Type B, and the top of the object is more than 45 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be alternately low-intensity obstacle lights, Type B, and medium-intensity obstacle lights, Type B, and shall be spaced as equally as practicable between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52m.
 - (v) Where an object is indicated by medium-intensity obstacle lights, Type C, and the top of the object is more than 45 m above the level of the surrounding ground or the elevation of tops of nearby buildings (when the object to be marked is surrounded by buildings), additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52m.
 - (vi) Where high-intensity obstacle lights, Type A, are used, they shall be spaced at uniform intervals not exceeding 105m between the ground level and the top light(s) specified in 13.6.2.3.10, except that where an object to be marked is surrounded by buildings, the elevation of the tops of the buildings may be used as the equivalent of the ground level when determining the number of light levels.
- (8) ***Lighting of objects with a height 150 m or more above ground level***
- (i) High-intensity obstacle lights, Type A, shall be used to indicate the presence of an object if its height above the level of the surrounding ground exceeds 150 m and an aeronautical study indicates such lights to be essential for the recognition of the object by day.
 - (ii) Where high-intensity obstacle lights, Type A, are used, they shall be spaced at uniform intervals not exceeding 105 m between the ground
 - (iii) level and the top light(s) specified in 13.6.2.3.10, except that where an object to be marked is surrounded by buildings, the elevation of the tops of the buildings may be used as the equivalent of the ground level when determining the number of light levels.
 - (iv) Where, in the opinion of the appropriate authority, the use of high-intensity obstacle lights, Type A, at night may dazzle pilots in the vicinity
 - (v) of an aerodrome (within approximately 10 000 m radius) or cause significant environmental concerns, medium-intensity obstacle lights, Type C, shall be

used alone, whereas medium intensity obstacle lights, Type B, shall be used either alone or in combination with low-intensity obstacle lights, Type B.

- (vi) Where an object is indicated by medium-intensity obstacle lights, Type A, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 105m.
- (vii) Where an object is indicated by medium-intensity obstacle lights, Type B, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be alternately low-intensity obstacle lights, Type B, and medium-intensity obstacle lights, Type B, and shall be spaced as equally as practicable between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52m.
- (viii) Where an object is indicated by medium-intensity obstacle lights, Type C, additional lights shall be provided at intermediate levels. These additional intermediate lights shall be spaced as equally as practicable, between the top lights and ground level or the level of tops of nearby buildings, as appropriate, with the spacing not exceeding 52m.

(d) Wind Turbines

- (1) **General.** A wind turbine shall be marked and/or lighted if it is determined by the Authority to be an obstacle.

Note 1. — Additional lighting or markings may be provided where in the opinion of LCAA such lighting or markings are deemed necessary.

Note 2. — See 13.1.4.4(a) and 13.1.4.4(b)

- (2) **Markings.** The rotor blades, nacelle and upper 2/3 of the supporting mast of wind turbines shall be painted white, unless otherwise indicated by an aeronautical study.

- (3) **Lighting**

- (i) When lighting is deemed necessary, in the case of a wind farm, i.e. a group of two or more wind turbines, the wind farm shall be regarded as an extensive object and the lights shall be installed:

- (A) to identify the perimeter of the wind farm;
- (B) respecting the maximum spacing, in accordance with 13.6.2.3.15, between the lights along the perimeter, unless a dedicated assessment shows that a greater spacing can be used;
- (C) so that, where flashing lights are used, they flash simultaneously throughout the wind farm;
- (D) so that, within a wind farm, any wind turbines of significantly higher elevation are also identified wherever they are located; and
- (E) at locations prescribed in (A), (B) and (D), respecting the following criteria:

- 1. for wind turbines of less than 150 m in overall height (hub height

- plus vertical blade height), medium-intensity lighting on the nacelle shall be provided;
2. for wind turbines from 150 m to 315 m in overall height, in addition to the medium-intensity light installed on the nacelle, a second light serving as an alternate shall be provided in case of failure of the operating light. The lights should be installed to assure that the output of either light is not blocked by the other; and
 3. in addition, for wind turbines from 150 m to 315 m in overall height, an intermediate level at half the nacelle height of at least three low-intensity Type E lights, as specified in 13.6.2.1.3, shall be provided. If an aeronautical study shows that low-intensity Type E lights are not suitable, low-intensity Type A or B lights may be used.

Note. — The above 13.1.6.2(d)(3)(i)(E) does not address wind turbines of more than 315 m of overall height. For such wind turbines, additional marking and lighting may be required as determined by an aeronautical study.

- (ii) The obstacle lights shall be installed on the nacelle in such a manner as to provide an unobstructed view for aircraft approaching from any direction.
- (iii) Where lighting is deemed necessary for a single wind turbine or short line of wind turbines, the installation should be in accordance with 13.6.2.4.3 (e) or as determined by an aeronautical study.

(e) Overhead wires, cables, etc., and supporting towers

- (1) **Marking.** The wires, cables, etc., to be marked shall be equipped with markers; the supporting tower should be colored.
- (2) **Marking by colors.** The supporting towers of overhead wires, cables, etc., that require marking shall be marked in accordance with 13.6.2.3.1 to 13.6.2.3.4, except that the marking of the supporting towers may be omitted when they are lighted by high-intensity obstacle lights by day.
- (3) **Marking by markers**
 - (i) Markers displayed on or adjacent to objects shall be located in conspicuous positions so as to retain the general definition of the object
 - (ii) and shall be recognizable in clear weather from a distance of at least 1 000 m for an object to be viewed from the air and 300 m for an object to be viewed from the ground in all directions in which an aircraft is likely to approach the object. The shape of markers shall be distinctive to the extent necessary to ensure that they are not mistaken for markers employed to convey other information, and they shall be such that the hazard presented by the object they mark is not increased.
 - (iii) A marker displayed on an overhead wire, cable, etc., shall be spherical and have a diameter of not less than 60cm.
 - (iv) The spacing between two consecutive markers or between a marker and a

supporting tower should be appropriate to the diameter of the marker, but in no case shall the spacing exceed:

- (A) 30 m where the marker diameter is 60 cm progressively increasing with the diameter of the marker to
 - (B) 35 m where the marker diameter is 80 cm and further progressively increasing to a maximum of
 - (C) 40 m where the marker diameter is of at least 130 cm. Where multiple wires, cables, etc., are involved, a marker shall be located not lower than the level of the highest wire at the point marked.
- (v) A marker shall be of one color. When installed, white and red, or white and orange markers should be displayed alternately. The color selected shall contrast with the background against which it will be seen.
 - (vi) When it has been determined that an overhead wire, cable, etc., needs to be marked but it is not practicable to install markers on the wire, cable, etc., then high-intensity obstacle lights, Type B, shall be provided on their supporting towers.
- (4) **Lighting**
- (i) High-intensity obstacle lights, Type B, shall be used to indicate the presence of a tower supporting overhead wires, cables, etc., where:
 - (A) an aeronautical study indicates such lights to be essential for the recognition of the presence of wires, cables, etc.; or
 - (B) it has not been found practicable to install markers on the wires, cables, etc.
 - (ii) Where high-intensity obstacle lights, Type B, are used, they shall be located at three levels:
 - (A) at the top of the tower;
 - (B) at the lowest level of the catenary of the wires or cables; and
 - (C) at approximately midway between these two levels.

Note. — In some cases, this may require locating the lights off the tower.

- (iii) High-intensity obstacle lights, Type B, indicating the presence of a tower supporting overhead wires, cables, etc., shall flash sequentially; first the middle light, second the top light and last, the bottom light. The intervals between flashes of the lights shall approximate the following ratios:

Flash interval between	Ratio of cycle time
middle and top light	1/13
top and bottom light	2/13
bottom and middle light	10/13.

Note. — High-intensity obstacle lights are intended for day use as well as night use. Care is needed to ensure that these lights do not create disconcerting dazzle. Guidance on the design, operation and

- (iv) The installation setting angles for high-intensity obstacle lights, Type B, shall be in accordance with Table 13.1.6-5.

Table 13.1.6-5. Installation setting angles for high-intensity obstacle lights

Height of light unit above terrain (AGL)		Angle of the peak of the beam above the horizontal
Greater than	Not exceeding	
151 m		0°
122 m	151 m	1°
92 m	122 m	2°
	92 m	3°

13.1.7 VISUAL AIDS FOR DENOTING RESTRICTED USE AREAS

13.1.7.1 Closed Runways And Taxiways, or Parts Thereof

(a) Application

- (1) The Aerodrome Operator shall ensure that a closed marking shall be displayed on a runway or taxiway or portion thereof which is permanently closed to the use of all aircraft.
- (2) A closed marking shall be displayed on a temporarily closed runway or taxiway or portion thereof, except that such marking may be omitted when the closing is of short duration and adequate warning by air traffic services is provided.

(b) Location. On a runway a closed marking shall be placed at each end of the runway, or portion thereof, declared closed, and additional markings shall be so placed that the maximum interval between markings does not exceed 300 m. On a taxiway a closed marking shall be placed at least at each end of the taxiway or portion thereof closed.

(c) Characteristics

- (1) The closed marking shall be of the form and proportions as detailed in Figure 7-1, Illustration a), when displayed on a runway, and shall be of the form and proportions as detailed in Figure 13.1.7-1, Illustration b), when displayed on a taxiway. The marking shall be white when displayed on a runway and shall be yellow when displayed on a taxiway.

Note. — When an area is temporarily closed, frangible barriers or markings utilizing materials other than paint or other suitable means may be used to identify the closed area.

Note 2.— Procedures pertaining to the planning, coordination, monitoring and safety management of works in progress on the movement area are specified in the PANS-Aerodromes (Doc 9981)

- (2) When a runway or taxiway or portion thereof is permanently closed, all normal runway and taxiway markings shall be obliterated.
- (3) Lighting on a closed runway or taxiway or portion thereof shall not be operated, except as required for maintenance purposes.
- (4) In addition to closed markings, when the runway or taxiway or portion thereof closed is intercepted by a usable runway or taxiway which is used at night, un serviceability lights shall be placed across the entrance to the closed area at intervals not exceeding 3 m (see 13.7.4.4).




Figure 13.1.7-1. Closed runway and taxiway markings

13.1.7.2 Non-Load-Bearing Surfaces

- (a) **Application.** Shoulders for taxiways, runway turn pads, holding bays and aprons and other non-load-bearing surfaces which cannot readily be distinguished from load-bearing surfaces and which, if used by aircraft, might result in damage to the aircraft shall have the boundary between such areas and the load-bearing surface marked by a taxi side stripe marking.

Note. — The marking of runway sides is specified in 13.5.2.7.

(b) **Location**

- (1) A taxi side stripe marking shall be placed along the edge of the load-bearing pavement, with the outer edge of the marking approximately on the edge of the load-bearing pavement.

- (2) A taxi side stripe marking shall consist of a pair of solid lines, each 15 cm wide and spaced 15 cm apart and the same color as the taxiway center line marking.

Note. — Guidance on providing additional transverse stripes at an intersection or a small area on the apron is given in the Aerodrome Design Manual (Doc 9157), Part 4.

13.1.7.3 Pre-Threshold Area

- (a) **Application:** When the surface before a threshold is paved and exceeds 60 m in length and is not suitable for normal use by aircraft, the entire length before the threshold shall be marked with a chevron marking.
- (b) **Location:** A chevron marking shall point in the direction of the runway and be placed as shown in Figure 13.1.7-2.
- (c) **Characteristics:** A chevron marking should be of conspicuous color and contrast with the color used for the runway markings; it should preferably be yellow. It shall have an overall width of at least 0.9 m.




Figure 13.1.7-2. Pre-threshold marking

13.1.7.4 Unserviceable Areas

- (a) **Application.** Un serviceability markers shall be displayed wherever any portion of a taxiway, apron or holding bay is unfit for the movement of aircraft but it is still possible for aircraft to bypass the area safely. On a movement area used at night, un serviceability lights shall be used.

Note 1 — Un serviceability markers and lights are used for such purposes as warning pilots of a hole in a taxiway or apron pavement or outlining a portion of pavement, such as on an apron, that is under repair. They are not suitable for use when a portion of a runway becomes unserviceable, nor on a taxiway when a major portion of the width becomes unserviceable. In such instances, the runway or taxiway is normally closed.

Note 2.— Procedures pertaining to the planning, coordination, monitoring and safety management of works in progress on the movement area are specified in the PANS-Aerodromes (Doc 9981).

- (b) **Location.** Unserviceability markers and lights shall be placed at intervals sufficiently close so as to delineate the unserviceable area.
- (c) **Characteristics of unserviceability markers.** Unserviceability markers shall consist of conspicuous upstanding devices such as flags, cones or marker boards.
- (d) **Characteristics of unserviceability lights.** An unserviceability light shall consist of a red fixed light. The light shall have an intensity sufficient to ensure conspicuity considering the intensity of the adjacent lights and the general level of illumination against which it would normally be viewed. In no case shall the intensity be less than 10 cd of red light.
- (e) **Characteristics of unserviceability cones.** An unserviceability cone shall be at least 0.5 m in height and red, orange or yellow or any one of these colors in combination with white.
- (f) **Characteristics of unserviceability flags.** An unserviceability flag shall be at least 0.5 m square and red, orange or yellow or any one of these colors in combination with white.
- (g) **Characteristics of unserviceability marker boards.** An unserviceability marker board shall be at least 0.5 m in height and 0.9 m in length, with alternate red and white or orange and white vertical stripes.

13.1.8 ELECTRICAL SYSTEMS

13.1.8.1 Electrical Power Supply Systems For Air Navigation Facilities

Note.— The safety of operations at aerodromes depends on the quality of the supplied power. The total electrical power supply system may include connections to one or more external sources of electric power supply, one or more local generating facilities and to a distribution network including transformers and switchgear. Many other aerodrome facilities supplied from the same system need to be taken into account while planning the electrical power system at aerodromes.

- (a) Adequate primary power supply shall be available at aerodromes for the safe functioning of air navigation facilities.
- (b) The design and provision of electrical power systems for aerodrome visual and radio navigation aids shall be such that an equipment failure will not leave the pilot with inadequate visual and non-visual guidance or misleading information.

Note. — The design and installation of the electrical systems need to take into consideration factors that can lead to malfunction, such as electromagnetic disturbances, line losses, power quality, etc. Additional guidance is given in the Aerodrome Design Manual (Doc 9157), Part 5.

- (c) Electric power supply connections to those facilities for which secondary power is required shall be so arranged that the facilities are automatically connected to the secondary power supply on failure of the primary source of power.
- (d) The time interval between failure of the primary source of power and the complete restoration of the services required by 13.8.1.10 shall be as short as practicable, except that for visual aids associated with non-precision, precision approach or take-off runways the requirements of Table 8-1 for maximum switch-over times shall apply.

Note. — A definition of switch-over time is given in section 13.1.1.

- (e) The electric power supply connections to those facilities for which secondary power is required shall be so arranged that the facilities are capable of meeting the requirements of Table 13.1.8-1 for maximum switch-over times as defined Subpart 1 of this Regulation.

(f) Visual Aids

(1) Application

- (i) For a precision approach runway, a secondary power supply capable of meeting the requirements of Table 13.1.8-1 for the appropriate category of precision approach runway shall be provided. Electric power supply connections to those facilities for which secondary power is required shall be so arranged that the facilities are automatically connected to the secondary power supply on failure of the primary source of power.
- (ii) For a runway meant for take-off in runway visual range conditions less than a value of 800 m, A secondary power supply capable of meeting the relevant requirements of Table 13.1.8-1 shall be provided.
- (iii) At an aerodrome where the primary runway is a non-precision approach runway, a secondary power supply capable of meeting the requirements of Table 13.1.8-1 shall be provided except that a secondary power supply for

visual aids need not be provided for more than one non-precision approach runway.

- (iv) At an aerodrome where the primary runway is a non-instrument runway, a secondary power supply capable of meeting the requirements of 13.1.8.1 (d) shall be provided, except that a secondary power supply for visual aids need not be provided when an emergency lighting system in accordance with the specification of 13.5.3.2 is provided and capable of being deployed in 15minutes.
- (v) The following aerodrome facilities shall be provided with a secondary power supply capable of supplying power when there is a failure of the primary power supply:

1. the signaling lamp and the minimum lighting necessary to enable air traffic services personnel to carry out their duties;

Note. — *The requirement for minimum lighting may be met by other than electrical means.*

2. all obstacle lights which, in the opinion of the appropriate authority, are essential to ensure the safe operation of aircraft;
3. approach, runway and taxiway lighting as specified in 13.1.8.1(f)(1)(i) to 13.1.8.1(f)(1)(iv);
4. meteorological equipment;
5. essential security lighting, if provided in accordance with 13.9.11;
6. essential equipment and facilities for the aerodrome responding emergency agencies;
7. floodlighting on a designated isolated aircraft parking position if provided in accordance with 13.5.3.24.1; and
8. illumination of apron areas over which passengers may walk.

Note. — *Specifications for secondary power supply for radio navigation aids and ground elements of communications systems are given in Liberia Civil Aviation (ANS) Regulations.*

- (vi) Requirements for a secondary power supply shall be met by either of the following:

1. independent public power, which is a source of power supplying the aerodrome service from a substation other than the normal substation through a transmission line following a route different from the normal power supply route and such that the possibility of a simultaneous failure of the normal and independent public power supplies is extremely remote; or
2. standby power unit(s), which are engine generators, batteries, etc., from which electric power can be obtained.

Note. — *Guidance on electrical systems is included in the Aerodrome Design*

Manual (Doc 9157), Part 5

Table 13.1.8-1. Secondary power supply requirements
(see 13.1.8.1(d))

Runway	Lighting aids requiring power	Maximum switch-over time
Non-instrument	Visual approach slope indicators ^a	See
	Runway edge ^b	8.1.4 and
	Runway threshold ^b	13.1.8.1(d) and
	Runway end ^b	13.1.8.1(f)(1)(iv)
	Obstacle ^a	13.1.8.1(f)(1)(iv)
Non-precision approach	Approach lighting system	15 seconds
	Visual approach slope indicators ^{a, d}	15 seconds
	Runway edge ^d	15 seconds
	Runway threshold ^d	15 seconds
	Runway end	15 seconds
	Obstacle ^a	15 seconds
Precision approach category I	Approach lighting system	15 seconds
	Runway edge ^d	15 seconds
	Visual approach slope indicators ^{a, d}	15 seconds
	Runway threshold ^d	15 seconds
	Runway end	15 seconds
	Essential taxiway ^a	15 seconds
	Obstacle ^a	15 seconds
Precision approach category II/III	Inner 300 m of the approach lighting system	1 second
	Other parts of the approach lighting system	15 seconds
	Obstacle ^a	15 seconds
	Runway edge	15 seconds
	Runway threshold	1 second
	Runway end	1 second
	Runway centre line	1 second
	Runway touchdown zone	1 second
	All stop bars	1 second
	Essential taxiway	15 seconds
Runway meant for take-off in runway visual range conditions less than a value of 800 m	Runway edge	15 seconds ^f
	Runway end	1 second
	Runway centre line	1 second
	All stop bars	1 second
	Essential taxiway ^a	15 seconds
	Obstacle ^a	15 seconds

- (a) Supplied with secondary power when their operation is essential to the safety of flight operation.
- (b) See Section 13.1.5, paragraph 13.1. 5.3.(b), regarding the use of emergency lighting.
- (c) One second where no runway center line lights are provided.
- (d) One second where approaches are over hazardous or precipitous terrain.

13.1.8.2 **System Design**

- (a) For a runway meant for use in runway visual range conditions less than a value of 550 m, the electrical systems for the power supply, lighting and control of the lighting systems included in Table 8-1 shall be so designed that an equipment failure will not leave the pilot with inadequate visual guidance or misleading information.

Note. — Guidance on means of providing this protection is given in the Aerodrome Design Manual (Doc 9157), Part 5.

- (b) Where the secondary power supply of an aerodrome is provided by the use of duplicate feeders, such supplies shall be physically and electrically separate so as to ensure the required level of availability and independence.
- (c) Where a runway forming part of a standard taxi-route is provided with runway lighting and taxiway lighting, the lighting systems shall be interlocked to preclude the possibility of simultaneous operation of both forms of lighting.

13.1.8.3 **Monitoring**

- (a) A system of monitoring shall be employed to indicate the operational status of the lighting systems.

Note. — Guidance on this subject is given in the Aerodrome Design Manual (Doc 9157), Part 5.

- (b) Where lighting systems are used for aircraft control purposes, such systems shall be monitored automatically so as to provide an indication of any fault which may affect the control functions. This information shall be automatically relayed to the air traffic services unit.
- (c) Where a change in the operational status of lights has occurred, an indication shall be provided within two seconds for a stop bar at a runway-holding position and within five seconds for all other types of visual aids.
- (d) For a runway meant for use in runway visual range conditions less than a value of 550 m, the lighting systems detailed in Table 8-1 shall be monitored automatically so as to provide an indication when the serviceability level of any element falls below the minimum serviceability level specified in 13.1.10.5 (c)(7) to 13.1.10.5 (c)(11), as appropriate. This information shall be automatically relayed to the maintenance crew.

- (e) For a runway meant for use in runway visual range conditions less than a value of 550 m, the lighting systems detailed in Table 13.1.8-1 shall be monitored automatically to provide an indication when the serviceability level of any element falls below the minimum level specified by the appropriate authority below which operations shall not continue. This information shall be automatically relayed to the air traffic services unit and displayed in a prominent position.

Note. — Guidance on air traffic control interface and visual aids monitoring is included in the Aerodrome Design Manual (Doc 9157), Part 5.

13.1.9 AERODROME OPERATIONAL SERVICES, EQUIPMENT AND INSTALLATIONS

13.1.9.1 Aerodrome Emergency Planning

(a) General

Introductory Note.— Aerodrome emergency planning is the process of preparing an aerodrome to cope with an emergency occurring at the aerodrome or in its vicinity. The objective of aerodrome emergency planning is to minimize the effects of an emergency, particularly in respect of saving lives and maintaining aircraft operations. The aerodrome emergency plan sets forth the procedures for coordinating the response of different aerodrome agencies (or services) and of those agencies in the surrounding community that could be of assistance in responding to the emergency. Guidance material to assist the appropriate authority in establishing aerodrome emergency planning is given in the Airport Services Manual (Doc 9137), Part 7.

- (1) The Aerodrome Operator shall establish an aerodrome emergency plan at an aerodrome, commensurate with the aircraft operations and other activities conducted at the aerodrome.
- (2) The aerodrome emergency plan shall provide for the coordination of the actions to be taken in an emergency occurring at an aerodrome or in its vicinity.

Note 1. — Examples of emergencies are: aircraft emergencies, sabotage including bomb threats, unlawfully seized aircraft, dangerous goods occurrences, building fires, natural disaster and public health emergencies.

Note 2. — Examples of public health emergencies are increased risk of travelers or cargo spreading a serious communicable disease internationally through air transport and severe outbreak of a communicable disease potentially affecting a large proportion of aerodrome staff.

- (3) The plan shall coordinate the response or participation of all existing agencies which, in the opinion of the appropriate authority, could be of assistance in responding to an emergency.

Note 1.— Examples of agencies are:

— on the aerodrome: air traffic control units, rescue and firefighting services, aerodrome administration, medical and ambulance services, aircraft operators, security services, and police;

— off the aerodrome: fire departments, police, health authorities (including medical, ambulance, hospital and public health services), military, and harbor patrol or coast guard.

Note 2.— Public health services include planning to minimize adverse effects to the community from health-related events and deal with population health issues rather than provision of health services to individuals.

Note 2. — Public health services include planning to minimize adverse effects to the community from health-related events and deal with population health issues rather than provision of health services to individuals.

- (4) The plan shall provide for cooperation and coordination with the rescue coordination center, as necessary.
- (5) The aerodrome emergency plan document shall include at least the following:

- (i) types of emergencies planned for;
 - (ii) agencies involved in the plan;
 - (iii) responsibility and role of each agency, the emergency operations center and the command post, for each type of emergency;
 - (iv) information on names and telephone numbers of offices or people to be contacted in the case of a particular emergency; and
 - (v) a grid map of the aerodrome and its immediate vicinity.
- (6) The plan shall observe Human Factors principles to ensure optimum response by all existing agencies participating in emergency operations.

Note 1 — Guidance material on Human Factors principles can be found in the Human Factors Training Manual (Doc 9683).

Note 2.— General principles and procedures on the training of aerodrome personnel, including training programmes and competence checks, are specified in the PAN-Aerodromes (Doc 9981)

(b) Emergency Operations Center And Command Post

- (1) The Aerodrome Operator shall ensure that a fixed emergency operations center and a mobile command post shall be available for use during an emergency.
- (2) The emergency operations center shall be a part of the aerodrome facilities and shall be responsible for the overall coordination and general direction of the response to an emergency.
- (3) The command post shall be a facility capable of being moved rapidly to the site of an emergency, when required, and shall undertake the local coordination of those agencies responding to the emergency.
- (4) The Aerodrome Operator shall ensure that a person is assigned to assume control of the emergency operations center and, when appropriate, another person at the command post.

(c) Communication System

- (1) Adequate communication systems linking the command post and the emergency operations center with each other and with the participating agencies shall be provided in accordance with the plan and consistent with the particular requirements of the aerodrome.

(d) Aerodrome Emergency Exercise

- (1) The plan shall contain procedures for periodic testing of the adequacy of the plan and for reviewing the results in order to improve its effectiveness.

Note. — The plan includes all participating agencies and associated equipment.

- (2) The plan shall be tested by conducting:
 - (i) a full-scale aerodrome emergency exercise at intervals not exceeding two years and partial emergency exercises in the intervening year to ensure that any deficiencies found during the full-scale aerodrome emergency exercise have been corrected; or
 - (ii) a series of modular tests commencing in the first year and concluding in a full-scale aerodrome emergency exercise at intervals not exceeding three years; and reviewed thereafter, or after an actual emergency, so as to correct any deficiency found during such exercises or actual emergency.

Note 1. — The purpose of a full-scale exercise is to ensure the adequacy of the plan to cope with different types of emergencies. The purpose of a partial exercise is to ensure the adequacy of the response to individual participating agencies and components of the plan, such as the communications system. The purpose of modular tests is to enable concentrated effort on specific components of established emergency plans.

Note 2. — Guidance material on airport emergency planning is available in the Airport Services Manual (Doc 9137), Part 7

(e) Emergencies In Difficult Environments

- (1) The plan shall include the ready availability of, and coordination with, appropriate specialist rescue services to be able to respond to emergencies where an aerodrome is located close to water and/or swampy areas and where a significant portion of approach or departure operations takes place over these areas.
- (2) At those aerodromes located close to water and/or swampy areas, or difficult terrain, the aerodrome emergency plan shall include the establishment, testing and assessment at regular intervals of a predetermined response for the specialist rescue services.
- (3) An assessment of the approach and departure areas within 1 000 m of the runway threshold shall be carried out to determine the options available for intervention.

Note. — Guidance material on assessing approach and departure areas within 1 000 m of runway thresholds can be found in Chapter 13 of the Airport Services Manual (Doc 9137), Part 1.

13.1.9.2 Rescue and Firefighting

(a) General

(1) Application

- (i) The Aerodrome Operator shall ensure that Rescue and firefighting equipment and services are provided at an aerodrome.
- (ii) Where an aerodrome is located close to water/swampy areas, or difficult terrain, and where a significant portion of approach or departure operations takes place over these areas, specialist rescue services and firefighting equipment appropriate to the hazard and risk shall be available.

Note 1. — Special firefighting equipment need not be provided for water areas; this does not prevent the provision of such equipment if it would be of practical use, such as when the areas concerned include reefs or islands.

Note 2. — The objective is to plan and deploy the necessary life-saving flotation equipment as expeditiously as possible in a number commensurate with the largest aeroplane normally using the aerodrome.

Note 3 – Additional Standards which aerodrome operators shall comply with are available in Liberia Rescue and Fire Fighting Manual RFFM-AGA006

Note 4. — Additional guidance is available in Chapter 13 of the Airport Services Manual (Doc 9137), Part 1.

(b) Level of protection to be provided

- (1) The level of protection provided at an aerodrome for rescue and firefighting shall be appropriate to the aerodrome category determined using the principles in 13.1.9 (b)(3) and 13.1.9 (b)(4), except that, where the number of movements of the aeroplanes in the highest category normally using the aerodrome is less than 700 in the busiest consecutive three months, the level of protection provided shall be not less than one category below the determined category.

Note. — Either a take-off or a landing constitutes a movement.

- (2) The level of protection provided at an aerodrome for rescue and firefighting shall be equal to the aerodrome category determined using the principles in (3) and(4).
- (3) The aerodrome category shall be determined from Table 13.1.9-1 and shall be based on the longest aeroplanes normally using the aerodrome and their fuselage width.

Note. — To categorize the aeroplanes using the aerodrome, first evaluate their overall length and second, their fuselage width.

- (4) If, after selecting the category appropriate to the longest aeroplane's overall length, that aeroplane's fuselage width is greater than the maximum width in Table 13.1.9-1, column 3, for that category, then the category for that aeroplane shall actually be one category higher.

Note 1. — See guidance in the Airport Services Manual (Doc 9137), Part 1, for categorizing aerodromes, including those for all-cargo aircraft operations, for rescue and firefighting purposes.

Note 2. — Principles and Procedures on training including training programmes and competence checks, are specified in PAN-Aerodromes (Doc 9981). Further guidance on training of personnel, rescue equipment for difficult environments and other facilities and services for rescue and firefighting is given in Attachment A, Section 18, and in the Airport Services Manual (Doc 9137), Part 1.

- (5) During anticipated periods of reduced activity, the level of protection available shall be no less than that needed for the highest category of aeroplane planned
- (6) to use the aerodrome during that time irrespective of the number of movements.

Table 13.1.9-1. Aerodrome category for rescue and firefighting

Aerodrome category (1)	Aeroplane overall length (2)	Maximum fuselage width (3)
1	0 m up to but not including 9 m	2 m
2	9 m up to but not including 12 m	2 m
3	12 m up to but not including 18 m	3 m
4	18 m up to but not including 24 m	4 m
5	24 m up to but not including 28 m	4 m
6	28 m up to but not including 39 m	5 m
7	39 m up to but not including 49 m	5 m
8	49 m up to but not including 61 m	7 m
9	61 m up to but not including 76 m	7 m
10	76 m up to but not including 90 m	8 m

(c) Extinguishing agents

(1) Both principal and complementary agents shall normally be provided at an aerodrome.

Note. — Descriptions of the agents may be found in the Airport Services Manual (Doc 9137), Part 1.

- (2) The principal extinguishing agent shall be:
- (i) a foam meeting the minimum performance level A; or
 - (ii) a foam meeting the minimum performance level B; or
 - (iii) a foam meeting the minimum performance level C; or
 - (iv) a combination of these agents

except that the principal extinguishing agent for aerodromes in categories 1 to 3 shall preferably meet a performance level B or C foam.

Note. — Information on the required physical properties and fire extinguishing performance criteria needed for a foam to achieve an acceptable performance level A, B or C rating is given in the Airport Services Manual (Doc 9137), Part 1.

(3) The complementary extinguishing agent shall be a dry chemical powder suitable for extinguishing hydro carbon fires.

Note 1. — When selecting dry chemical powders for use with foam, care must be exercised to ensure compatibility.

Note 2. — Alternate complementary agents having equivalent firefighting capability may be utilized. Additional information on extinguishing agents is given in the Airport Services Manual (Doc 9137), Part 1.

(4) The amounts of water for foam production and the complementary agents to be provided on the rescue and firefighting vehicles shall be in accordance with the aerodrome category determined under 13.1.9(b)(1), 13.1.9(b)(2), 13.1.9(b)(3), 13.1.9(b)(4) and Table 13.1.9-2, except that for aerodrome categories 1 and 2 up to 100 per cent of the water may be substituted with complementary agent. For the purpose of agent substitution, 1 kg of complementary agent shall be

taken as equivalent to 1.0 L of water for production of a foam meeting performance level A.

Note 1. — The amounts of water specified for foam production are predicated on an application rate of 8.2 L/min/m² for a foam meeting performance level A, 5.5 L/min/m² for a foam meeting performance level B and 3.75 L/min/m² for a foam meeting performance level C.

Note 2. — When any other complementary agent is used, the substitution ratios need to be checked.

- (5) At aerodromes where operations by aeroplanes larger than the average size in a given category are planned, the quantities of water shall be recalculated and the amount of water for foam production and the discharge rates for foam solution shall be increased accordingly.

Note. — Guidance on the determination of quantities of water and discharge rates based on the largest theoretical aeroplane in a given category is available in Chapter 2 of the Airport Services Manual (Doc 9137), Part 1.

- (6) At aerodromes where operations by aeroplanes larger than the average size in a given category are planned, the quantities of water shall be recalculated and the amount of water for foam production and the discharge rates for foam solution shall be increased accordingly.

Note. — Guidance on the determination of quantities of water and discharge rates based on the largest overall length of aeroplane in a given category is available in Chapter 2 of the Airport Services Manual (Doc 9137), Part 1.

Table 13.1.9-2: Minimum usable amounts of extinguishing agents

Aerodrome category	Foam meeting performance level A		Foam meeting performance level B		Foam meeting performance level C		Complementary agents	
	Water (L)	Discharge rate foam solution/minute	Water (L)	Discharge rate foam solution/minute	Water (L)	Discharge rate foam solution/minute	Dry chemical powders (kg)	Discharge Rate (kg/second)
		(L)		(L)		(L)		
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
1	350	350	230	230	160	160	45	2.25
2	1 000	800	670	550	460	360	90	2.25
3	1 800	1 300	1 200	900	820	630	135	2.25
4	3 600	2 600	2 400	1 800	1 700	1 100	135	2.25
5	8 100	4 500	5 400	3 000	3 900	2 200	180	2.25
6	11 800	6 000	7 900	4 000	5 800	2 900	225	2.25
7	18 200	7 900	12 100	5 300	8 800	3 800	225	2.25
8	27 300	10 800	18 200	7 200	12 800	5 100	450	4.5
9	36 400	13 500	24 300	9 000	17 100	6 300	450	4.5
10	48 200	16 600	32 300	11 200	22 800	7 900	450	4.5

Note.— The quantities of water shown in columns 2, 4 and 6 are based on the average overall length of aeroplanes in a given category.

- (7) The quantity of foam concentrates separately provided on vehicles for foam production shall be in proportion to the quantity of water provided and the foam concentrate selected.

- (8) The amount of foam concentrate provided on a vehicle shall be sufficient to produce at least two loads of foam solution.
- (9) Supplementary water supplies, for the expeditious replenishment of rescue and firefighting vehicles at the scene of an aircraft accident, shall be provided.
- (10) When a combination of different performance level foams are provided at an aerodrome, the total amount of water to be provided for foam production shall be calculated for each foam type and the distribution of these quantities shall be documented for each vehicle and applied to the overall rescue and firefighting requirement.
- (11) The discharge rate of the foam solution shall not be less than the rates shown in Table 13.1.9- 2.
- (12) The complementary agents shall comply with the appropriate specifications of the International Organization for Standardization(ISO).*
- (13) The discharge rate of complementary agents shall be no less than the values shown in Table 13.1.9-2.
- (14) Dry chemical powders shall only be substituted with an agent that has equivalent or better firefighting capabilities for all types of fires where complementary agent is expected to be used.

Note. — Guidance on the use of complementary agents can be found in the Airport Services Manual (Doc 9137), Part 1.

- (15) A reserve supply of foam concentrate, equivalent to 200 per cent of the quantities identified in Table 13.1.9-2, shall be maintained on the aerodrome for vehicle replenishment purposes.

Note. — Foam concentrate carried on fire vehicles in excess of the quantity identified in Table 13.1.9-2 can contribute to the reserve.

- (16) A reserve supply of complementary agent, equivalent to 100 per cent of the quantity identified in Table 13.1.9-2, shall be maintained on the aerodrome for vehicle replenishment purposes. Sufficient propellant gas shall be included to utilize this reserve complementary agent.
- (17) Category 1 and 2 aerodromes that have replaced up to 100 per cent of the water with complementary agent shall hold a reserve supply of complementary agent of 200 per cent.
- (18) Where a major delay in the replenishment of the supplies is anticipated, the amount of reserve supply in 13.1.9.2 (c)(15), 13.1.9.2 (c)(16) and 13.1.9.2 (c)(17) shall be increased as determined by a risk assessment.

Note. — See the Airport Services Manual (Doc 9137), Part 1 for guidance on the conduct of a risk analysis to determine the quantities of reserve extinguishing agents.

(d) Rescue equipment

- (1) Rescue equipment commensurate with the level of aircraft operations shall be provided on the rescue and firefighting vehicle(s).* See ISO Publication 7202(Powder).

Note. — Guidance on the rescue equipment to be provided at an aerodrome is given in the Airport Services Manual (Doc 9137), Part 1.

(e) Response time

- (1) The operational objective of the rescue and firefighting service shall be to achieve a response time not exceeding two minutes to any point of each operational runway, in optimum visibility and surface conditions.
- (2) The operational objective of the rescue and firefighting service shall be to achieve a response time not exceeding two minutes to any other part of the movement area, in optimum visibility and surface conditions.

Note 1. — Response time is considered to be the time between the initial call to the rescue and firefighting service, and the time when the first responding vehicle(s) is (are) in position to apply foam at a rate of at least 50 per cent of the discharge rate specified in Table 13.1.9-2.

(f) Emergency access roads

- (1) Emergency access roads shall be provided on an aerodrome where terrain conditions permit their construction, so as to facilitate achieving minimum response times. Particular attention shall be given to the provision of ready access to approach areas up to 1 000 m from the threshold, or at least within

the aerodrome boundary. Where a fence is provided, the need for convenient access to outside areas should be taken into account.

Note. — Aerodrome service roads may serve as emergency access roads when they are suitably located and constructed.

- (2) Emergency access roads shall be capable of supporting the heaviest vehicles, which will use them, and be usable in all weather conditions. Roads within 90 m of a runway shall be surfaced to prevent surface erosion and the transfer of debris to the runway. Sufficient vertical clearance shall be provided from overhead obstructions for the largest vehicles.
- (3) When the surface of the road is indistinguishable from the surrounding area of the roads, edge markers shall be placed at intervals of about 10m.

(g) Fire stations

- (1) All rescue and firefighting vehicles shall normally be housed in a fire station. Satellite fire stations shall be provided whenever the response time cannot be achieved from a single fire station.
- (2) The fire station shall be located so that the access for rescue and firefighting vehicles into the runway area is direct and clear, requiring a minimum number of turns.

(h) Communication and alerting systems

- (1) A discrete communication system shall be provided linking a fire station with the control tower, any other fire station on the aerodrome and the rescue and fire fighting vehicles.
- (2) An alerting system for rescue and firefighting personnel, capable of being operated from that station, shall be provided at a fire station, any other fire station on the aerodrome and the aerodrome control tower.

(i) Number of rescue and firefighting vehicles

- (1) The minimum number of rescue and firefighting vehicles provided at an aerodrome shall be in accordance with the following tabulation:

Aerodrome category	Rescue and firefighting vehicles
1	1
2	1
3	1
4	1
5	1
6	2
7	2
8	3
9	3
10	3

Note. — Guidance on minimum characteristics of rescue and firefighting vehicles is given in the Airport Services Manual (Doc 9137), Part 1

(j) Personnel

- (1) All rescue and firefighting personnel shall be properly trained to perform their duties in an efficient manner and shall participate in live fire drills commensurate with the types of aircraft and type of rescue and firefighting equipment in use at the aerodrome, including pressure-fed fuel fires.

Note 1 — Guidance to assist the aerodrome operator in providing proper training is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 19; ICAO Airport Services Manual (Doc 9137), Part 1; and ICAO Training Manual, Part E-2

Note 2. — Fires associated with fuel discharged under very high pressure from a ruptured fuel tank are known as “pressure-fed fuel fires”.

- (2) The rescue and firefighting personnel training program shall include training in human performance, including team coordination.

Note. — Guidance material to design training programs on human performance and team coordination can be found in the Human Factors Training Manual (Doc 9683).

- (3) During flight operations, sufficient trained and competent personnel shall be designated to be readily available to ride the rescue and firefighting vehicles and to operate the equipment at maximum capacity. These personnel shall be deployed in a way that ensures that minimum response times can be achieved and that continuous agent application at the appropriate rate can be fully maintained. Consideration shall also be given for personnel to use hand lines, ladders and other

rescue and firefighting equipment normally associated with aircraft rescue and firefighting operations.

- (4) In determining the minimum number of rescue and firefighting personnel required, a task resource analysis shall be completed and the level of staffing documented in the Aerodrome Manual.

Note. — Guidance on the use of a task resource analysis can be found in the Airport Services Manual (Doc 9137), Part 1.

- (5) All responding rescue and firefighting personnel shall be provided with protective clothing and respiratory equipment to enable them to perform their duties in an effective manner.

13.1.9.3 **Disabled Aircraft Removal**

- (a) A plan for the removal of an aircraft disabled on, or adjacent to, the movement area shall be established for an aerodrome, and a coordinator designated to implement the plan, when necessary.

Note. — Guidance on removal of a disabled aircraft, including recovery equipment, is given in the Airport Services Manual (Doc 9137), Part 5. See also Annex 13 — Aircraft Accident and Incident Investigation concerning protection of evidence, custody and removal of aircraft.

- (b) The disabled aircraft removal plan shall be based on the characteristics of the aircraft that may normally be expected to operate at the aerodrome, and include among other things:

- (1) a list of equipment and personnel on, or in the vicinity of, the aerodrome which would be available for such purpose; and
- (2) arrangements for the rapid receipt of aircraft recovery equipment kits available from other aerodromes.

13.1.9.4 **Wildlife Strike Hazard Reduction**

Note.—The presence of wildlife (birds and animals) on and in the aerodrome vicinity poses a serious threat to aircraft operational safety.

- (a) The wildlife strike hazard on, or in the vicinity of, an aerodrome shall be assessed through:

- (1) the establishment of a national procedure for recording and reporting wildlife strikes to aircraft;
- (2) the collection of information from aircraft operators, aerodrome personnel and other sources on the presence of wildlife on or around the aerodrome constituting a potential hazard to aircraft operations; and
- (3) an ongoing evaluation of the wildlife hazard by competent personnel.

Note. — see ICAO annex 15, Chapter 5

- (b) Wildlife strike reports shall be collected by the Authority and forwarded to ICAO for inclusion in the ICAO Bird Strike Information System (IBIS) database.

Note. — The IBIS is designed to collect and disseminate information on wildlife strikes to aircraft. Information on the system is included in the Manual on the ICAO Bird Strike Information System (IBIS) (Doc 9332).

- (c) Action shall be taken to decrease the risk to aircraft operations by adopting measures to minimize the likelihood of collisions between wildlife and aircraft.

Note.— Procedures for the management of wildlife hazards on and within the vicinity of aerodromes, including the establishment of a wildlife hazard management programme (WHMP), wildlife risk assessment, land-use management and personnel training, are specified in the PANS-Aerodromes (Doc 9981), Part II, Chapters 1 and 6. Further guidance is given in the Airport Services Manual (Doc 9137), Part 3.

- (d) Appropriate measures shall be put in place to eliminate or to prevent the establishment of garbage disposal dumps or any other source which may attract wildlife to the aerodrome, or its vicinity, unless an appropriate wildlife assessment indicates that they are unlikely to create conditions conducive to a wildlife hazard problem. Where the elimination of existing sites are not possible, the measure shall ensure that any risk to aircraft posed by these sites is assessed and reduced to as low as reasonably practicable.
- (e) The Authority shall give due consideration to aviation safety concerns related to land developments in the vicinity of the aerodrome that may attract wildlife.

13.1.9.5 **Apron Management Service**

- (a) When warranted by the volume of traffic and operating conditions, an appropriate apron management service shall be provided on an apron by an aerodrome ATS unit, by another Aerodrome Operator, or by a cooperative combination of these, in order to:
- (1) regulate movement with the objective of preventing collisions between aircraft, and between aircraft and obstacles;
 - (2) regulate entry of aircraft into, and coordinate exit of aircraft from, the apron with the aerodrome control tower; and
 - (3) ensure safe and expeditious movement of vehicles and appropriate directive of other activities.
- (b) When the aerodrome control tower does not participate in the apron management service, procedures shall be established to facilitate the orderly transition of aircraft between the apron management unit and the aerodrome control tower.

Note. — Guidance on an apron management service is given in the Airport Services Manual (Doc 9137), Part 8, and in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476).

- (c) An apron management service shall be provided with radiotelephony communications facilities.
- (d) Where low visibility procedures are in effect, persons and vehicles operating on an apron shall be restricted to the essential minimum.

Note. — Procedures on apron safety are specified in the PANS-Aerodromes (Doc 9981). Guidance on related special procedures is given in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476).

- (e) An emergency vehicle responding to an emergency shall be given priority over all other surface movement traffic.
- (f) A vehicle operating on an apron shall:
 - (1) give way to an emergency vehicle; an aircraft taxiing, about to taxi, or being pushed or towed; and
 - (2) give way to other vehicles in accordance with local Directives.
- (g) An aircraft stand shall be visually monitored to ensure that the recommended clearance distances are provided to an aircraft using the stand.

Note.— Procedures on the training of operational personnel and on apron safety and operations, are specified in the PANS-Aerodromes (Doc 9981), Part II, Chapters 1 and 7.

13.1.9.6 **Ground Servicing Of Aircraft**

- (a) The Aerodrome Operator shall ensure that fire extinguishing equipment suitable for at least initial intervention in the event of a fuel fire and personnel trained in its use, shall be readily available during the ground servicing of an aircraft, and there shall be a means of quickly summoning the rescue and firefighting service in the event of a fire or major fuel spill.
- (b) When aircraft refueling operations take place while passengers are embarking, on board or disembarking, ground equipment shall be positioned so as to allow:
 - (1) the use of a sufficient number of exits for expeditious evacuation; and
 - (2) a ready escape route from each of the exits to be used in an emergency.

13.1.9.7 **Aerodrome Vehicle Operations**

Note 1.— Procedures on the establishment of an airside driver permit (ADP) scheme and vehicle/equipment safety requirements, including detailed personnel training, are specified in the PANS-Aerodromes (Doc 9981), Part II, Chapter 9.

Note 2 — Guidance on aerodrome vehicle operations is contained in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005), Section 20 and on traffic rules and regulations for vehicles is contained in the ICAO Manual of Surface Movement Guidance and Control Systems (SMGCS)(Doc 9476).

Note 3 — It is intended that roads located on the movement area be restricted to the exclusive use of aerodrome personnel and other authorised persons, and that access to the public buildings by an unauthorised person will not require use of such roads.

Note 4 — The Airport Traffic Directives XCAA-ATD-AGA013 issued by the Authority contains rules and regulations to be complied with by persons who have the need to drive a vehicle on the movement areas

- (a) A vehicle shall be operated:
 - (1) on a maneuvering area only as authorized by the aerodrome control tower; and

- (2) on an apron only as authorized by the appropriate designated authority.

Note 1. — Guidance on aerodrome vehicle operations is contained in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476)

Note 2. — It is intended that roads located on the movement area be restricted to the Exclusive use of aerodrome personnel and other authorized persons, and that access to the public buildings by an unauthorized person will not require use of such roads.

- (b) The driver of a vehicle on the movement area shall comply with all mandatory instructions conveyed by markings and signs unless otherwise authorized by:
- (1) the aerodrome control tower when on the maneuvering area; or
 - (2) the appropriate designated authority when on the apron.
- (c) The driver of a vehicle on the movement area shall comply with all mandatory instructions conveyed by lights.
- (d) The driver of a vehicle on the movement area shall be appropriately trained for the tasks to be performed and shall comply with the instructions issued by:
- (1) the aerodrome control tower, when on the maneuvering area; and
 - (2) the appropriate designated authority, when on the apron.
- (e) The driver of a radio-equipped vehicle shall establish satisfactory two-way radio communication with the aerodrome control tower before entering the maneuvering area and with the appropriate designated authority before entering the apron. The driver shall maintain a continuous listening watch on the assigned frequency when on the movement area.

13.1.9.8 **Surface Movement Guidance and Control Systems**

- (a) **Application.** The Aerodrome Operator shall provide a surface movement guidance and control system (SMGCS) shall be provided at an aerodrome.

Note. — Guidance on surface movement guidance and control systems is contained in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476).

(b) **Characteristics**

- (1) The design of an SMGCS shall take into account:
 - (i) the density of air traffic;
 - (ii) the visibility conditions under which operations are intended;
 - (iii) the need for pilot orientation;
 - (iv) the complexity of the aerodrome layout; and
 - (v) movements of vehicles.

- (2) The visual aid components of an SMGCS, i.e. markings, lights and signs, shall be designed to conform with the relevant specifications in 13.1.5.2, 13.1.5.3 and 13.1.5.4, respectively.
- (3) An SMGCS shall be designed to assist in the prevention of inadvertent incursions of aircraft and vehicles onto an active runway.
- (4) The system shall be designed to assist in the prevention of collisions between aircraft, and between aircraft and vehicles or objects, on any part of the movement area.

Note. — Guidance on control of stop bars through induction loops and on a visual taxiing guidance and control system is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

- (5) Where an SMGCS is provided by selective switching of stop bars and taxiway center line lights, the following requirements shall be met:
 - (i) taxiway routes which are indicated by illuminated taxiway center line lights shall be capable of being terminated by an illuminated stopbar;
 - (ii) the control circuits shall be so arranged that when a stop bar located ahead of an aircraft is illuminated, the appropriate section of taxiway center line lights beyond it is suppressed; and
 - (iii) the taxiway center line lights are activated ahead of an aircraft when the stop bar is suppressed.

Note 1. — See Sections **13.5.3.17** and **13.5.3.20** for specifications on taxiway center line lights and stop bars, respectively.

Note 2. — Guidance on installation of stop bars and taxiway center line lights in SMGCSs is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- (6) Surface movement radar for the maneuvering area shall be provided at an aerodrome intended for use in runway visual range conditions less than a value of 350m.
- (7) Surface movement radar for the maneuvering area shall be provided at an aerodrome other than that in **13.9.8.7** when traffic density and operating conditions are such that regularity of traffic flow cannot be maintained by alternative procedures and facilities.

Note. - Guidance on the use of surface movement radar is given in the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476) and in the Air Traffic Services Planning Manual (Doc 9426).

13.1.9.9 **Siting Of Equipment and Installations On Operational Areas**

- (a) Unless its function requires it to be there for air navigation or for aircraft safety purposes, no equipment or installation shall be:
 - (1) on a runway strip, a runway end safety area, a taxiway strip or within the distances specified in Table 13.1.3-1, column 11, if it would endanger an aircraft; or

- (2) on a clearway if it would endanger an aircraft in the air.

Note 1. — Requirements for obstacle limitation surfaces are specified in 13.1.4.2.

Note 2. — The design of light fixtures and their supporting structures, light units of visual approach slope indicators, signs, and markers, is specified in 13.5.3.1, 13.5.3.5, 13.5.4.1 and 5.5.1, respectively. Guidance on the frangible design of visual and non-visual aids for navigation is given in the Aerodrome Design Manual (Doc 9157), Part 6.

- (b)** Any equipment or installation required for air navigation or for aircraft safety purposes which must be located:

- (1) on that portion of a runway strip within:

- (i) 75m of the runway centerline where the code number is 3 or 4;or
- (ii) 45m of the runway centerline where the code number is 1 or 2;or
- (iii) on a runway end safety area, a taxiway strip or within the distances specified in Table 13.1.3-1;

- (2) on a clearway and which would endanger an aircraft in the air; shall be frangible and mounted as low as possible.

- (c)** Any equipment or installation required for air navigation or for aircraft safety purposes which must be located on the non-graded portion of a runway strip shall be regarded as an obstacle and shall be frangible and mounted as low as possible.

Note. — Guidance on the siting of navigation aids is contained in the Aerodrome Design Manual (Doc 9157), Part 6.

- (d)** Unless its function requires it to be there for air navigation or for aircraft safety purposes, no equipment or installation shall be located within 240 m from the end of the strip and within:

- (1) 60 m of the extended center line where the code number is 3 or 4;or
- (2) 45 m of the extended center line where the code number is 1 or 2; of a precision approach runway category I, II or III.

- (e)** Any equipment or installation required for air navigation or for aircraft safety purposes which must be located on or near a strip of a precision approach runway category I, II or III and which:

- (1) is situated within 240 m from the end of the strip and within:

- (i) 60m of the extended runway centerline where the code number is 3 or 4;or
- (ii) 45m of the extended runway centerline where the code number is 1 or 2;or

- (2) penetrates the inner approach surface, the inner transitional surface or the balked landing surface; shall be frangible and mounted as low as possible.

- (f) Any equipment or installation required for air navigation or for aircraft safety purposes which is an obstacle of operational significance in accordance with 13.4.2.4, 13.4.2.11, 13.4.2.20 or 13.4.2.27 shall be frangible and mounted as low as possible.

13.1.9.10 **Fencing**

(a) **Application**

- (1) The Aerodrome Operator shall ensure that a fence or other suitable barrier shall be provided on an aerodrome to prevent the entrance to the movement area of animals large enough to be a hazard to aircraft.
- (2) A fence or other suitable barrier shall be provided on an aerodrome to deter the inadvertent or premeditated access of an unauthorized person onto a non-public area of the aerodrome.

Note 1. — This is intended to include the barring of sewers, ducts, tunnels, etc., where necessary to prevent access.

Note 2. — Special measures may be required to prevent the access of an unauthorized person to runways or taxiways which overpass public roads

- (3) Suitable means of protection shall be provided to deter the inadvertent or premeditated access of unauthorized persons into ground installations and facilities essential for the safety of civil aviation located off the aerodrome.

(b) **Location**

- (1) The fence or barrier shall be located so as to separate the movement area and other facilities or zones on the aerodrome vital to the safe operation of aircraft from areas open to public access.
- (2) Where the Authority deems it necessary following a security risk assessment, a cleared area shall be provided on both sides of the fence or barrier to facilitate the work of patrols and to make trespassing more difficult. Consideration shall be given to the provision of a perimeter road inside the aerodrome fencing for the use of both maintenance personnel and security patrols.

13.1.9.11 **Security Lighting**

- (a) At an aerodrome where it is deemed desirable for security reasons, a fence or other barrier provided for the protection of international civil aviation and its facilities shall be illuminated at a minimum essential level. Consideration shall be given to locating lights so that the ground area on both sides of the fence or barrier, particularly at access points, is illuminated.

13.1.9.12 **Autonomous Runway Incursion Warning System**

Note 1.— The inclusion of detailed specifications for an autonomous runway incursion warning system (ARIWS) in this section is not intended to imply that an ARIWS has to be provided at an aerodrome.

Note 2.— The implementation of an ARIWS is a complex issue deserving careful consideration by aerodrome operators, air traffic services and States, and in coordination with the aircraft operators.

Note 3.— Attachment A, Section 21, provides a description of an ARIWS and information on its use.

(b) Characteristics

- (1) Where an ARIWS is installed at an aerodrome:
 - (i) it shall provide autonomous detection of a potential incursion or of the occupancy of an active runway and a direct warning to a flight crew or vehicle operator;
 - (ii) it shall function and be controlled independently of any other visual system on the aerodrome;
 - (iii) its visual aid components, i.e. lights, shall be designed to conform with the relevant specifications in 13.1.5.3; and
 - (iv) failure of part or all of it shall not interfere with normal aerodrome operations. To this end, provision shall be made to allow the ATC unit to partially or entirely shut down the system.

Note 1. — An ARIWS may be installed in conjunction with enhanced taxiway center line markings, stop bars or runway guard lights.

Note 2. — It is intended that the system(s) be operational under all weather conditions, including low visibility.

Note 3. — An ARIWS may share common sensory components of an SMGCS or A-SMGCS, however, it operates independently of either system.

- (2) Where an ARIWS is installed at an aerodrome, information on its characteristics and status shall be provided to the appropriate aeronautical information services for promulgation in the AIP with the description of the aerodrome surface movement guidance and control system and markings as specified in ICAO Annex 15.

Note.— Detailed specifications concerning the AIP are contained in PANS-AIM (Doc 10066).

13.1.10 AERODROME MAINTENANCE

13.1.10.1 General

- (a) A maintenance program, including preventive maintenance where appropriate, shall be established by the Aerodrome Operator at an aerodrome to maintain facilities in a condition which does not impair the safety, regularity or efficiency of air navigation, subject to the approval of the Authority.

Note 1. — Preventive maintenance is programmed maintenance work done in order to prevent a failure or degradation of facilities.

Note 2. — “Facilities” are intended to include such items as pavements, visual aids, fencing, drainage systems, electrical systems and buildings.

- (b) The design and application of the maintenance program shall observe Human Factors principles.

Note 1 — Guidance material on Human Factors principles can be found in the Human Factors Training Manual (Doc 9683) and in the Airport Services Manual (Doc 9137), Part 8. Airport Operational Services

Note 2.— General principles and procedures on the training of aerodrome personnel, including training programmes and competence checks, are specified in the PANS-Aerodromes (Doc 9981).

13.1.10.2 Pavements

- (a) The surfaces of all movement areas including pavements (runways, taxiways and aprons) and adjacent areas shall be inspected and their conditions monitored regularly as part of an aerodrome preventive and corrective maintenance program with the objective of avoiding and eliminating any foreign object debris (FOD) that might cause damage to aircraft or impair the operation of aircraft systems.

Note 1. — See 14.2.9.3 for inspections of movement areas.

Note 2. — Procedures on carrying out daily inspections of the movement area and control of FOD are given in the PANS-Aerodromes (Doc 9981), the Manual of Surface Movement Guidance and Control Systems (SMGCS) (Doc 9476) and the Advanced Surface Movement Guidance and Control Systems (A-SMGCS) Manual (Doc 9830).

Note 3. — Additional guidance on sweeping/cleaning of surfaces is contained in the Airport Services Manual (Doc 9137), Part 9.

Note 4.— Guidance on precautions to be taken in regard to the surface of shoulders is given in Guidance Material “Supplementary Guidance Material to Aerodrome Regulation” (GM-AGA005) Section 10, and the Aerodrome Design Manual (Doc 9157), Part 2

Note 5. — Where the pavement is used by large aircraft or aircraft with tire pressures in the upper categories referred to in 13.2.6.6 c), particular attention should be given to the integrity of light fittings in the pavement and pavement joints.

- (b) The surface of a runway shall be maintained in a condition such as to prevent formation of harmful irregularities.
- (c) A paved runway shall be maintained in a condition so as to provide surface friction characteristics at or above the minimum friction level specified by the Authority.

Note — See *Guidance Material* “*Supplementary Guidance Material to Aerodrome Regulation*” (GM-AGA005) Section 5.

- (d) Runway surface friction characteristics for maintenance purposes shall be periodically measured with a continuous friction measuring device using self-wetting features and documented. The frequency of these measurements shall be sufficient to determine the trend of the surface friction characteristics of the runway.

Note 1— *Guidance on evaluating the friction characteristics of a runway is provided in Guidance Material* “*Supplementary Guidance Material to Aerodrome Regulation*” (GM-AGA005), Section 8 of this Part. *Additional guidance is included in the Guidance Material—(AC Number) and ICAO Airport Services Manual (Doc 9137), Part 2.*

Note 2. — *The objective of 13.10.2.3 to 13.10.2.6 is to ensure that the surface friction characteristics for the entire runway remain at or above a minimum friction level specified by LCAA.*

Note 3.— *Guidance for the determination of the required frequency is provided in Guidance Material* “*Supplementary Guidance Material to Aerodrome Regulation*” (GM-AGA005) Section 8 and in the *Airport Services Manual (Doc 9137), Part 2, Appendix 5.*

- (e) Corrective maintenance action shall be taken to prevent the runway surface friction characteristics for either the entire runway or a portion thereof from falling below a minimum friction level specified by LCAA.

Note. — *A portion of runway in the order of 100 m long may be considered significant for maintenance or reporting action.*

- (f) When there is reason to believe that the drainage characteristics of a runway, or portions thereof, are poor due to slopes or depressions, then the runway surface friction characteristics shall be assessed under natural or simulated conditions that are representative of local rain, and corrective maintenance action shall be taken as necessary.
- (g) When a taxiway is used by turbine-engined aeroplanes, the surface of the taxiway shoulders shall be maintained so as to be free of any loose stones or other objects that could be ingested by the aeroplane engines.

Note. — *Guidance on this subject is given in the Aerodrome Design Manual (Doc 9157) Part 2.*

13.1.10.3 **Removal of Contaminants**

- (a) Standing water, mud, dust, sand, oil, rubber deposits and other contaminants shall be removed from the surface of runways in use as rapidly and completely as possible to minimize accumulation.

Note. — *Guidance on the use of chemicals for aerodrome pavements is given in the Airport Services Manual (Doc 9137), Part 2.*

- (b) Chemicals which may have harmful effects on aircraft or pavements, or chemicals which may have toxic effects on the aerodrome environment, shall not be used.

13.1.10.4 Runway Pavement Overlays

- (a) The longitudinal slope of the temporary ramp, measured with reference to the existing runway surface or previous overlay course, shall be:

- (1) 0.5 to 1.0 per cent for overlays up to and including 5 cm in thickness; and
- (2) not more than 0.5 per cent for overlays more than 5 cm in thickness.

Note. — The following specifications are intended for runway pavement overlay projects when the runway is to be returned temporarily to an operational status before resurfacing is complete. This may necessitate a temporary ramp between the new and old runway surfaces. Guidance on overlaying pavements and assessing their operational status is given in the *Aerodrome Design Manual (Doc 9157), Part 3*.

- (b) Overlaying shall proceed from one end of the runway toward the other end so that based on runway utilization most aircraft operations will experience a down ramp.
- (c) The entire width of the runway shall be overlaid during each work session.
- (d) Before a runway being overlaid is returned to a temporary operational status, a runway center line marking conforming to the specifications in Section 13.5.2.3 shall be provided. Additionally, the location of any temporary threshold shall be identified by a 3.6 m wide transverse stripe.
- (e) The overlay shall be constructed and maintained above the minimum friction level specified in 13.10.2.3.

13.1.10.5 Visual Aids

- (a) A light shall be deemed to be unserviceable when the main beam average intensity is less than 50 per cent of the value specified in the appropriate figure in Appendix 2. For light units where the designed main beam average intensity is above the value shown in Appendix 2, the 50 per cent value shall be related to that design value.
- (b) A system of preventive maintenance of visual aids shall be employed to ensure lighting and marking system reliability.

Note. — Guidance on preventive maintenance of visual aids is given in the *Airport Services Manual (Doc 9137), Part 9*.

- (c) The system of preventive maintenance employed for a precision approach runway category II or III shall include at least the following checks:
- (1) visual inspection and in-field measurement of the intensity, beam spread and orientation of lights included in the approach and runway lighting systems;
 - (2) control and measurement of the electrical characteristics of each circuitry included in the approach and runway lighting systems; and
 - (3) control of the correct functioning of light intensity settings used by air traffic control.
 - (4) In-field measurement of intensity, beam spread and orientation of lights included in approach and runway lighting systems for a precision approach runway category II or III shall be undertaken by measuring all lights, as far as practicable, to ensure conformance with the applicable specification of Appendix 2.

- (5) Measurement of intensity, beam spread and orientation of lights included in approach and runway lighting systems for a precision approach runway category II or III shall be undertaken using a mobile measuring unit of sufficient accuracy to analyze the characteristics of the individual lights.
- (6) The frequency of measurement of lights for a precision approach runway category II or III shall be based on traffic density, the local pollution level, the reliability of the installed lighting equipment and the continuous assessment of the results of the in-field measurements but, in any event, shall not be less than twice a year for in-pavement lights and not less than once a year for other lights.
- (7) The system of preventive maintenance employed for a precision approach runway category II or III shall have as its objective that, during any period of category II or III operations, all approach and runway lights are serviceable and that, in any event, at least:
 - (i) no more than two lights will remain unserviceable; and
 - (ii) two adjacent lights will not remain unserviceable unless the light spacing is significantly less than that specified.
- (8) The system of preventive maintenance employed for a taxiway intended for use in runway visual range conditions less than a value of 350 m shall have as its objective that no two adjacent taxiway center line lights be unserviceable.
- (9) The system of preventive maintenance employed for a precision approach runway category I shall have as its objective that, during any period of category I operations, all approach and runway lights are serviceable and that, in any event, at least 85 per cent of the lights are serviceable in each of the following:
 - (i) precision approach category I lighting system;
 - (ii) runway threshold lights;
 - (iii) runway edge lights; and
 - (iv) runway end lights

In order to provide continuity of guidance an unserviceable light shall not be permitted adjacent to another unserviceable light unless the light spacing is significantly less than that specified.

Note. — In barrettes and crossbars, guidance is not lost by having two adjacent unserviceable lights.

- (10) The system of preventive maintenance employed for a runway meant for take-off in runway visual range conditions less than a value of 550 m shall have as its objective that, during any period of operations, all runway lights are serviceable and that in any event:
 - (i) at least 95 per cent of the lights are serviceable in the runway center line lights (where provided) and in the runway edge lights; and
 - (ii) at least 75 per cent of the lights are serviceable in the runway end lights.

In order to provide continuity of guidance, an unserviceable light shall not be permitted adjacent to another unserviceable light.

- (11) The system of preventive maintenance employed for a runway meant for take-off in runway visual range conditions of a value of 550 m or greater shall have as its objective that, during any period of operations, all runway lights are serviceable and that, in any event, at least 85 per cent of the lights are serviceable in the runway edge lights and runway end lights. In order to provide continuity of guidance, an unserviceable light shall not be permitted adjacent to another unserviceable light.
- (12) During low visibility procedures the appropriate authority shall restrict construction or maintenance activities in the proximity of aerodrome electrical systems.

APPENDIX 1: COLORS FOR AERONAUTICAL GROUND LIGHTS, MARKINGS, SIGNS AND PANELS

1. General

Introductory Note.— *The following specifications define the chromaticity limits of colors to be used for aeronautical ground lights, markings, signs and panels. The specifications are in accord with the 1983 specifications of the International Commission on Illumination (CIE), except for the color orange in Figure A1-2.*

It is not possible to establish specifications for colors such that there is no possibility of confusion. For reasonably certain recognition, it is important that the eye illumination be well above the threshold of perception, that the color not be greatly modified by selective atmospheric attenuations and that the observer's color vision be adequate. There is also a risk of confusion of color at an extremely high level of eye illumination such as may be obtained from a high-intensity source at very close range. Experience indicates that satisfactory recognition can be achieved if due attention is given to these factors.

*The chromaticities are expressed in terms of the standard observer and coordinate system adopted by the International Commission on Illumination (CIE) at its Eighth Session at Cambridge, England, in 1931.**

The chromaticities for solid state lighting (e.g. LED) are based upon the boundaries given in the standard S 004/E-2001 of the International Commission on Illumination (CIE), except for the blue boundary of white.

2. Colors for aeronautical ground lights

2.1 Chromaticities for lights having filament-type light sources

- 2.1.1 The chromaticities of aeronautical ground lights with filament-type light sources shall be within the following boundaries:

CIE Equations (see Figure A1-1a):

- a) Red
- | | |
|-----------------|--|
| Purple boundary | $y = 0.980 - x$ |
| Yellow boundary | $y = 0.335$, except for visual approach slope indicator systems |
| Yellow boundary | $y = 0.320$, for visual approach slope indicator systems |

Note.— See 5.3.5.15 and 5.3.5.31.

- b) Yellow
- | | |
|----------------|----------------------|
| Red boundary | $y = 0.382$ |
| White boundary | $y = 0.790 - 0.667x$ |
| Green boundary | $y = x - 0.120$ |

c) Green

Yellow boundary	$x = 0.360 - 0.080y$
White boundary	$x = 0.650y$
Blue boundary	$y = 0.390 - 0.171x$

d) Blue

Green boundary	$y = 0.805x + 0.065$
White boundary	$y = 0.400 - x$
Purple boundary	$x = 0.600y + 0.133$

e) White

Yellow boundary	$x = 0.500$
Blue boundary	$x = 0.285$
Green boundary	$y = 0.440$ and $y = 0.150 + 0.640x$
Purple boundary	$y = 0.050 + 0.750x$ and $y = 0.382$

f) Variable white

Yellow boundary	$x = 0.255 + 0.750y$ and $y = 0.790 - 0.667x$
Blue boundary	$x = 0.285$
Green boundary	$y = 0.440$ and $y = 0.150 + 0.640x$
Purple boundary	$y = 0.050 + 0.750x$ and $y = 0.382$

Note.— Guidance on chromaticity changes resulting from the effect of temperature on filtering elements is given in the Aerodrome Design Manual (Doc 9157), Part 4.

- 2.1.2 Where dimming is not required, or where observers with defective color vision must be able to determine the color of the light, green signals should be within the following boundaries:

<i>Yellow boundary</i>	$y = 0.726 - 0.726x$
<i>White boundary</i>	$x = 0.650y$
<i>Blue boundary</i>	$y = 0.390 - 0.171x$

Note.— Where the color signal is to be seen from long range, it has been the practice to use colors within the boundaries of 2.1.2.

- 2.1.3 Where increased certainty of recognition from white is more important than maximum visual range, green signals should be within the following boundaries:

<i>Yellow boundary</i>	$y = 0.726 - 0.726x$
<i>White boundary</i>	$x = 0.625y - 0.041$
<i>Blue boundary</i>	$y = 0.390 - 0.171x$

2.2 Discrimination between lights having filament-type sources

- 2.2.1 If there is a requirement to discriminate yellow and white from each other, they should be displayed in close proximity of time or space as, for example, by being flashed successively from the same beacon.

- 2.2.2 If there is a requirement to discriminate yellow from green and/or white, as for example on exit taxiway center line lights, the y coordinates of the yellow light should not exceed a value of 0.40.

Note.— The limits of white have been based on the assumption that they will be used in situations in which the characteristics (color temperature) of the light source will be substantially constant.

- 2.2.3 The color variable white is intended to be used only for lights that are to be varied in intensity, e.g. to avoid dazzling. If this color is to be discriminated from yellow, the lights should be so designed and operated that:

*5.the x coordinate of the yellow is at least 0.050 greater than the x coordinate of the white;
and*

6.the disposition of the lights will be such that the yellow lights are displayed simultaneously and in close proximity to the white lights.

2.3 Chromaticities for lights having a solid state light source

- 2.3.1 The chromaticities of aeronautical ground lights with solid state light sources, e.g. LEDs, shall be within the following boundaries:

CIE Equations (see Figure A1-1b):

a) Red

Purple boundary	$y = 0.980 - x$
Yellow boundary	$y = 0.335$, except for visual approach slope indicator systems
Yellow boundary	$y = 0.320$, for visual approach slope indicator systems

Note.— See 5.3.5.15 and 5.3.5.31.

b) Yellow

Red boundary	$y = 0.387$
White boundary	$y = 0.980 - x$
Green boundary	$y = 0.727x + 0.054$

c) Green (also refer to 2.3.2 and 2.3.3)

Yellow boundary	$x = 0.310$
White boundary	$x = 0.625y - 0.041$
Blue boundary	$y = 0.400$

d) Blue

Green boundary	$y = 1.141x - 0.037$
White boundary	$y = 0.400 - y$
Purple boundary	$x = 0.134 + 0.590y$

e) White

Yellow boundary	$x = 0.440$
-----------------	-------------

Blue boundary	$x = 0.320$
Green boundary	$y = 0.150 + 0.643x$
Purple boundary	$y = 0.050 + 0.757x$

7. Variable white

The boundaries of variable white for solid state light sources are those of e) White above.

- 2.3.2 Where observers with defective color vision must be able to determine the color of the light, green signals should be within the following boundaries:

Yellow boundary	$y = 0.726 - 0.726x$
White boundary	$x = 0.625y - 0.041$
Blue boundary	$y = 0.400$

- 2.3.3 In order to avoid a large variation of shades of green, if colors within the boundaries below are selected, colors within the boundaries of 2.3.2 should not be used.

Yellow boundary	$x = 0.310$
White boundary	$x = 0.625y - 0.041$
Blue boundary	$y = 0.726 - 0.726x$

2.4 Color measurement for filament-type and solid state-type light sources

- 2.4.1 The color of aeronautical ground lights shall be verified as being within the boundaries specified in Figure A1-1a or A1-1b, as appropriate, by measurement at five points within the area limited by the innermost isocandela curve (isocandela diagrams in Appendix 2 refer), with operation at rated current or voltage. In the case of elliptical or circular isocandela curves, the color measurements shall be taken at the center and at the horizontal and vertical limits. In the case of rectangular isocandela curves, the color measurements shall be taken at the center and the limits of the diagonals (corners). In addition, the color of the light shall be checked at the outermost isocandela curve to ensure that there is no color shift that might cause signal confusion to the pilot.

Note 1.— For the outermost isocandela curve, a measurement of color coordinates should be made and recorded for review and judgement of acceptability by the State.

Note 2.— Certain light units may have application so that they may be viewed and used by pilots from directions beyond that of the outermost isocandela curve (e.g. stop bar lights at significantly wide runway-holding positions). In such instances, the State should assess the actual application and if necessary require a check of color shift at angular ranges beyond the outermost curve.

- 2.4.2 In the case of visual approach slope indicator systems and other light units having a color transition sector, the color shall be measured at points in accordance with 2.4.1, except that the color areas shall be treated separately and no point shall be within 0.5 degrees of the transition sector.

3. Colors for markings, signs and panels

Note 1.— The specifications of surface colors given below apply only to freshly colored surfaces. Colors used for markings, signs and panels usually change with time and therefore require renewal

Note 2.— Guidance on surface colors is contained in the CIE document entitled Recommendations for Surface Colors for Visual Signalling — Publication No. 39-2 (TC-106) 1983.

Note 3.— The specifications recommended in 3.4 for trans illuminated panels are interim in nature and are based on the CIE specifications for trans illuminated signs. It is intended that these specifications will be reviewed and updated as and when CIE develops specifications for trans illuminated panels.

- 3.1 The chromaticities and luminance factors of ordinary colors, colors of retro reflective materials and colors of trans illuminated (internally illuminated) signs and panels shall be determined under the following standard conditions:
1. angle of illumination: 45°;
 2. direction of view: perpendicular to surface; and
 3. illuminant: CIE standard illuminant D₆₅.
- 3.2 The chromaticity and luminance factors of ordinary colors for markings and externally illuminated signs and panels should be within the following boundaries when determined under standard conditions.

CIE Equations (see Figure AI-2):

- a) Red
- | | |
|------------------|----------------------|
| Purple boundary | $y = 0.345 - 0.051x$ |
| White boundary | $y = 0.910 - x$ |
| Orange boundary | $y = 0.314 + 0.047x$ |
| Luminance factor | $\beta = 0.07$ (mnm) |
- b) Orange
- | | |
|------------------|----------------------|
| Red boundary | $y = 0.285 + 0.100x$ |
| White boundary | $y = 0.940 - x$ |
| Yellow boundary | $y = 0.250 + 0.220x$ |
| Luminance factor | $\beta = 0.20$ (mnm) |
- c) Yellow
- | | |
|------------------|----------------------|
| Orange boundary | $y = 0.108 + 0.707x$ |
| White boundary | $y = 0.910 - x$ |
| Green boundary | $y = 1.35x - 0.093$ |
| Luminance factor | $\beta = 0.45$ (mnm) |
- d) White
- | | |
|------------------|----------------------|
| Purple boundary | $y = 0.010 + x$ |
| Blue boundary | $y = 0.610 - x$ |
| Green boundary | $y = 0.030 + x$ |
| Yellow boundary | $y = 0.710 - x$ |
| Luminance factor | $\beta = 0.75$ (mnm) |
- e) Black
- | | |
|-----------------|-----------------|
| Purple boundary | $y = x - 0.030$ |
|-----------------|-----------------|

Blue boundary	$y = 0.570 - x$
Green boundary	$y = 0.050 + x$
Yellow boundary	$y = 0.740 - x$
Luminance factor	$\beta = 0.03$ (max)
f) Yellowish green	
Green boundary	$y = 1.317x + 0.4$
White boundary	$y = 0.910 - x$
Yellow boundary	$y = 0.867x + 0.4$
g) Green	
Yellow boundary	$x = 0.313$
White boundary	$y = 0.243 + 0.670x$
Blue boundary	$y = 0.493 - 0.524x$
Luminance factor	$\beta = 0.10$ (mnm)

Note.— The small separation between surface red and surface orange is not sufficient to ensure the distinction of these colors when seen separately.

3.3 The chromaticity and luminance factors of colors of retro reflective materials for markings, signs and panels should be within the following boundaries when determined under standard conditions.

CIE Equations (see Figure A1-3):

a) Red	
Purple boundary	$y = 0.345 - 0.051x$
White boundary	$y = 0.910 - x$
Orange boundary	$y = 0.314 + 0.047x$
Luminance factor	$\beta = 0.03$ (mnm)
b) Orange	
Red boundary	$y = 0.265 + 0.205x$
White boundary	$y = 0.910 - x$
Yellow boundary	$y = 0.207 + 0.390x$
Luminance factor	$\beta = 0.14$ (mnm)
c) Yellow	
Orange boundary	$y = 0.160 + 0.540x$
White boundary	$y = 0.910 - x$
Green boundary	$y = 1.35x - 0.093$
Luminance factor	$\beta = 0.16$ (mnm)
d) White	
Purple boundary	$y = x$
Blue boundary	$y = 0.610 - x$
Green boundary	$y = 0.040 + x$
Yellow boundary	$y = 0.710 - x$
Luminance factor	$\beta = 0.27$ (mnm)
e) Blue	
Green boundary	$y = 0.118 + 0.675x$

White boundary	$y = 0.370 - x$
Purple boundary	$y = 1.65x - 0.187$
Luminance factor	$\beta = 0.01$ (mnm)

f) Green

Yellow boundary	$y = 0.711 - 1.22x$
White boundary	$y = 0.243 + 0.670x$
Blue boundary	$y = 0.405 - 0.243x$
Luminance factor	$\beta = 0.03$ (mnm)

3.4 The chromaticity and luminance factors of colors for luminescent or trans illuminated (internally illuminated) signs and panels should be within the following boundaries when determined under standard conditions.

CIE Equations (see Figure A1-4):

a) Red

Purple boundary	$y = 0.345 - 0.051x$
White boundary	$y = 0.910 - x$
Orange boundary	$y = 0.314 + 0.047x$
Luminance factor	$\beta = 0.07$ (mnm)
(day condition)	
Relative luminance	5% (mnm)
to white (night	20% (max)
condition)	

b) Yellow

Orange boundary	$y = 0.108 + 0.707x$
White boundary	$y = 0.910 - x$
Green boundary	$y = 1.35x - 0.093$
Luminance factor	$\beta = 0.45$ (mnm)
(day condition)	
Relative luminance	30% (mnm)
to white (night	80% (max)
condition)	

c) White

Purple boundary	$y = 0.010 + x$
Blue boundary	$y = 0.610 - x$
Green boundary	$y = 0.030 + x$
Yellow boundary	$y = 0.710 - x$
Luminance factor	$\beta = 0.75$ (mnm)
(day condition)	

Relative luminance
to white (night
condition) 100%

d) Black

Purple boundary	$y = x - 0.030$
Blue boundary	$y = 0.570 - x$
Green boundary	$y = 0.050 + x$

Yellow boundary $y = 0.740 - x$
 Luminance factor $\beta = 0.03$ (max)
 (day condition)
 Relative luminance 0% (min)
 to white (night 2% (max)
 condition)

e) Green

Yellow boundary : $x = 0.313$
 White boundary: $y = 0.243 + 0.670x$
 Blue boundary: $y = 0.493 - 0.524x$
 Luminance factor: $\beta = 0.10$ minimum (day conditions)
 Relative luminance: 5% (minimum)
 to white (night 30% (maximum)
 conditions)




Figure A1-1a. Colours for aeronautical ground lights (filament-type lamps)




Figure A1-1b. Colours for aeronautical ground lights (solid state lighting)




Figure A1-1b. Colours for aeronautical ground lights (solid state lighting)




Figure A1-3. Colours of retroreflective materials for markings, signs and panels





Figure A1-4. Colours of luminescent or transilluminated (internally illuminated) signs and panels

APPENDIX 2: AERONAUTICAL GROUND LIGHT CHARACTERISTICS



Notes:

1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$


a	10	14	15
b	5.5	6.5	8.5

2. Vertical setting angles of the lights shall be such that the following vertical coverage of the main beam will be met:

distance from threshold	vertical main beam coverage
threshold to 315 m	0° — 11°
316 m to 475 m	0.5° — 11.5°
476 m to 640 m	1.5° — 12.5°
641 m and beyond	2.5° — 13.5° (as illustrated above)

3. Lights in crossbars beyond 22.5 m from the centre line shall be toed-in 2 degrees. All other lights shall be aligned parallel to the centre line of the runway.
4. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-1. Isocandela diagram for approach center line light and crossbars (white light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.5	7.5	9.0
b	4.5	6.0	8.5

2. Toe-in 3.5 degrees
3. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-2. Isocandela diagram for approach side row light (red light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.5	7.5	9.0
b	4.5	6.0	8.5

2. Toe-in 3.5 degrees
3. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-3. Isocandela diagram for threshold light (green light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	7.0	11.5	16.5
b	5.0	6.0	8.0

2. Toe-in 2 degrees
3. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-4. Isocandela diagram for threshold wing bar light (green light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.0	7.0	8.5
b	3.5	6.0	8.5

2. Toe-in 4 degrees
3. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-5. Isocandela diagram for touchdown zone light (white light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.0	7.0	8.5
b	3.5	6.0	8.5

2. For red light, multiply values by 0.15.
3. For yellow light, multiply values by 0.40.
4. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-6. Isocandela diagram for runway center line light with 30 m longitudinal spacing (white light) and rapid exit taxiway indicator light (yellow light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.0	7.0	8.5
b	4.5	8.5	10

2. For red light, multiply values by 0.15.
3. For yellow light, multiply values by 0.40.
4. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-7. Isocandela diagram for runway center line light with 15 m longitudinal spacing (white light) and rapid exit taxiway indicator light (yellow light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	6.0	7.5	9.0
b	2.25	5.0	6.5

2. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-8. Isocandela diagram for runway end light (red light)



Notes:


1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.5	7.5	9.0
b	3.5	6.0	8.5

2. Toe-in 3.5 degrees
3. For red light, multiply values by 0.15.
4. For yellow light, multiply values by 0.40.
5. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-9. Isocandela diagram for runway edge light where width of runway is 45 m (white light)



Notes:

1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	6.5	8.5	10.0
b	3.5	6.0	8.5

2. Toe-in 4.5 degrees
3. For red light, multiply values by 0.15.
4. For yellow light, multiply values by 0.40.
5. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-10. Isocandela diagram for runway edge light where width of runway is 60 m (white light)





Figure A2-11. Grid points to be used for the calculation of average intensity of approach and runway light

Collective notes to Figures A2-1 to A2-11 and A2-26

1. The ellipses in each figure are symmetrical about the common vertical and horizontal axes.
2. Figures A2-1 to A2-10, as well as Figure A2-26, show the minimum allowable light intensities. The average intensity of the main beam is calculated by establishing grid points as shown in Figure A2-11 and using the intensity value measures at all grid points located within and on the perimeter of the ellipse representing the main beam. The average value is the arithmetic average of light intensities measured at all considered grid points.
3. No deviations are acceptable in the main beam pattern when the lighting fixture is properly aimed.
4. Average intensity ratio. The ratio between the average intensity within the ellipse defining the main beam of atypical new light and the average light intensity of the main beam of a new runway edge light shall be as follows:

Figure A2-1	Approach centre line and crossbars	1.5 to 2.0 (white light)
Figure A2-2	Approach side row	0.5 to 1.0 (red light)
Figure A2-3	Threshold	1.0 to 1.5 (green light)
Figure A2-4	Threshold wing bar	1.0 to 1.5 (green light)
Figure A2-5	Touchdown zone	0.5 to 1.0 (white light)
Figure A2-6	Runway centre line (longitudinal spacing 30 m)	0.5 to 1.0 (white light)
Figure A2-7	Runway centre line (longitudinal spacing 15 m)	0.5 to 1.0 for CAT III (white light)
		0.25 to 0.5 for CAT I, II (white light)
Figure A2-8	Runway end	0.25 to 0.5 (red light)
Figure A2-9	Runway edge (45 m runway width)	1.0 (white light)
Figure A2-10	Runway edge (60 m runway width)	1.0 (white light)


5. The beam coverages in the figures provide the necessary guidance for approaches down to an RVR of the order of 150 m and take-offs down to an RVR of the order of 100 m.
6. Horizontal angles are measured with respect to the vertical plane through the runway center line. For lights other than center line lights, the direction towards the runway center line is considered positive. Vertical angles are measured with respect to the horizontal plane.
7. Where, for approach center line lights and crossbars and for approach side row lights, inset lights are used in lieu of elevated lights, e.g. on a runway with a displaced threshold, the intensity requirements can be met by installing two or three fittings (lower intensity) at each position.
8. The importance of adequate maintenance cannot be overemphasized. The average intensity should never fall to a value less than 50 per cent of the value shown in the figures, and it should be the aim of airport authorities to maintain a level of light output close to the specified minimum average intensity.
9. The light unit shall be installed so that the main beam is aligned within one-half degree of the specified requirement.



Note:

1. These beam coverages allow for displacement of the cockpit from the center line up to distances of the order of 12 m and are intended for use before and after curves.
2. See collective notes for Figures A2-12 to A2-21.
3. Increased intensities for enhanced rapid exit taxiway center line lights as recommended in 5.3.16.9 are four times the respective intensities in the figure (i.e. 800 cd for minimum average main beam).


Figure A2-12. Isocandela diagram for taxiway center line (15 m spacing), RELs, no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of less than a value of 350 m where large offsets can occur and for low-intensity runway guard lights, Configuration B



Note:

1. These beam coverages are generally satisfactory and cater for a normal displacement of the cockpit from the center line of approximately 3 m.
2. See collective notes for Figures A2-12 to A2-21.


Figure A2-13. Isocandela diagram for taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of less than a value of 350m



Note:

1. Lights on curves to be toed-in 15.75 degrees with respect to the tangent of the curve. This does not apply to runway entrance lights (RELs)
2. Increased intensities for RELs shall be twice the specified intensities, i.e., minimum 20 cd, main beam minimum 100 cd and minimum average 200 cd.
3. See collective notes for Figures A2-12 to A2-21.


Figure A2-14. Isocandela diagram for taxiway center line (7.5 m spacing), RELs, no-entry bar and stop bar lights in curved sections intended for use in runway visual range conditions of less than a value of 350m



Note:

1. At locations where high background luminance is usual and where deterioration of light output resulting from dust, snow and local contamination is a significant factor, the cd-values should be multiplied by 2.5.
2. Where omnidirectional lights are used they shall comply with the vertical beam requirements in this figure.
3. See collective notes for Figures A2-12 to A2-21.


Figure A2-15. Isocandela diagram for taxiway center line (30 m, 60 m spacing), no-entry bar and stop bar lights in straight sections intended for use in runway visual range conditions of 350 m or greater



Notes:

1. Lights on curves to be toed-in 15.75 degrees with respect to the tangent of the curve.
2. At locations where high background luminance is usual and where deterioration of light output resulting from dust, snow and local contamination is a significant factor, the cd-values should be multiplied by 2.5.
3. These beam coverages allow for displacement of the cockpit from the center line up to distances of the order of 12 m as could occur at the end of curves.
4. See collective notes for Figures A2-12 to A2-21.

Figure A2-16. Isocandela diagram for taxiway center line (7.5 m, 15 m, 30 m spacing), no-entry bar and stop bar lights in curved sections intended for use in runway visual range conditions of 350 m or greater.




Curve	a	b	c	d	e
Intensity (cd)	8	20	100	450	1 800

Notes:

1. These beam coverages allow for displacement of the cockpit from the centre line up to distances of the order of 12 m and are intended for use before and after curves.
2. See collective notes for Figures A2-12 to A2-21.

Figure A2-17. Isocandela diagram for high-intensity taxiway center line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required and where large offsets can occur




Curve	a	b	c	d	e
Intensity (cd)	8	20	100	450	1 800

Notes:

1. These beam coverages are generally satisfactory and cater for a normal displacement of the cockpit corresponding to the outer main gear wheel on the taxiway edge.
2. See collective notes for Figures A2-12 to A2-21.

Figure A2-18. Isocandela diagram for high-intensity taxiway centre line (15 m spacing), no-entry bar and stop bar lights in straight sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required




Curve	a	b	c	d
Intensity (cd)	8	100	200	400

Notes:

1. Lights on curves to be toed-in 17 degrees with respect to the tangent of the curve.
2. See collective notes for Figures A2-12 to A2-21.

Figure A2-19. Isocandela diagram for high-intensity taxiway centre line (7.5 m spacing), no-entry bar and stop bar lights in curved sections intended for use in an advanced surface movement guidance and control system where higher light intensities are required



Notes:

1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed for incandescent lamps.
2. See collective notes for Figures A2-12 to A2-21.

Figure A2-20. Isocandela diagram for high-intensity runway guard lights, Configuration B




Figure A2-21. Grid points to be used for calculation of average intensity of taxiway centre line and stop bar lights

Collective notes to Figures A2-12 to A2-21

1. The intensities specified in Figures A2-12 to A2-20 are in green and yellow light for taxiway center line lights, yellow light for runway guard lights and red light for stop bar lights.
2. Figures A2-12 to A2-20 show the minimum allowable light intensities. The average intensity of the main beam is calculated by establishing grid points as shown in Figure A2-21 and using the intensity values measured at all grid points located within and on the perimeter of the rectangle representing the main beam. The average value is the arithmetic average of the light intensities measured at all considered grid points.
3. No deviations are acceptable in the main beam or in the innermost beam, as applicable, when the lighting fixture is properly aimed.
4. Horizontal angles are measured with respect to the vertical plane through the taxiway center line except on curves where they are measured with respect to the tangent to the curve.
5. Vertical angles are measured from the longitudinal slope of the taxiway surface.
6. The importance of adequate maintenance cannot be overemphasized. The intensity, either average where applicable or as specified on the corresponding isocandela curves, should never fall to a value less than 50 per cent of the value shown in the figures, and it should be the aim of airport authorities to maintain a level of light output close to the specified minimum average intensity.
7. The light unit shall be installed so that the main beam or the innermost beam, as applicable, is aligned within one half degree of the specified requirement






Figure A2-22. Light intensity distribution of T-VASIS and AT-VASIS



Notes:

1. These curves are for minimum intensities in red light.
2. The intensity value in the white sector of the beam is no less than 2 and may be as high as 6.5 times the corresponding intensity in the red sector.
3. The intensity values shown in brackets are for APAPI.


Figure A2-23. Light intensity distribution of PAPI and APAPI



Notes:

1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed for incandescent lamps.
2. The intensities specified are in yellow light.


Figure A2-24. Isocandela diagram for each light in low-intensity runway guard lights, Configuration A



Notes:

1. Although the lights flash in normal operation, the light intensity is specified as if the lights were fixed for incandescent lamps.
2. The intensities specified are in yellow light.

Figure A2-25. Isocandela diagram for each light in high-intensity runway guard lights, Configuration A



Notes:

1. Curves calculated on formula

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

a	5.0	7.0
b	4.5	8.5

2. See collective notes for Figures A2-1 to A2-11 and A2-26.

Figure A2-26. Isocandela diagram for take-off and hold lights (THL) (red light)

APPENDIX 3: MANDATORY INSTRUCTION MARKINGS AND INFORMATION MARKINGS

Note 1.— See Sections 13.1.5, paragraphs 5.2.16 and 5.2.17, for specifications on the application, location and characteristics of mandatory instruction markings and information markings.

Note 2.— This appendix details the form and proportions of the letters, numbers and symbols of mandatory instruction markings and information markings on a grid.

Note 3.— The mandatory instruction markings and information markings on pavements are formed as if shadowed (i.e., stretched) from the characters of an equivalent elevated sign by a factor of 2.5 as shown in Figure A3-1. The shadowing, however, only affects the vertical dimension. Therefore, the spacing of characters for pavement marking is obtained by first determining the equivalent elevated sign character height and then proportioning from the spacing values given in Table A4-1.

For example, in the case of the runway designator “10” which is to have a height of 4 000 mm (H_{ps}), the equivalent elevated sign character height is $4\ 000/2.5=1\ 600$ mm (H_{es}). Table A4-1(b) indicates numeral to numeral code 1 and from Table A4-1(c) this code has a dimension of 96 mm, for a character height of 400 mm. The pavement marking spacing for “10” is then $(1\ 600/400)*96=384$ mm.






Figure A3-1


APP 3-1




APP 3-2



APP 3-3



APP 3-4



APP 3-5

APPENDIX 4. REQUIREMENTS CONCERNING DESIGN OF

TAXIING GUIDANCE SIGNS

Note.— See Chapter 5, Section 5.4, for specifications on the application, location and characteristics of signs.

1. Inscription heights shall conform to the following tabulation.

Runway code number	Minimum character height		
	Mandatory instruction sign	Information sign	
		Runway exit and runway vacated signs	Other signs
1 or 2	300 mm	300 mm	200 mm
3 or 4	400 mm	400 mm	300 mm

Note.— Where a taxiway location sign is installed in conjunction with a runway designation sign (see 5.4.3.22), the character size shall be that specified for mandatory instruction signs.

2. Arrow dimensions shall be as follows:

<i>Legend height</i>	<i>Stroke</i>
200 mm	32 mm
300 mm	48 mm
400 mm	64 mm

3. Stroke width for single letter shall be as follows:

<i>Legend height</i>	<i>Stroke</i>
200 mm	32 mm
300 mm	48 mm
400 mm	64 mm

4. Sign luminance shall be as follows:

- a) Where operations are conducted in runway visual range conditions less than a value of 800 m, average sign luminance shall be at least:

Red	10 cd/m ²
Yellow	50 cd/m ²
White	100 cd/m ²

Note.— In runway visual range conditions less than a value of 400 m, there will be some degradation in the performance of signs.

5. The luminance ratio between red and white elements of a mandatory sign shall be between 1:5 and 1:10.
6. The average luminance of the sign is calculated by establishing grid points as shown in Figure A4-1 and using the luminance values measured at all grid points located within the rectangle representing the sign.
7. The average value is the arithmetic average of the luminance values measured at all considered grid points.

Note.— Guidance on measuring the average luminance of a sign is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

8. The ratio between luminance values of adjacent grid points shall not exceed 1.5:1. For areas on the sign face where the grid spacing is 7.5 cm, the ratio between luminance values of adjacent grid points shall not exceed 1.25:1. The ratio between the maximum and minimum luminance value over the whole sign face shall not exceed 5:1.
9. The forms of characters, i.e. letters, numbers, arrows and symbols, shall conform to those shown in Figure A4-2.
The width of characters and the space between individual characters shall be determined as indicated in Table A4-1.

10. The face height of signs shall be as follows:

<i>Legend height</i>	<i>Face height (min)</i>
200 mm	400 mm
300 mm	600 mm
400 mm	800 mm

11. The face width of signs shall be determined using Figure A4-4 except that, where a mandatory instruction sign is provided on one side of a taxiway only, the face width shall not be less than:


- a) 1.94 m where the code number is 3 or 4; and
- b) 1.46 m where the code number is 1 or 2.

Note.— Additional guidance on determining the face width of a sign is contained in the Aerodrome Design Manual (Doc 9157), Part 4.

12. Borders

- a) The black vertical delineator between adjacent direction signs should have a width of approximately 0.7 of the stroke width.
- b) The yellow border on a stand-alone location sign should be approximately 0.5 stroke width.

13. The colors of signs shall be in accordance with the appropriate specifications in Appendix 1.



Note 1.— The average luminance of a sign is calculated by establishing grid points on a sign face showing typical inscriptions and a background of the appropriate color (red for mandatory instruction signs and yellow for direction and destination signs) as follows:

- a) Starting at the top left corner of the sign face, establish a reference grid point at 7.5 cm from the left edge and the top of the sign face.
- b) Create a grid of 15 cm spacing horizontally and vertically from the reference grid point. Grid points within 7.5 cm of the edge of the sign face shall be excluded.
- c) Where the last point in a row/column of grid points is located between 22.5 cm and 15 cm from the edge of the sign face (but not inclusive), an additional point shall be added 7.5 cm from this point.
- d) Where a grid point falls on the boundary of a character and the background, the grid point shall be slightly shifted to be completely outside the character.

Note 2.— Additional grid points may be required to ensure that each character includes at least five evenly spaced grid points.

Note 3.— Where one unit includes two types of signs, a separate grid shall be established for each type.

Figure A4-1. Grid points for calculating average luminance of a sign




Figure A4-2. Forms of characters




Figure A4-2. (cont.)




Figure A4-2. (cont.)




Figure A4-2. (cont.)





Figure A4-2. (cont.)




Arrow, dot and dash


Note 1.—The arrow stroke width, diameter of the dot, and both width and length of the dash shall be proportioned to the character stroke widths.

Note 2.— The dimensions of the arrow shall remain constant for a particular sign size, regardless of orientation.

Figure A4-2.



Runway vacated sign (with typical location sign)



NO ENTRY sign

Figure A4-3. Runway vacated and NO ENTRY signs




Figure A4-4. Sign dimensions

Amended 14/10/2020

Table A4-1. Letter and numeral widths and space between letters or numerals

a) Letter to letter code number			
Preceding Letter	Following Letter		
	B, D, E, F, H, I, K, L, M, N, P, R, U	C, G, O, Q, S, X, Z	A, J, T, V, W, Y
	Code number		
A	2	2	4
B	1	2	2
C	2	2	3
D	1	2	2
E	2	2	3
F	2	2	3
G	1	2	2
H	1	1	2
I	1	1	2
J	1	1	2
K	2	2	3
L	2	2	4
M	1	1	2
N	1	1	2
O	1	2	2
P	1	2	2
Q	1	2	2
R	1	2	2
S	1	2	2
T	2	2	4
U	1	1	2
V	2	2	4
W	2	2	4
X	2	2	3
Y	2	2	4
Z	2	2	3

b) Numeral to numeral code number			
Preceding Numeral	Following numeral		
	1, 5	2, 3, 6, 8, 9, 0	4, 7
	Code number		
1	1	1	2
2	1	2	2
3	1	2	2
4	2	2	4
5	1	2	2
6	1	2	2
7	2	2	4
8	1	2	2
9	1	2	2
0	1	2	2

c) Space between characters			
Code No.	Character height (mm)		
	200	300	400
	Space (mm)		
1	48	71	96
2	38	57	76
3	25	38	50
4	13	19	26


d) Width of letter			
Letter	Letter height (mm)		
	200	300	400
	Width (mm)		
A	170	255	340
B	137	205	274
C	137	205	274
D	137	205	274
E	124	186	248
F	124	186	248
G	137	205	274
H	137	205	274
I	32	48	64
J	127	190	254
K	140	210	280
L	124	186	248
M	157	236	314
N	137	205	274
O	143	214	286
P	137	205	274
Q	143	214	286
R	137	205	274
S	137	205	274
T	124	186	248
U	137	205	274
V	152	229	304
W	178	267	356
X	137	205	274
Y	171	257	342
Z	137	205	274

e) Width of numeral			
Numeral	Numeral height (mm)		
	200	300	400
	Width (mm)		
1	50	74	98
2	137	205	274
3	137	205	274
4	149	224	298
5	137	205	274
6	137	205	274
7	137	205	274
8	137	205	274
9	137	205	274
0	143	214	286

INSTRUCTIONS


1. To determine the proper SPACE between letters or numerals, obtain the code number from table a) or b) and enter table c) for that code number to the desired letter or numeral height.
2. The space between words or groups of characters forming an abbreviation or symbol should be equal to 0.5 to 0.75 of the height of the characters used except that where an arrow is located with a single character such as 'A →', the space may be reduced to not less than one quarter of the height of the character in order to provide a good visual balance.
3. Where the numeral follows a letter or vice versa use Code 1.
4. Where a hyphen, dot, or diagonal stroke follows a character or vice versa use Code 1.
5. For the intersection take-off sign, the height of the lower case "m" is 0.75 of the height of the preceding "0" (zero) and spaced from the preceding "0" at code 1 for the character height of the numerals.

APPENDIX 5: LOCATION OF LIGHTS ON OBSTACLES




Note.— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground level. If medium-intensity lighting is used, marking will also be required.

Figure A5-1. Medium-intensity flashing-white obstacle lighting system, Type A




Note.— For night-time use only.

Figure A5-2. Medium-intensity flashing-red obstacle lighting system, Type B




Note.— For night-time use only.

Figure A5-3. Medium-intensity fixed-red obstacle lighting system, Type C



Note.— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground el. If medium-intensity lighting is used, marking will also be required.

Figure A5-4. Medium-intensity dual obstacle lighting system, Type A/Type B



Note.— High-intensity obstacle lighting is recommended on structures with a height of more than 150 m above ground level. If medium-intensity lighting is used, marking will also be required.

Figure A5-5. Medium-intensity dual obstacle lighting system, Type A/Type C




Figure A5-6. High-intensity flashing-white obstacle lighting system, Type A




Figure AS-7. High-/medium-intensity dual obstacle lighting system, Type A/Type B




Figure A5-7. High-/medium-intensity dual obstacle lighting system, Type A/Type B




Figure A5-8. High-/medium-intensity dual obstacle lighting system, Type A/Type C